

TSWELOPELE LOCAL MUNICIPALITY

RETROFITTING OF 6 SEWER PUMP STATIONS, INSTALLATION OF INLINE GRINDERS AND REPAIRS TO WASTE WATER TREATMENT PLANT IN HOOPSTAD AND TIKWANA

CIDB GRADING: 6ME OR HIGHER TENDER NO. SCM/TSW/14/2025-2026.

CLOSING DATE: 01 DECEMBER 2025

CLOSING TIME: 12H00 ISSUED BY: PREPARED BY: **Muteo Consulting cc Tswelopele Local Municipality** Unit A3 Centurion P.O. Box 3 Close119 Gerhard Bultfontein Street 9670 0157 Tel: 051 853 1111 Tel: +27 12 664 6577 Fax: 051 853 1332 Fax: +27 86 672 0952 Email: Malokase.pmu@tswelopele.org Email: arinaon@muteo.co.za CSD No. CIDB Registration Number: Grade: Grade: Total price inclusive of Value added Tax: R

Amount in Words.....

CONTENTS

T1	TENDERING PROCEDURES	11
T1.1	TENDER NOTICE AND INVITATION TO TENDER	11
T1.2	TENDER DATA	14
T1.2.1	STANDARD CONDITIONS OF TENDER	14
T1.3	PREFERENTIAL PROCUREMENT REGULATIONS	32
T2	RETURNABLE DOCUMENTS	34
T2.1	LIST OF RETURNABLE DOCUMENTS	34
		55
C1	AGREEMENT AND CONTRACT DATA	
C1.1	FORM OF OFFER AND ACCEPTANCE	68
C1.2	CONTRACT DATA	72
C1.2.1	CONTRACT SPECIFIC DATA	72
C1.2.2	DATA PROVIDED BY THE CONTRACTOR	74
C1.2.3	EPWP SPECIFIC CONDITIONS OF CONTRACT	76
C1.3	BLASTING INDEMNITY	83
C1.4	HEALTH AND SAFETY CONTRACT: GENERAL INFORMATION	84
C1.4.1	HEALTH AND SAFETY CONTRACT BETWEEN EMPLOYER AND CONTRA	CTOR
	IN TERMS OF SECTION 37(2) OF THE OCCUPATIONAL HEALTH AND SA	
	ACT NO 85 OF 1993	
C1.4.2	OCCUPATIONAL HEALTH AND SAFETY INDEMNITY UNDERTAKING	
C1.5	INCLEMENT WEATHER	
C2	PRICING DATA	
C2.1	PRICING INSTRUCTIONS	
C2.2	BILL OF QUANTITIES	
C3	SCOPE OF WORK	110
C3.1	DESCRIPTION OF WORKS	_
C3.1.1	LOCATION OF WORKS	
C3.1.2	NATURE OF WORKS	
C3.1.3	SCOPE	111
C3.1.3.1	MECHANICAL SCOPE OF WORK	111
C3.1.3.2	CIVIL AND BUILDING SCOPE OF WORK	112
C3.1.3.3	ELECTRICAL, CONTROL AND INSTRUMENTATION SCOPE OF WORK	112
C3.1.4	TIME FOR COMPLETION	113
C3.1.5	GENERAL INFORMATION	113
C3.1.5.1	DRAWINGS	113
C3.1.5.2	POWER, WATER SUPPLY AND OTHER SERVICES	113
C3.1.5.3	CONTRACTOR'S CAMP SITE AND SECURITY	113
C3.1.5.4	ADDITIONAL REQUIREMENTS FOR CONSTRUCTION ACTIVITIES	113
C3.1.5.4.1	THE CONTRACTOR MAY NOT COMMENCE CONSTRUCTIONAL ACTIVITY BEFORE ADEQUATE PROVISION HAS BEEN MADE TO ACCOMMODATE TRAFFIC IN ACCORDANCE WITH THE REQUIREMENTS OF THIS DOCUMENTATION AND THE SOUTH AFRICAN ROAD TRAFFIC SIGNS MANUAL	ЛЕNT
C3.1.5.4.2	THE CONTRACTOR SHALL SUBMIT PROPOSALS IN CONNECTION WITH DIRECTIONAL SIGNS TO THE ENGINEER FOR APPROVAL	
C3.1.5.5	PROGRAMME REQUIREMENTS FOR CONSTRUCTION ACTIVITIES	114

C3.1.5.5.1	THE CONTRACTOR SHALL PROGRAMME HIS ACTIVITIES TO BE SUITERMS OF HIS RESOURCES TO COMPLETE THE CONTRACT INSIDE STIPULATED TIME PERIOD.	THE
C3.1.5.6	CONSTRUCTION IN CONFINED AREAS	114
C3.1.6	BARRICADING OF EXCAVATIONS	114
C3.1.7	CONTINUITY OF WATER SUPPLY	114
C3.1.8	ENGINEERING	116
C3.1.8.1	DESIGN	116
C3.1.8.1.1	THE EMPLOYER IS RESPONSIBLE FOR THE DESIGN OF THE PERMA WORKS AS REFLECTED IN THESE CONTRACT DOCUMENTS UNLES OTHERWISE STATED.	S
C3.1.8.1.2	THE CONTRACTOR IS RESPONSIBLE FOR THE DESIGN OF THE TEMWORKS AND THEIR COMPATIBILITY WITH THE PERMANENT WORKS	
C3.1.8.1.3	THE CONTRACTOR SHALL SUPPLY ALL DETAILS NECESSARY TO AS ENGINEER IN THE COMPILATION OF THE AS-BUILT DRAWINGS	
C3.1.8.1.4	EMPLOYER'S DESIGN	116
C3.1.8.1.5	CONTRACTOR'S DESIGN	116
C3.1.8.2	DESIGN PROCEDURES	116
C3.1.8.3	EQUIVALENCY OF STANDARDS AND CODES	116
C3.2	STANDARD SPECIFICATIONS	117
C3.2	STANDARD SPECIFICATIONS – MECHANICAL, ELECTRICAL, CONTRINSTRUMENTATION ENGINEERING	
C 3.3 TECH	INICAL SPECIFICATIONS – MECHANICAL WORKS	120
C3.3	TECHNICAL SPECIFICATIONS – MECHANICAL WORKS	121
C3.3.1	CONTRACTOR'S ESTABLISHMENT ON SITE AND GENERAL CHARGE	S 121
C3.3.1.1	SCOPE	121
C3.3.1.2	NOTICES, SIGNS AND ADVERTISEMENTS	121
C3.3.1.3	COMPLIANCE WITH OCCUPATIONAL HEALTH AND SAFETY ACT, ITS REGULATIONS AND THE EMPLOYER'S HEALTH AND SAFETY SPECI	FICATION
C3.3.1.4	COMPLIANCE WITH ENVIRONMENTAL MANAGEMENT PLAN	
C3.3.2	SCOPE	
C3.3.2.1	HOOPSTAAD COMMANDO	
C3.3.2.2	TIKWANA NO.1	122
C3.3.2.3	TIKWANA NO.2	122
C3.3.2.4	TIKWANA NO.3	123
C3.3.2.5	TIKWANA NO.5	123
C3.3.2.6	DEWATERING PUMPS FOR ALL STATIONS	123
C3.3.3.1	FLOW METERS	125
C3.3.3.2	ELECTROMAGNETIC FLOW METERS	125
C3.3.4	VALVE CONSTRUCTION AND OPERATIONAL REQUIREMENTS	125
C3.3.4.1	NON-RETURN VALVES	126
C3.3.4.2	WEDGE GATE VALVES (DELIVERY)	126
C3.3.4.3	WEDGE GATE VALVES (SUCTION SIDE OF PUMPS)	128
C3.3.4.4	PUMP CONTROL VALVES	

C3.3.5	SCHEDULE OF EQUIPMENT AND MATERIALS OFFERED (MECHANIC EQUIPMENT)	
C3.3.5.1	LOW LIFT PUMPS	
C 3.4 TECH	HNICAL SPECIFICATIONS – ELECTRICAL WORKS	
C3.4	TECHNICAL SPECIFICATIONS – ELECTRICAL, CONTROL AND INSTRUMENTATION WORKS	
C3.4.1	MINIATURE SUBSTATIONS	
C3.4.2	MOTOR CONTROL CENTRES AND DISTRIBUTION BOARDS	
C3.4.2.1	MCC 01: SCOPE	134
C3.4.2.2	MCC 02: CONDITIONS TO SERVICE	134
C3.4.2.3	MCC 03: STANDARDS AND TESTS	134
C3.4.2.4	MCC 04: CONSTRUCTION	134
C3.4.2.5	MCC 05: GENERAL REQUIREMENTS	136
C3.4.2.6	MCC 06: MOTOR STARTERS AND ACCESSORIES FOR SWITCHBOA	RDS137
C3.4.2.7	MCC 07: DANGER SIGNS	144
C3.4.2.8	MMC08: ELECTRONIC LEVEL CONTROL	144
C3.4.2.9	MCC 09: EMERGENCY STOP PUSH BUTTONS AND WEATHERPROC	
C3.4.2.10	MCC 10: EARTHING	145
C3.4.2.11	MCC 11: INFORMATION TO BE SUBMITTED WITH THE TENDERS IN OF THE 380 VOLT DISTRIBUTION BOARDS AND MOTOR CONTROL	BOARDS
C3.4.2.12	MCC 12: INFORMATION TO BE SUBMITTED BY THE SUCCESSFUL T	ENDERER
C3.4.2.13	MCC 13: INSPECTIONS AND TESTS	-
C3.4.2.14	MCC 14: TESTING OF DISTRIBUTION / MOTOR CONTROL BOARDS / MANUFACTURER'S WORKS	
C3.4.2.15	MCC 15: CONCRETE PLINTH FOR OUTDOOR STARTER PANELS AN PEDESTALS	
C3.4.2.16	MCC 16: INSTALLATION OF DISTRIBUTION BOARDS AND MOTOR C	
C3.4.2.17	MCC 17: TESTING AND COMMISSIONING OF DISTRIBUTION / MOTO CONTROL BOARDS AFTER INSTALLATION ON SITE	
C3.4.2.18	MCC 18: OPERATING AND MAINTENANCE INSTRUCTIONS	147
C3.4.2.19	MCC 19: MEASUREMENT AND PAYMENT	147
C3.4.3	ELECTRICAL CABLES	147
C3.4.4	ELECTRICAL DISTRIBUTION SYSTEM	148
C3.4.5	TELEMETRY SYSTEMS	150
C3.4.5.1	TMS1: SCOPE	150
C3.4.5.2	TMS 2: CONDITIONS TO SERVICE	150
C3.4.5.3	TMS 3: STANDARDS AND TESTS	151
C3.4.5.4	TMS 4: OUTSTATION CABINETS	151
C3.4.5.5	TMS 5: RADIO	151
C3.4.5.6	TMS 6: GSM AND GPRS MODULES	152
C3.4.5.7	TMS 7: SOLAR PANEL AND BATTERIES	152

C3.4.5.8	TMS 8: SURGE PROTECTION	. 152
C3.4.5.9	TMS 9: EARTHING	. 153
C3.4.5.10	TMS 10: SOLENOID VALVES	. 153
C3.4.5.11	TMS 11: NUMBERING OF CONDUCTOR ENDS	. 153
C3.4.5.12	TMS 12: CONNECTION OF CONDUCTOR ENDS	. 153
C3.4.5.13	TMS 13: MONITORING SYSTEM	. 153
C3.4.5.14	TMS 14: TRANSDUCERS AND INTERFACES	. 154
C3.4.5.15	TMS 15: CIRCUIT BOARDS AND COMPONENTS	. 154
C3.4.5.16	TMS 16: FAULT FINDING AND TEST FACILITIES	. 154
C3.4.5.17	TMS 17: MODULAR DESIGN	. 155
C3.4.5.18	TMS 18: ANTENNAE	. 155
C3.4.5.19	TMS 19: OUTSTATIONS HARDWARE	. 156
C3.4.5.20	TMS20: MEASUREMENT AND PAYMENT	. 157
C3.4.6	PROGRAMMABLE LOGIC CONTROLLERS	. 158
C3.4.6.1	PLC 1: SCOPE	. 158
C3.4.6.2	PLC 2: CONDITIONS TO SERVICE	. 158
C3.4.6.3	PLC 3: STANDARDS AND TESTS	. 158
C3.4.6.4	PLC 4: PROGRAMMABLE LOGIC CONTROLLER HARDWARE	. 159
C3.4.6.5	PLC 5:PLC GENERAL	
C3.4.6.6	PLC 6 :COMMUNICATION	. 162
C3.4.6.7	PLC 7 :PLC SOFTWARE DEVELOPMENT	. 165
C3.4.7	UN-INTERRUPTED POWER SUPPLY	. 171
C3.4.7.1	UPS01: UNINTERRUPTED POWER SUPPLY (UPS)	. 171
C3.4.7.2	UPS 02: CONSTRUCTION OF CUBICLES AND SWITCHBOARDS	
C3.4.7.3	UPS 03: INSTRUMENTATION AND CONTROLS	. 178
C3.4.7.4	UPS 04: ALARMS	. 178
C3.4.7.5	UPS 05: VENTILATION	. 179
C3.4.7.6	UPS 06: QUALITY ASSURANCE	. 179
C3.4.7.7	UPS 07: INSTRUCTION OF OPERATOR AND MANUALS	. 179
C3.4.7.8	UPS 08: TESTS	. 179
C3.4.8	SCHEDULE OF MATERIALS AND EQUIPMENT OFFERED	. 180
C3.4.8.1	MCC	. 180
C3.4.8.2	SENSORS	. 180
C3.4.8.3	LOW VOLTAGE CABLES AND TELEMETRY SYSTEMS	. 181
C3.4.8.4	PROGRAMMABLE LOGIC CONTROLLER (PLC)	. 182
C3.4.8.5	UN-INTERRUPTED POWER SUPPLY	. 182
C3.4.9	TESTING OF EQUIPMENT	. 182
C3.4.10	FACTORY ACCEPTANCE TESTING	. 182
C3.4.11	DRY COMMISSIONING	. 182
C3.4.12	WET COMMISSIONING	. 183
C3.4.13	TRIAL OPERATION PERIOD	. 184
C3.4.14	FINAL PERFORMANCE TEST AFTER COMPLETION OF TRIAL PERIOD	. 185
C3.4.15	GUARANTEES OF PERFORMANCE	. 185

C3.4.16	LIQUIDATED DAMAGES FOR FAILURES TO ACHIEVE GUARANTEES	185
C3.4.17	DEFECTS NOTIFICATION PERIOD	185
C3.4.18	TEST PLAN AND REPORTS	185
C3.4.19	ENGINEERING	186
C3.4.19.1	CONTRACTOR'S DESIGN	186
C3.4.19.2	DRAWINGS.	186
C 3.5 STAN	DARD AND TECHNICAL SPECIFICATIONS – CIVIL ENGINEERING WORK	S187
C3.5	STANDARD AND TECHNICAL SPECIFICATIONS - CIVIL ENGINEERING	WORKS
		188
C3.5.1	SCOPE	188
C3.5.2	STATUS	
C3.5.3	PORTION 1: THE WORKS	188
C3.5.4	PORTION 1: THE WORKS	190
C3.5.5	PORTION 2: VARIATIONS FROM STANDARD SPECIFICATIONS	194
C 3.6 HIV/A	DS REQUIREMENT	200
C3.6	HIV/AIDS REQUIREMENTS	201
C3.6.1	SCOPE	201
C3.6.2	DEFINITIONS AND ABBREVIATIONS	201
C3.6.2.1	DEFINITIONS	201
C3.6.2.2	ABBREVIATIONS	201
C3.6.3	BASIC METHOD REQUIREMENT	202
C3.6.4	HIV/ AIDS AWARENESS EDUCATION AND TRAINING	203
C3.6.5	ENSURING ACCESS TO HIV/AIDS TESTING AND COUNSELLING FACIL	ITIES
	AND TREATMENT OF SEXUALLY TRANSMITTED INFECTIONS (STI)	205
C3.6.6	APPOINTMENT OF AN HIV/AIDS AWARENESS CHAMPION	205
C3.6.7	MONITORING	206
C 3.7 OCCL	IPATION HEALTH AND SAFETY	207
C3.7	OCCUPATIONAL HEALTH AND SAFETY	208
C3.7.1	GENERAL	208
C3.7.1.1	TENDER DOCUMENT	208
C3.7.1.2	PRINCIPAL CONTRACTOR	208
C3.7.1.3	START OF CONSTRUCTION PHASE	208
C3.7.2	SUB-CONTRACTORS, SUPPLIERS & DESIGNERS	208
C3.7.2.1	LIAISON	210
C3.7.2.2	ADVICE	210
C3.7.2.3	UNDERTAKING BY PRINCIPAL CONTRACTOR AND SUB-CONTRACTOR APPOINTED BY THE PRINCIPAL CONTRACTOR	
C3.7.3	INFORMATION REQUIREMENTS	210
C3.7.3.1	GENERAL	210
C3.7.3.2	MANAGEMENT	210
C3.7.3.3	HAZARD IDENTIFICATION, RISK MANAGEMENT AND CONTROL	211
C3.7.3.4	HEALTH AND SAFETY PLAN	212
C3.7.3.5	PROGRAMME	212
C3 7 3 6	COST	213

C3.7.4	GENERAL SITE SAFETY	213
C3.7.4.1	SAFETY TRAINING & EDUCATION	213
C3.7.4.2	INDUCTION TRAINING	213
C3.7.4.3	INDUCTION TRAINING FOR SPECIFIED WORK	213
C3.7.4.4	RECORDING & REPORTING OF INJURIES	213
C3.7.4.5	FIRST AID	214
C3.7.4.6	FIRE PROTECTION AND PREVENTION	214
C3.7.4.7	SITE EMERGENCY PROCEDURES	215
C3.7.4.8	HOUSEKEEPING	215
C3.7.4.9	STACKING & STORAGE	215
C3.7.4.10	ILLUMINATION	216
C3.7.4.11	SANITATION / HYGIENE	216
C3.7.4.12	PERSONAL PROTECTIVE EQUIPMENT	216
C3.7.4.13	PERMIT TO WORK REQUIREMENTS	216
C3.7.4.14	LOCK-OUT	217
C3.7.4.15	MONTHLY HEALTH AND SAFETY AUDITS	217
C3.7.4.16	MANAGEMENT REVIEW	217
C3.7.4.17	PROVISION OF INFORMATION	217
C3.7.4.18	STOP THE EXECUTION OF CONSTRUCTION WORK	218
C3.7.4.19	HANDING OVER OF PROJECT HEALTH AND SAFETY FILE	219
C3.7.4.20	RECORDS AND RECORDS MANAGEMENT	219
C3.7.5	CHEMICAL HAZARDS	219
C3.7.6	SAFETY HAZARDS	219
C3.7.6.1	TOOLS	219
C3.7.6.2	PORTABLE ELECTRICAL TOOLS	219
C3.7.7	EXCAVATIONS	220
C3.7.8	FORMWORK & SUPPORT WORK	221
C3.7.9	CONSTRUCTION VEHICLES	221
C3.7.10	ELECTRICAL INSTALLATIONS	222
C3.7.11	USE & STORAGE OF FLAMMABLE LIQUIDS	223
C3.7.12	WELDING & CUTTING	223
C3.7.13	BLASTING & USE OF EXPLOSIVES	224
C3.7.13.1	SAFETY DISTANCES	224
C3.7.13.2	SUPERVISION OF EXPLOSIVES	224
C3.7.13.3	SAFE HANDLING OF EXPLOSIVES	224
C3.7.13.4	DANGEROUS AREAS	225
C3.7.14	VESSELS UNDER PRESSURE	226
C3.7.14.1	MANUFACTURER'S DATA PLATE	227
C3.7.14.2	PORTABLE GAS CONTAINERS	227
C3.7.14.3	HAND -HELD FIRE EXTINGUISHERS	227
C3.7.14.4	GAS FUEL USE, EQUIPMENT AND SYSTEMS	227
C3.7.14.5	INSPECTION AND TEST	227
C3.7.14.6	RECORDKEEPING	228

C3.7.14.7	MAINTENANCE	. 228
C3.7.15	PHYSICAL HAZARDS	. 228
C3.7.15.1	ERGONOMICS	. 228
C3.7.15.2	NOISE	. 228
C3.7.15.3	VIBRATION	. 229
C3.7.16	SITE WIDE ELEMENTS	. 229
C3.7.16.1	SITE ACCESS AND EGRESS	. 229
C3.7.16.2	VISITORS TO THE SITE	. 229
C3.7.16.3	DELIVERIES	
C3.7.16.4	EMERGENCIES	. 229
C3.7.16.5	LOCATION OF TEMPORARY SITE ACCOMMODATION	. 230
C3.7.16.6	LOCATION OF MATERIALS UNLOADING AND STORAGE	. 230
C3.7.16.7	TRAFFIC AND PEDESTRIAN ROUTES	. 230
C3.7.16.8	SAFETY	. 230
C3.7.17	CONTINUING LIAISON	. 230
C3.7.17.1	UNFORESEEN EVENTUALITIES	
C3.7.17.2	SITE LIAISON	. 231
C3.7.17.3	HEALTH AND SAFETY FILE	. 231
C3.7.17.4	DESIGN DEVELOPMENT	. 231
C3.7.18	CONCLUSION	. 231
C3.7.19	MANAGEMENT	. 231
C 4. SITE IN	IFORMATION	.232
C4	SITE INFORMATION	. 233
C4.1	LOCATION OF SITE	. 233
DRAWINGS	3 234	
C5	DRAWINGS- BOOK 1 OF 1	. 234

The Tender Document is expected to be submitted in this format:

CONT	ENTS	PAGE NUMBERS	
Annexure	Α	TENDER DOCUMENT	
Annexure	В	CSD SUMMARY REPORT	
Annexure	С	MUNICIPAL RATES & TAXES 1. COMPANY 2. DIRECTORS/TRUSTEES/MEMBERS/SHAREHOLDERS	
Annexure	D	OTHER CERTIFICATES (CIDB, BBBEE)	
Annexure	Е	FUNCTIONALITY DOCUMENTS 1. EPERIENCE AND COMPLETION ON SIMILAR PROJECTS 2. CAPACITY AND RESOURCES RELEVANT TO SCOPE OF WORKS 3. FINANCIAL VIABILITY (CREDIT RATING) 4. WORKS PROGRAM AND CASH FLOW	

NUMBER	HEADING	COLOUR
Part T1:	Tendering Procedures	
T1.1	Tender Notice and Invitation to Tender	White
T1.2	Tender Data	White
T1.3	Preferential Procurement Regulations	White
Part T2:	Returnable Documents	
T2.1	List of Returnable Documents	White
T2.2	Returnable Schedules	White
Part C1:	Agreement and Contract Data	
C1.1	Form of Offer and Acceptance	White
C1.2	Contract Data	White
C1.3	Blasting Indemnity	White
C1.4	OHS Contract	White
C1.5	Inclement Weather	White
Part C2:	Pricing data	
C2.1	Pricing Instructions	White
C2.2	Bill of Quantities	White
C2.3	Summary of Schedules	White
Part C3:	Scope of Work	White
C3.1	Description of Works	White
C3.2	Standard Specifications – Mechanical, Electrical, Control and Instrumentation Engineering	White
C3.3	Technical Specifications – Mechanical Engineering	White
C3.4	Technical Specifications – Electrical, Control and Instrumentation Engineering	White
C3.5	Standard and Technical Specifications – Civil Engineering Works	White
C3.6	HIV/AIDS Requirements	White
C3.7	Occupational Health and Safety	White
C4	Site Information	White
C5	Drawings	White

T1 TENDERING PROCEDURES

T1.1 TENDER NOTICE AND INVITATION TO TENDER

Bidders are hereby invited for the retrofitting of 6 sewer pump stations, installation of inline grinders and repairs to waste water treatment plant in Hoopstad and Tikwana. Bidders must have CIDB Grading of 6ME or Higher.

Bid documents will be available as from the **10**th **November 2025, Monday**, on the website of the Municipality or e-tender.

No briefing session will be held.

Bids are to be completed in accordance with the conditions and rules contained in the bid documents. All documents must be sealed and labelled with the Bid number and description, and placed in the tender box, at the offices of **Tswelopele Local Municipality**, **Bosman Street**, **Bultfontein**, **9670**, not later than **12h00 on Monday**, **01 December 2025**.

All bids should be valid for **90 days** as from the closing date.

Bid documents which are not deposited in the tender box by 12h00 on the closing date will not be accepted nor considered.

Procurement related enquiries may be directed to Mr Kennedy Lebitsa at 051 853 1111 and Technical related enquiries may be directed to Mr Lebohang Malokase at 051 853 1111 from 08h00 to 16h00.

The lowest or any bid will not necessarily be accepted and Tswelopele Local Municipality reserves the right not to consider any bid suitably endorsed or comprehensively completed, as well as the right to accept a bid in whole or part. Any bidder not contacted within 90-120 days after the closing date must consider their proposal unsuccessful.

The 80/20 Preferential Points System will be used to evaluate this bid in line with the Preferential Procurement Policy Framework Act,2011. *Bidders will be evaluated on functionality first, only those qualifying by achieving the minimum cut off point of 60% will be evaluated on administrative compliance and then price and specific points.*

RETURNABLE DOCUMENTS

- Completed Tender Enquiry document
- The tender should be returned complete as per the issued document
- Form of offer and acceptance signed
- The completed Contract document, the acceptance page signed in full and all other pages initialled at the bottom or signed in full as required.
- Schedule A Bill of quantities electronic copy
- Applicable schedule of rates for plant and labour
- Valid CIDB Contractor Registration Certificate (minimum of 6ME or higher for lead partner of Joint Venture of CIDB registered entities with the JV CIDB scoring achieving the required minimum)
- Letter of Good standing with Compensation Commissioner
- Certificate of Compliance with the Employment Equity Act (if employing more than 50 employees)
- Proof of your Workmen's compensation registration
- Proof of contractor's guarantee
- Bidding entity company profile
- Proposed Project Organogram and CVs of key personnel
- ORHVS certificates, first aid certificates and vehicle drivers'/operator licences/certificates
- Proposed construction programme (Gantt chart showing activities & resources) in Microsoft Projects or similar software
- Projected cash flow statement and invoicing schedule
- Signed Completion certificates or similar documentation for completed similar projects
- Supporting documents for claiming of functionality points
- Other items specified and completed throughout this document.
- CSD summary report or CSD number
- Latest Municipal rates & taxes account (not older than 3 months) which is not in arrears for more than 3 months for the company & directors/trustees/members/shareholders.
- In the event of a tenant (renting) a copy of a valid signed lease agreement for the company & directors/trustees/members/shareholders and the lates Municipal statement.

PART T1

TENDERING PROCEDURES

T1.2 TENDER DATA

T1.2.1 STANDARD CONDITIONS OF TENDER

The conditions of tender are the Standard Conditions of Tender as contained in **Annex F** of the **CIDB** Standard for Uniformity in Construction Procurement which are reproduced without amendment or alteration for the convenience of tenderers. The Standard Conditions of Tender make several references to the Tender Data for details that apply specifically to this tender. The Tender Data shall have precedence in the interpretation of any ambiguity or inconsistency between it and the Standard Conditions of Tender.

F.1 General

F.1.1 Actions

The Employer and each tenderer submitting a tender offer shall comply with these conditions of tender. In their dealings with each other, they shall discharge their duties and obligations as set out in F.2 and F.3, timeously and with integrity, and behave equitably, honestly and transparently.

F.1.2 Tender Documents

The documents issued by the Employer for the purpose of a tender offer are listed in the tender data. The tender documents issued by Tswelopele Local Municipality comprise of the following:

Part T1: Tendering Procedures

- T1.1 Tender notice and invitation to tender
- T1.2 Tender Data
- T1.3 Preferential Procurement Regulations Tswelopele Local Municipality

Part T2: Returnable Documents

- T2.1 List of returnable documents
- T2.2 Returnable schedules

Part C1: Agreements and Contract Data

- C1.1 Form of offer and acceptance
- C1.2 Contract Data
- C1.3 Blasting Indemnity

Part C2: Pricing data

- C2.1 Pricing instructions
- C2.2 Activity schedules / Bills of Quantities
- C2.3 Summary of schedule of works

Part C3: Scope of work

- C3 .1 Description of Works
- C3. 2 Standard Specifications Mechanical, Electrical, Control and Instrumentation Engineering

- C3. 3 Technical Specifications Mechanical Engineering
- C3. 4 Technical Specifications Electrical, Control and Instrumentation Engineering
- C3. 5 Standard and Technical Specifications Civil Engineering Works
- C3. 6 HIV/AIDS Requirements
- C3. 7 Occupational Health and Safety

Part C4: Site Information

C4.1 Site Information

Part C5: Contract Drawings

C5. 1 Contract Drawings

F.1.3 Interpretation

- **F.1.3.1** The Tender Data and additional requirements contained in the tender schedules that are included in the returnable documents are deemed to be part of these conditions of tender.
- **F.1.3.2** These conditions of tender, the Tender Data and tender schedules which are only required for tender evaluation purposes, shall not form part of any contract arising from the invitation to tender.
- **F.1.3.3** For the purposes of these conditions for the calling for expressions of interest, the following definitions apply:
 - (a) **Comparative offer** means the tenderer's financial offer after the factors of nonfirm prices, all unconditional discounts and any other tendered parameters that will affect the value of the financial offer have been taken into consideration
 - (b) corrupt practice means the offering, giving, receiving or soliciting of anything of value to influence the action of the Employer or his staff or agents in the tender process; and
 - (c) Fraudulent practice means the misrepresentation of the facts in order to influence the tender process or the award of a contract arising from a tender offer to the detriment of the Employer, including collusive practices intended to establish prices at artificial levels
 - (d) **Quality (Functionality)** means the totality of features and characteristics of a product or service that bear on its ability to satisfy stated or implied needs

F.1.5 the Employer's right to accept or reject any tender offer

- **F.1.5.1** The Employer may accept or reject any variation, deviation, tender offer, or alternative tender offer, and may cancel the tender process and reject all tender offers at any time before the formation of a contract. The Employer shall not accept or incur any liability to a tenderer for such cancellation and rejection but will give reasons for such action upon written request to do so.
- **F.1.5.2** The Employer may not subsequent to the cancellation or abandonment of a tender process or the rejection of all tender offers re-issue a tender covering substantially

RETROFITTING OF 6 sewer pump stations , INSTALLATION OF INLINE GRINDERS AND REPAIRS TO WASTE WATER TREATMENT PLANT IN HOOPSTAD AND TIKWANA

TENDER PROCEDURES

the same scope of work within a period of six months unless only one tender was received and such tender was returned unopened to the tenderer.

F.2 Tenderers obligation

F2.1 Eligibility

- **F2.1.1** Submit a tender offer only if the tenderer satisfies the criteria stated in the tender data and have in their employ management and supervisory staff satisfying the requirements of the Scope of Work for labour intensive competencies for supervisory, and the tenderer, or any of his principals, is not under any restriction to do business with employer.
- **F2.1.2** Notify the employer of any proposed material change in the capabilities or formation of the tendering entity (or both) or any other criteria which formed part of the qualifying requirements used by the employer as the basis in a prior process to invite the tenderer to submit a tender offer and obtain the employer's written approval to do so prior to the closing time for tenders.
- F2.1.2.1 The following tenderers who are registered with the **CIDB**, or are capable of being so registered prior to the evaluation of submissions, are eligible to submit tenders:
 - a) contractors who have a contractor grading designation equal to or higher than a contractor grading designation determined in accordance with the sum tendered for a 6ME or Higher class of construction work; and
 - b) contractors registered as potentially emerging enterprises with the CIDB who are registered in one contractor grading designation lower than that required in terms of a) above
- F2.1.2.2 Joint ventures are eligible to submit tenders provided that:
 - a) Every member of the joint venture is registered with the CIDB;
 - b) The lead partner has a contractor grading designation in the **6ME or Higher** class of Mechanical Engineering construction work; and
 - c) The combined contractor grading designation calculated in accordance with the Construction Industry Development Regulations is equal to or higher than a contractor grading designation determined in accordance with the sum tendered for 6ME or Higher
 - (d) A Joint Venture Agreement in line with CIDB Regulations and **Tswelopele Local Municipality** Supply Chain Management Policy in SBD 6.1 (8).
 - (e) **CIDB** Certificates or CRS Numbers for both Joint Venture Partners are attached.

F.2.2 Cost of tendering

Accept that the Employer will not compensate the tenderer for any costs incurred in the preparation and submission of a tender offer, including the costs of any testing necessary to demonstrate that aspects of the offer satisfy requirements.

F.2.3 Check documents

Check the tender documents on receipt for completeness and notify the Employer of any discrepancy or omission.

F.2.4 Confidentiality and copyright of documents

Treat as confidential all matters arising in connection with the tender. Use and copy the documents issued by the Employer only for the purpose of preparing and submitting a tender offer in response to the invitation.

F.2.5 Reference documents

Obtain, as necessary for submitting a tender offer, copies of the latest versions of standards, specifications, Conditions of Contract and other publications, which are not attached but which are incorporated into the tender documents by reference.

F.2.6 Acknowledge addenda

Acknowledge receipt of addenda to the tender documents, which the Employer may issue, and if necessary apply for an extension to the closing time stated in the Tender Data, in order to take the addenda into account.

F.2.7 Site visit and clarification meeting

Attend, where required, a site visit and clarification meeting at which tenderers may familiarize themselves with aspects of the proposed work, services or supply and raise questions. Details of the meeting(s) are stated in the Tender Data.

F.2.8 Seek clarification

Request clarification of the tender documents, if necessary, by notifying the Employer at least five working days before the closing time stated in the Tender Data.

F.2.9 Insurance

Be aware that the extent of insurance to be provided by the Employer (if any) may not be for the full cover required in terms of the Conditions of Contract identified in the Contract Data. The tenderer is advised to seek qualified advice regarding insurance.

F.2.10 Pricing the tender offer

- **F.2.10.1** Include in the rates, prices, and the tendered total of the prices (if any) all duties, taxes (except Value Added Tax (VAT), and other levies payable by the successful tenderer, such duties, taxes and levies being those applicable 14 days before the closing time stated in the Tender Data.
- **F2.10.2** Show VAT payable by the Employer separately as an addition to the tendered total of the prices.
- **F.2.10.3** Provide rates and prices that are fixed for the duration of the contract and not subject to adjustment except as provided for in the Conditions of Contract identified in the Contract Data.

F.2.10.4 State the rates and prices in Rand unless instructed otherwise in the Tender Data. The Conditions of Contract identified in the Contract Data may provide for part payment in other currencies.

F.2.11 Alterations to documents

Not make any alterations or additions to the tender documents, except to comply with instructions issued by the Employer, or necessary to correct errors made by the tenderer. All signatories to the tender offer shall initial all such alterations. Erasures and the use of masking fluid are prohibited.

F.2.12 Alternative tender offers

- **F.2.12.1** Unless otherwise stated in the tender data, submit alternative tender offers only if a main tender offer, strictly in accordance with all the requirements of the tender documents, is also submitted as well as a schedule that compares the requirements of the tender documents with the alternative requirements that are proposed.
- **F.2.12.2** Accept that an alternative tender offer may be based only on the criteria stated in the Tender Data or criteria otherwise acceptable to the Employer.

F.2.13 Submitting a tender offer

- **F.2.13.1** Submit a tender offer to provide the whole of the works, services or supply identified in the Scope of Work, unless stated otherwise in the Tender Data.
- **F.2.13.2** Return all returnable documents to the Employer after completing them in their entirety, either electronically (if they were issued in electronic format) or by writing in black ink.
- **F.2.13.3** Submit the parts of the tender offer communicated on paper as an original plus the number of copies stated in the Tender Data, with an English translation of any documentation in a language other than English, and the parts communicated electronically in the same format as they were issued by the Employer.
- **F.2.13.4** Sign the original and all copies of the tender offer where required in terms of the Tender Data. The Employer will hold all authorized signatories liable on behalf of the tenderer. Signatories for tenderers proposing to contract as joint ventures shall state which of the signatories is the lead partner whom the Employer shall hold liable for the purpose of the tender offer.
- **F.2.13.5** Each package shall state on the outside the Employer's address and identification details stated in the Tender Data, as well as the tenderer's name and contact address.
- **F.2.13.6** Where a two-envelope system is required in terms of the Tender Data, place and seal the returnable documents listed in the Tender Data in an envelope marked "financial proposal" and place the remaining returnable documents in an envelope marked "technical proposal". Each envelope shall state on the outside the employer's address and identification details stated in the tender data, as well as the tenderer's name and contact address.

F.2.13.8 Accept that the Employer shall not assume any responsibility for the misplacement or premature opening of the tender offer if the outer package is not sealed and marked as stated.

F.2.14 Information and data to be completed in all respects

Accept that tender offers, which do not provide all the data or information requested completely and, in the form, required, may be regarded by the Employer as non-responsive.

F.2.15 Closing time

- **F.2.15.1** Ensure that the Employer receives the tender offer at the address specified in the Tender Data not later than the closing time stated in the Tender Data. Proof of posting shall not be accepted as proof of delivery. The Employer shall not accept tender offers submitted by telegraph, telex, facsimile or e-mail, unless stated otherwise in the Tender Data.
- **F.2.15.2** Accept that, if the Employer extends the closing time stated in the Tender Data for any reason, the requirements of these conditions of tender apply equally to the extended deadline

F.2.16 Tender offer validity

- **F.2.16.1** Hold the tender offer(s) valid for acceptance by the Employer at any time during the validity period stated in the Tender Data after the closing time stated in the Tender Data.
- **F.2.16.2** If requested by the Employer, consider extending the validity period stated in the Tender Data for an agreed additional period.

F.2.17 Clarification of tender offer after submission

Provide clarification of a tender offer in response to a request to do so from the Employer during the evaluation of tender offers. This may include providing a breakdown of rates or prices and correction of arithmetical errors by the adjustment of certain rates or item prices (or both). No change in the total of the prices or substance of the tender offer is sought, offered, or permitted. The total of the prices stated by the tenderer shall be binding upon the tenderer.

F.2.18 Provide other material

- **F.2.18.1** Provide, on request by the Employer, any other material that has a bearing on the tender offer, the tenderer's commercial position (including notarized joint venture agreements), pre-referencing arrangements, or samples of materials, considered necessary by the Employer for the purpose of a full and fair risk assessment. Should the tenderer not provide the material, or a satisfactory reason as to why it cannot be provided, by the time for submission stated in the Employer's request, the Employer may regard the tender offer as non-responsive.
- **F.2.18.2** Dispose of samples of materials provided for evaluation by the Employer, where required.

F.2.19 Inspections, tests and analysis

Provide access during working hours to premises for inspections, tests and analysis as provided for in the Tender Data.

F.2.20 Submit securities, bonds, policies, etc.

If requested, submit for the Employer's acceptance before formation of the contract, all securities, bonds, guarantees, policies and certificates of insurance required in terms of the Conditions of Contract identified in the Contract Data.

F.2.21 Check final draft

Check the final draft of the contract provided by the Employer within the time available for the Employer to issue the contract.

F.2.22 Return of other tender documents

If so instructed by the Employer, return all retained tender documents within 28 days after the expiry of the validity period stated in the Tender Data.

F.2.23 Certificates

Include in the tender submission or provide the Employer with any certificates as stated in the Tender Data.

F.3 The Employer's undertakings

F.3.1 Respond to request from the tenderer

F.3.1.1 Unless otherwise stated in the tender Data respond to a request for clarification received up to five working days before the tender closing time stated in the Tender Data and notify all tenderers who drew procurement documents.

F.3.2 Issue Addenda

If necessary, issue addenda that may amend or amplify the tender documents to each tenderer during the period from the date of the Tender Notice until seven days before the tender closing time stated in the Tender Data. If, as a result a tenderer applies for an extension to the closing time stated in the Tender Data, the Employer may grant such extension and, will then notify it to all tenderers who drew documents.

F.3.3 Return late tender offers

Return tender offers received after the closing time stated in the Tender Data, unopened, (unless it is necessary to open a tender submission to obtain a forwarding address), to the tenderer concerned.

F.3.4 Opening of tender submissions

- **F.3.4.2** Announce at the opening held immediately after the opening of tender submissions, at a venue indicated in the Tender Data, the name of each tenderer whose tender offer is opened, the total of his prices, preferences claimed and time for completion, if any, for the main tender offer only.
- **F.3.4.3** Make available the record outlined in F.3.4.2 to all interested persons upon request if the employer deemed necessary.

F.3.5 Two-envelope system

- **F.3.5.1** Where stated in the Tender Data that a two-envelope system is to be followed, open only the technical proposal of valid tenders in the presence of tenderers' agents who choose to attend at the time and place stated in the Tender Data and announce the name of each tenderer whose technical proposal is opened
- **F.3.5.2** Evaluate the quality of the technical proposals offered by tenderers, then advice tenderers who remain in contention for the award of the contract of the time and place when the financial proposals will be opened. Open only the financial proposals of tenderers, who score in the quality evaluation above the minimum number of points for quality stated in the Tender Data, and announce the score obtained for the technical proposals and the total price and any preferences claimed. Return unopened financial proposals to tenderers whose technical proposals failed to achieve the minimum number of points for quality.

F.3.6 Non-disclosure

Not disclose to tenderers, or to any other person not officially concerned with such processes, information relating to the evaluation and comparison of tender offers, the final evaluation price and recommendations for the award of a contract, until after the award of the contract to the successful tenderer.

F.3.7 Grounds for rejection and disqualification

Determine whether there has been any effort by a tenderer to influence the processing of tender offers and instantly disqualify a tenderer (and his tender offer) if it is established that he engaged in corrupt or fraudulent practices.

F.3.8 Test for responsiveness

- **F.3.8.1** Determine, on opening and before detailed evaluation, whether each tender offer properly received:
 - a) Meets the requirements of these Conditions of Tender.
 - b) Has been properly and fully completed and signed, and
 - c) is responsive to the other requirements of the tender documents.
- **F.3.8.2** A responsive tender is one that conforms to all the terms, conditions, and specifications of the tender documents without material deviation or qualification. A material deviation or qualification is one which, in the Employer's opinion, would:

- a) detrimentally affect the scope, quality, or performance of the works, services or supply identified in the Scope of Work,
- change the Employer's or the tenderer's risks and responsibilities under the contract, or
- c) Affect the competitive position of other tenderers presenting responsive tenders, if it were to be rectified.

Reject a non-responsive tender offer, and not allow it to be subsequently made responsive by correction or withdrawal of the non-conforming deviation or reservation

F.3.9 Arithmetical errors, omissions and discrepancies.

- **F.3.9.1** Check responsive tenders for discrepancies between amounts in words and amounts in figures. Where there is a discrepancy between the amounts in figures and the amount in words, the amount in words shall govern.
- **F.3.9.2** Check the highest ranked tender or tenderer with the highest number of tender evaluation points after the evaluation of tender offers in accordance with F.3.11 for:
 - a) The gross misplacement of the decimal point in any unit rate;
 - b) Omissions made in completing the pricing schedule or bills of quantities; or
 - c) Arithmetic errors in:
 - i) Line item totals resulting from the product of a unit rate and a quantity in bills of quantities or schedules of prices; or
 - ii) The summation of the prices.
- **F.3.9.3** Notify the tenderer of all errors or omissions that are identified in the tender offer and either confirm the tender offer as tendered or accept the corrected total of prices.
- **F.3.9.4** Where the tenderer elects to confirm the tender offer as tendered, correct the errors as follows:
 - a) If bills of quantities or pricing schedules apply and there is an error in the line item total resulting from the product of the unit rate and the quantity, the line item total shall govern and the rate shall be corrected. Where there is an obviously gross misplacement of the decimal point in the unit rate, the line item total as quoted shall govern, and the unit rate shall be corrected.
 - b) Where there is an error in the total of the prices either as a result of other corrections required by this checking process or in the tenderer's addition of prices, the total of the prices shall govern and the tenderer will be asked to revise selected item prices (and their rates if bills of quantities apply) to achieve the tendered total of the prices.

F.3.10 Clarification of a tender offer

Obtain clarification from a tenderer on any matter that could give rise to ambiguity in a contract arising from the tender offer.

F.3.11 Evaluation of tender offers

F3.11.1 General

Appoint an evaluation panel of not less than three persons. Reduce each responsive tender offer to a comparative offer and evaluate it using the tender evaluation method that is indicated in the Tender Data and described below:

Method No.	Description
Method 1: Financial offer	Rank tender offers from the most favourable to the least favourable comparative offer.
	Recommend highest ranked tenderer for the award of the contract, unless there are compelling and justifiable reasons not to do so.
Method 2:	Score tender evaluation points for financial offer.
Financial offer and	Confirm that tenderers are eligible for the preferences claimed and if so, score tender evaluation points for referencing.
preferences	3) Calculate total tender evaluation points.
	Rank tender offers from the highest number of tender evaluation points to the lowest.
	5) Recommend tenderer with the highest number of tender evaluation points for the award of the contract, unless there are compelling and justifiable reasons not to do so.
Method 3: Financial offer	Score quality, rejecting all tender offers that fail to score the minimum number of points for quality stated in the Tender Data.
and quality	2) Score tender evaluation points for financial offer.
	3) Calculate total tender evaluation points.
	Rank tender offers from the highest number of tender evaluation points to the lowest.
	5) Recommend tenderer with the highest number of tender evaluation points for the award of the contract, unless there are compelling and justifiable reasons not to do so.
Method 4:	1) Score Quality/Functionality, rejecting all tender offers that fail to
Financial offer, Quality/	score the minimum number of points for Quality/Functionality stated in the Tender Data.
Functionality	2) Score tender evaluation points for financial offer.

Method No.	Description
and Preferences	3) Confirm that tenderers are eligible for the preferences claimed, and if so, score tender evaluation points for preference.
	4) Calculate total tender evaluation points.
	5) Rank tender offers from the highest number of tender evaluation points to the lowest.
	6) Recommend tenderer with the highest number of tender evaluation points for the award of the contract, unless there are compelling and justifiable reasons not to do so.

NOTE: $\underline{\textit{Method 4}}$ will be used to evaluate this tender. See below for evaluation criteria.

EVALUATION CRITERIA

THIS BID WILL BE EVALUATED AND ADJUDICATED ACCORDING TO THE FOLLOWING CRITERIA:

- Relevant specifications
- Value for money
 Capability to exe
- 3. Capability to execute the contract
- 4. PPPFA & associated regulations
- 5. TLM SCM Policy
- 6. Bids will be evaluated in terms of the following two stages:

Stage 1: Evaluation on Quality/Functionality

Under functionality, Bidders must achieve a minimum of 60% of quality/functionality points in order to be considered for further evaluation in stage 2 (Evaluation on Price and Specific Goals).

NB: Only the combined Price & Specific Goals points will determine the highest point scoring bidder to be awarded the contract

Table 1: Technical Functionality

Functionality	100 Points
A. Experience and completion on similar projects	45
B. Capacity and resources relevant to scope of works	40
C. Financial viability (Bank rating)	5
D. Works program and Cash Flow	10
Minimum Threshold = 60 points	

Table 2: Technical Functionality Point Allocation

A. Experience on similar projects within the last 10 years	Max. 45 Points
Four (4) projects (sewer / water pumping stations with pipelines and project cost over R3 million). Signed appointment letters and signed Completion Certificates.	45
Three (3) projects (sewer / water pumping stations with pipelines and project cost over R3 million). Signed appointment letters and signed Completion Certificates.	30
Two (2) projects (sewer / water pumping stations with pipelines and project cost over R3 million). Signed appointment letters and signed Completion Certificates.	20

	e (1) projects (sewer / water pumping stations with pipelines and project cost r R3 million). Signed appointment letters and signed Completion Certificates.	10
cost	o (0) projects (sewer / water pumping stations with pipelines and project tover R3 million). Signed appointment letters and signed Completion tificates.	0
В.	Key Personnel (Non-submission of CV, SA ID Copy and Engineering Qualifications is 0 points)	Max. 40 Points
	B1. Site Supervisor (Maximum of 15 points)	
	1 x Site Supervisor with more than 10 years relevant work experience. Detailed CV, ID copy and Qualification certificates must be provided.	15
	1 x Site Supervisor with 5 or more years relevant work experience. Detailed CV, ID copy and Qualification certificates must be provided.	10
	1 x Site Supervisor with less than 5 years relevant work experience. Detailed CV, ID copy and Qualification certificates must be provided.	0
	B2. Artisans (Maximum of 25 points)	
	1 x Qualified HT Electricians / Millwrights with 5 or more years of relevant experience. Copy of Journeyman Certificate, CV and ID must be provided. Two (2) points will be awarded for 1 to 4 years of relevant experience.	10
	1 x Qualified Fitter with 5 or more years of relevant experience. Copy of Journeyman Certificate, CV and ID must be provided. Two (2) points will be awarded for 1 to 4 years of relevant experience.	10
	1 x Qualified instrumentation artisan / technician with 5 or more years of relevant experience. CV, certificates and ID copy must be provided. Two (2) points will be awarded for 1 to 4 years of relevant experience.	5
C.	Financial Viability	Max 5 Points
	Credit rating / bank code of A to C (not older than 3 months from the closing date)	5
D.	Works Program & Cash Flow	Max 10 Points
	Level 2 schedule in Microsoft Projects / Similar scheduling software.	5
	Project Cash Flow with invoicing schedule.	5

Stage 2: Evaluation on Price and Specific Goals 80/20

FINANCIAL OFFER AND EVALUATION ON PRICE POINTS

- Score Bid evaluation points for financial offer.
- Confirm that Bidders are eligible for the Specific Goals claimed, and if so, score Bid evaluation points for specific Goals.

- Calculate total Bid evaluation points (Price points plus specified goals points)
- Rank Bid offers from the highest number of Bid evaluation points to the lowest.
- The bidder obtaining the highest number of total points will be awarded the contract.
- Preference points shall be calculated after prices have been brought to a comparative basis taking into account all factors of non-firm prices and all unconditional discounts;
- Points scored must be rounded off to the nearest 2 decimal places.
- In the event that two or more bids have scored equal total points, the successful bids must be the one scoring the highest number of preference points for Specific goals Points
- However, when functionality is part of the evaluation process and two or more bids have scored equal points including equal preference points for specific Goals, the successful bid must be the one scoring the highest score for functionality.
- Should two or more bids be equal in all respects, the award shall be decided by the drawing of lots.

2.2 Price formula

$$Np = 80[1 - (Pt - Pmin)]$$

Pmin

- Where: Np = the number of bid/tender adjudication points awarded for price.
- Pt = the bid/tender sum (corrected if applicable) of the responsive bid under consideration.
- Pmin = the bid/tender sum (corrected if applicable) of the lowest responsive tender/bid.

2.3 Scoring for Specific Goals

Specified Goals to be calculated as follows:

Points for the specific goals for contracting with persons, or categories of persons, historically disadvantaged by unfair discrimination on the basis of race:

Black-owned	Number of points on 80/20 points system	Number of points on 90/10 points system	Required Proof
51-100%Black-owned	8	3	CSD Report and ID
enterprise			Сору
41-50% Black-owned enterprise	6	2	CSD Report and ID Copy

31-40%Black-owned enterprise	4	1	CSD Report and ID Copy
21-30% Black-owned enterprise	2	0	CSD Report and ID Copy
0-20% Black-owned	1	0	CSD Report and ID
enterprise			Сору

Points for the specific goals for contracting with persons, or categories of persons, historically disadvantaged by unfair discrimination on the basis of gender:

Women-owned	Number of points on 80/20 points system	Number of points on 90/10 points system	Required Proof
51-100% Women-owned enterprise	4	3	CSD Report and ID Copy
31-50% Women-owned enterprise	3	1	CSD Report and ID Copy
11-30% Women-owned enterprise	2	1	CSD Report and ID Copy
1-10% Women-owned enterprise	1	1	CSD Report and ID Copy

Points for the specific goals for contracting with persons, or categories of persons, historically disadvantaged by unfair discrimination on the basis of disability:

Disability-owned	Number of points on 80/20 points	Number of points on 90/10 points	Required Proof
	system	system	
51-100% Disabled- owned enterprise	4	2	ID Copy, CSD Report and medical certificate
31-50% Disabled- owned enterprise	3	1	ID Copy, CSD Report and medical certificate
11-30% Disabled- owned enterprise	2	1	ID Copy, CSD Report and medical certificate
1-10% Disabled-owned enterprise	1	0	ID Copy, CSD Report and medical certificate

Points for the specific goals for contracting with persons, or categories of persons, historically disadvantaged by unfair discrimination on the basis of youth:

Youth-owned	Number of points on 80/20 points system	Number of points on 90/10 points system	Required Proof
51-100% Youth-owned enterprise	4	2	CSD Report and ID Copy
31-50% Youth-owned enterprise	3	1	CSD Report and ID Copy
11-30% Youth-owned enterprise	2	1	CSD Report and ID Copy
1-10% Youth-owned enterprise	0	0	CSD Report and ID Copy

F.3.11.6 Decimal places

Score financial offers, preferences and quality, as relevant, to two decimal places.

F.3.12 Insurance provided by the Employer

If requested by the proposed successful tenderer, submit for the tenderer's information the policies and / or certificates of insurance which the Conditions of Contract identified in the Contract Data, require the Employer to provide.

F.3.13 Acceptance of tender offer

Accept the tender offer, if in the opinion of the employer, it does not present any unacceptable commercial risk and only if the tenderer.

- a) is not under restrictions, or has principals who are under restrictions, preventing participating in the employer's procurement,
- b) can, as necessary and in relation to the proposed contract, demonstrate that he or she possesses the professional and technical qualifications, professional and technical competence, financial resources, equipment and other physical facilities, managerial capability, reliability, experience and reputation, expertise and the personnel, to perform the contract.
- c) has the legal capacity to enter into the contract,

- d) is not insolvent, in receivership, bankrupt or being wound up, has his affairs administered by a court or a judicial officer, has suspended his business activities, or is subject to legal proceedings in respect of any of the foregoing,
- e) Complies with the legal requirements, if any, stated in the tender data, and
- f) is able, in the opinion of the employer, to perform the contract free of conflicts of interest.
- **F.3.13.1** Accept tender offer only if the tenderer satisfies the legal requirements stated in the Tender Data.
- **F.3.13.2** Notify the successful tenderer of the Employer's acceptance of his tender offer by completing and returning one copy of the form of offer and acceptance before the expiry of the validity period stated in the Tender Data or agreed additional period. Providing the form of offer and acceptance does not contain any qualifying statements, it will constitute the formation of a contract between the Employer and the successful tenderer as described in the form of offer and acceptance.

F.3.14 Prepare contract documents

If necessary, revise documents that shall form part of the contract and that were issued by the Employer as part of the tender documents to take account of:

- a) Addenda issued during the tender period,
- b) Inclusion of some of the returnable documents,
- c) Other revisions agreed between the Employer and the successful tenderer, and
- d) The schedule of deviations attached to the form of offer and acceptance, if any.

F.3.15 Complete adjudicator's contract

Unless alternative arrangements have been agreed or otherwise provided for in the contract, arrange for both parties to complete formalities for appointing the selected adjudicator at the same time as the main contract is signed.

F.3.16 Notice to Unsuccessful Tenderers

After the successful tenderer has acknowledged the Employer's notice of acceptance, notify other tenderers that their tender offers have not been accepted.

F.3.18 Provide copies of the contracts

Provide to the successful tenderer the number of copies stated in the Tender Data of the signed copy of the contract as soon as possible after completion and signing of the form of offer and acceptance

T1.3 PREFERENTIAL PROCUREMENT REGULATIONS

Supply Chain Management Procedures

This Request for Proposals has been compiled and approved by the Bid Specification Committee of Tswelopele Local Municipality established in terms of the Public Finance Management Act and its Regulations.

The bids received will be evaluated by the Bid Evaluation Committee in terms of the bids evaluation criteria described in this document. The Committee will then submit a report on the bids received to the Bid Adjudication Committee.

The Bid Adjudication Committee will make a recommendation to the Accounting Officer or his delegate nominated in writing. The Accounting Officer will either accept the recommendation of the Bid Adjudication Committee or refer it back to the Bid Adjudication Committee for further investigation or award the contract to a different bidder. In the event that the contract is awarded to a different bidder from the one recommended by the Bid Adjudication Committee, the Auditor-General shall be informed of the reasons for the decision.

The above process will, depending upon the complexity of the project and the number of bids received, take between 4 and 6 weeks. Bidders are requested to refrain from making inquiries on progress and/or from submitting unsolicited information regarding their bids and especially from commenting on other bidders' proposals during this time. Tswelopele Local Municipality will endeavour to keep bidders informed of the progress of the process.

PART T2

RETURNABLE DOCUMENTS

T2 RETURNABLE DOCUMENTS

T2.1 LIST OF RETURNABLE DOCUMENTS

T2.1.1 The tenderer must complete the following returnable documents:

- a. Completed Tender Enquiry document
- b. The tender should be returned complete as per the issued document
- c. Form of offer and acceptance signed
- d. The completed Contract document, the acceptance page signed in full and all other pages initialled at the bottom or signed in full as required.
- e. Schedule A Bill of quantities electronic copy
- f. Valid CIDB Contractor Registration Certificate (minimum of 6ME or higher for lead partner of Joint Venture of CIDB registered entities with the JV CIDB scoring achieving the required minimum)
- g. Letter of Good standing with Compensation Commissioner
- h. Certificate of Compliance with the Employment Equity Act (if employing more than 50 employees)
- i. Proof of your Workmen's compensation registration
- j. Proof of contractor's guarantee
- k. Proposed Project Organogram and CVs of key personnel
- ORHVS certificates, first aid certificates and vehicle drivers'/operator licences/certificates
- m. Proposed construction programme (Gantt chart showing activities & resources) in Microsoft Projects or similar software
- n. Projected cash flow statement and invoicing schedule
- Signed Completion certificates or similar documentation for completed similar projects
- p. Supporting documents for claiming of functionality points
- q. CSD summary report
- r. Latest Municipal rates & taxes account (not older than 3 months) which is not in arrears for more than 3 months for the company & directors/trustees/members/shareholders.
- s. In the event of a tenant (renting) a copy of a valid signed lease agreement for the company & directors/trustees/members/shareholders and the municipal account statement.

T2.1.2 Returnable Schedules required for tender evaluation purposes:

- a) Schedule A Certificate for authority of companies
- b) Schedule B Record of Addenda to tender documents
- c) Schedule C Plant and Equipment
- e) Schedule D- Relevant work experience carried out by

Tenderer

- f) Schedule E Tenderer Key Personnel
- g) Schedule F Full Details of Directors/ Trustees/ Members/ Shareholders
- h) Schedule G Company Details Regarding Tenderer
- i) Schedule H Contractors OHS Management system checklist
- j) Schedule I Contractors Estimated monthly expenditure
- k) Schedule J Contractors Labour Content

T2.1.3 Returnable Schedules that are incorporated into the contract

- a) MBD 1 Invitation to Tender
- b) MBD 4 Declaration of interest
- c) MBD 5 Declaration for procurement above R10 Million
- d) MBD 6.1 Preference Points
- e) MBD 8 Declaration of Past Supply Chain Management Practises
- f) MBD 9 Certificate of Independent bid determination

SCHEDULE A: CERTIFICATE OF AUTHORITY FOR COMPANIES

This Returnable Schedule is to be completed by companies and close corporations. Indicate the status of the tenderer by ticking the appropriate box hereunder. The tenderer must complete the certificate set out below for the relevant category.

	A Company	C Joint Venture	E Close Corporation
	Company	John Ventare	Olose Corporation
В.	1 Certificate for company		
		, mana	
he 	reby confirm that by resolu	tion of the board taken on, has been duly authoriz contract resulting from it on behalf of	
	anaging director		
	ate		
В.:	2. Certificate for Joint Ventu	re	
W	e, the undersigned, are submi	tting this tender offer in Joint Ver	iture and hereby authorise
Mr	/Ms	, authorised	signatory of the company
		, act	ing in the capacity of lead
	rtner, to sign all documents in co r behalf of:	nnection with the tender offer and any	contract resulting from it on
	NAME OF FIRM	ADDRESS	AUTHORISING SIGNATURE, NAME & CAPACITY
	Lead partner		
- 1	I I		1

RETROFITTING OF 6 sewer pump stations , INSTALLATION OF INLINE GRINDERS AND REPAIRS TO WASTE WATER TREATMENT PLANT IN HOOPSTAD AND TIKWANA

Certificate for clo	se Corporation						
_	, being the	•					_
	• • • • • • • • • • • • • • • • • • • •						
y authorise Mr/Ms .							, to
ll documents in conn	ection with the te	ender ar	nd any contra	ct res	ulting	from it on ou	ır behalf of:
NAME	ADDRESS			SI	GNAT	URE	DATE

NOTE: This certificate is to be completed and signed by all of the key members upon who rests the direction of the affairs of the Close Corporation as a whole.

SCHEDULE B: RECORD OF ADDENDA TO TENDER DOCUMENTS

We co tender	nfirm that the following con offer, amending the tende	nmunications received from the Employer before the submission of this documents, have been taken into account in this tender offer:
	Date	Title or Details
1.		
2.		
3.		
4.		
5.		
6.		
7.		
8.		
NOTE	: Attach additional pages if	more space is required.
Sig	ned:	Date:
Na	me:	Position:
Te	nderer:	

RETURNABLE SCHEDULE

SCHEDULE C: PLANT AND EQUIPMENT

The following are lists of major items of relevant equipment that I/we presently own or lease (Attach proof of ownership or rental) and will have available for this contract or will acquire or hire for this contract if my/our tender is accepted. Details of major equipment that is owned by and immediately available for this contract. Description, size, capacity, etc. Quantity Attach additional pages if more space is required. Details of major equipment that will be hired or acquired for this contract if my/our tender is acceptable. Quantity Description, size, capacity, etc. Attach additional pages if more space is required. Date: Signed:

Tenderer:

Name: _____ Position: ____

RETURNABLE SCHEDUL	∟E	П	U	ı		ı	Е	1	H	3	C	S		Е	L	3	Œ	Δ	l	N	₹	JI	ΓL	E٦	R	
--------------------	----	---	---	---	--	---	---	---	---	---	---	---	--	---	---	---	---	---	---	---	---	----	----	----	---	--

SCHEDULE D: RELEVANT WORK CARRIED OUT BY TENDERER

Previous experience

Provide the following information on relevant previous experience (indicate specifically projects of similar or larger size and/or which is similar with regard to type of work. In addition to any requirements, bidders must furnish particulars of:

- (a) all Construction Work of similar nature of the assignment provided to an organ of state in the last five years;
- (b) any similar Construction Work provided to an organ of state in the last five years.

This information is material to the award of the Contract.

	Contract Value	Project	Duration	Expenditure		Reference	
Project Description	(VAT excl)	Start	Finish	@ Completion	Name:	Organisation:	Tel No:

Name of Tendering Ent	ity:	
Signature:		DATE:

SCHEDULE E: TENDERER'S KEY PERSONNEL

NAME	POSITION	NQF QUALIFICATION
TENDERER:		
SIGNATURE:	DATE:	

SCHEDULE F

FULL DETAILS OF DIRECTORS / TRUSTEES / MEMBERS / SHAREHOLDERS.

Full Name	Identity Number	Personal Tax Reference Number	State Employee Number / Perusal Number

SCHEDULE G

COMPANY DETAILS REGARDING TENDERER

	nplete Nan siness)	me :					
Reg	istered Ad	ldress :					
Reg	istration N	lo. :					
Туре	e of Busin	ess :					
India	cate with a	an "X"					
	ne-man usiness	Partnership	Private Company	Closed Corporation	Joint Venture	Consortium	Others
Date	e registere	ed :					
Tel.	No.	: (V	V) Code:	No.:			
Cell	No.	:					
Fax	No.	: Co	ode:	No.:			
E-m	ail	:					
AUT	HORIZE	O / CONTACT F	PERSON				
Nam	ne	:					
Title		:					
FINA	ANCIAL D	ETAIL					
(1)	Bank de	etail					
	Bank	:					
	Branch	:					
	Account	Name:					
	Account	No. :					
	Contact	person:					
	Tel No.	:					
	Fax No						

	SCHEDULE H: CONTRACTORS' OHS MANAGEMENT SYSTEM CHECKLIST	YES	I
1.	OHS Policy and Management	NO	
1.1	Is there a written company health and safety policy?		
1.2	Does the company have an OHS Management System?		
1.3	Is there a company OHS Management System manual or plan?		
1.4	Are health and safety responsibilities clearly identified for all levels of staff?		
2.	Safe Work Practices and Procedures		
2.1	Has the company prepared safe operating procedures or specific safety instructions relevant to its operations?		
2.2	Does the company have any permit to work systems?		
2.3	Is there a documented incident investigation procedure?		
2.4	Are there procedures for maintaining, inspecting and assessing the hazards of plant operated/ owned by the company?		
2.5	Are there procedures for storing and handling hazardous substances?		
2.6	Are there procedures for identifying, assessing and controlling risks associated with manual handling?		
3.	OHS Training		
3.1	Is health and safety training conducted in the company		
3.2	Is a record maintained of all training and induction programs undertaken for employees in the company?		
4.	Health and Safety Workplace Inspection		
4.1	Are regular health and safety inspections at worksites undertaken?] [
4.2 ir	Are standard workplace inspection checklists used to conduct health and safety aspections?] [
4.3	Is there a procedure by which employees can report hazards at workplaces?		
5.	Health and Safety Consultation		
5.1	Is there a workplace health and safety committee?		
5.2	Are employees involved in decision making over OHS matters?		

RETROFITTING OF 6 sewer pump stations , INSTALLATION OF INLINE GRINDERS AND REPAIRS TO WASTE WATER TREATMENT PLANT IN HOOPSTAD AND TIKWANA

RETURNABLE SCHEDULE

5.3 6.	Are there employee elected health and safety representatives? OHS Performance Monitoring	
6.1	Is there a system for recording and analysing health and safety performance statistics?	
6.2	Are employees regularly provided with information on company health and safety performance?	
6.3	Has the company ever been convicted of an occupational health and safety offence?	
7.	Health and Safety Plan for this specific contract	
7.1 Do	es your company's health and safety plan contain the following elements?	
a) b) c) d) e) f) g) h) i)	Description of contract OHS structure for work undertaken under this contract Induction and safety training Safe work practices and procedures for specific work undertaken Risk assessment for specific work undertaken Workplace inspection schedule for duration of contract OHS consultative processes to be followed Emergency procedures for specific contract Incident recording and investigation procedures Health and safety performance monitoring arrangements to be implemented during contract	
Signed	·	
Name:		
Positio	າ:	

SCHEDULE I CONTRACTORS' ESTIMATED MONTHLY EXPENDITURE

The tenderer shall state his estimated value of the work to be completed every month, based on his preliminary programme and his tendered unit rates, in the table below.

MONTH NO).	VALUE
1:	R	
2:	R	
3:	R	
4:	R	
5:	R	
6:	R	
7:	R	
8:	R	
9:	R	
10:	R	
11:	R	
12:	R	
13:	R	
14:	R	
15:	R	
16:	R	
17:	R	
18:	R	
TOTAL	R	

SIGNED ON BEHALF OF TENDERER:

Note to tenderer:...

If a tenderer wishes to submit an alternative tender then this form, appropriately completed, shall be attached to the bill of quantities for the alternative proposal.

SCHEDULE J: CONTRACTOR LABOUR CONTENT

The tenderer shall complete the table below to reflect the labour force anticipated to be employed on this contract, including labour employed by sub-contractors.

The specified minimum target value is 15% of Tendered Sum

TYPE OF LABOUR	MAN-HOURS	TOTAL WAGE COST (EXCL. VAT)
Permanent Labour		
Temporary Labour		
SMME/BEE's Labour		
	TOTAL	
	PERCENTAGE (%)	

Note to tenderer: Labour is defined as hourly paid personnel

SIGNED ON BEHALF OF THE TENDERER:

PART A INVITATION TO BID YOU ARE HEREBY INVITED TO BID FOR REQUIREMENTS OF THE TSWELOPELE LOCAL MUNICIPALITY

TOO AIL HEILE	BI INVITED TO BID TOK KEG	OINCEMENTO OF THE	TOWLLOI LLL	LOOAL MONIO	I ALII I	
BID NUMBER:	SCM/TSW/14/2025-2026.	CLOSING DATE:	01 December 20)25 CLO	SING TIME:	12h00
DESCRIPTION	APPOINTMENT OF A CONTRACTOR RETROFITTING OF 6 SEWER PUMP STATIONS, INSTALLATION OF INLINE GRINDERS AND REPAIRS TO WASTE WATER TREATMENT PLANT IN HOOPSTAD AND TIKWANA. CIDB GRADING: 6ME OR HIGHER					
THE SUCCESSF	UL BIDDER WILL BE REQUIR	ED TO FILL IN AND	SIGN A WRITTEN	CONTRACT F	ORM (MBD7).	
BID RESPONSE DOCUMENTS MAY BE DEPOSITED IN THE BID BOX SITUATED AT (STREET ADDRESS)						
SUPPLIER INFO	RMATION					
NAME OF BIDDE	R					
POSTAL ADDRE	SS					
STREET ADDRE	SS					
TELEPHONE NU	MBER	CODE		NUMBER		
CELLPHONE NU	MBER	1		1	1	
FACSIMILE NUM	BER	CODE		NUMBER		
E-MAIL ADDRES	S	'		1	1	
VAT REGISTRAT	TION NUMBER					
TAX COMPLIANO	CE STATUS	TCS PIN:	OR	CSD No:		

RETROFITTING OF 6 sewer pump stations , INSTALLATION OF INLINE GRINDERS AND REPAIRS TO WASTE WATER TREATMENT PLANT IN HOOPSTAD AND TIKWANA

RETURNABLE SCHEDULE

1. ARE YOU THE ACCREDITED REPRESENTATIVE IN SOUTH AFRICA FOR THE GOODS /SERVICES /WORKS OFFERED?	☐Yes ☐]No OF]	SUPPLIE GOODS	ARE YOU A N BASED ER FOR THE /SERVICES S OFFERED?	☐Yes	□No WER PART B:3]
3. TOTAL NUMBER OF ITEMS OFFERED			4. PRICE	TOTAL BID	R	
5. SIGNATURE OF BIDDER			6.	DATE		
7. CAPACITY UNDER WHICH THIS BID IS SIGNED						
BIDDING PROCEDURE ENQUIRIES MAY BE	DIRECTED TO:	TECHN	ICAL INFO	ORMATION MAY B	E DIRECTED 1	ГО:
DEPARTMENT		CONTA	CT PERS	ON		
CONTACT PERSON		TELEPH	HONE NUM	MBER		
TELEPHONE NUMBER		FACSIN	IILE NUME	BER		
FACSIMILE NUMBER		E-MAIL	ADDRESS	3		
E-MAIL ADDRESS						

DECLARATION OF INTEREST

- 1. Any legal person, including persons employed by the state¹, or persons having a kinship with persons employed by the state, including a blood relationship, may make an offer or offers in terms of this invitation to bid (includes an advertised competitive bid, a limited bid, a proposal or written price quotation). In view of possible allegations of favouritism, should the resulting bid, or part thereof, be awarded to persons employed by the state, or to persons connected with or related to them, it is required that the bidder or his/her authorised representative declare his/her position in relation to the evaluating/adjudicating authority where-
 - the bidder is employed by the state; and/or
 - the legal person on whose behalf the bidding document is signed, has a relationship with persons/a person who are/is involved in the evaluation and or adjudication of the bid(s), or where it is known that such a relationship exists between the person or persons for or on whose behalf the declarant acts and persons who are involved with the evaluation and or adjudication of the bid.
- 2. In order to give effect to the above, the following questionnaire must be completed and submitted with the bid.

2.1	Full Name of bidder or his or her representative
2.2	Identity Number:
2.3	Position occupied in the Company (director, trustee, shareholder², member):
2.4	Registration number of company, enterprise, close corporation, partnership agreement or trust:
2.5	Tax Reference Number:
2.6	VAT Registration Number

1"State" means -

2.6.1

The names of all directors / trustees / shareholders / members, their individual identity numbers, tax reference numbers and, if applicable, employee / PERSAL numbers must be indicated in

paragraph 3 below.

⁽a) any national or provincial department, national or provincial public entity or constitutional institution within the meaning of the Public Finance Management Act, 1999 (Act No. 1 of 1999);

⁽b) any municipality or municipal entity;

⁽c) provincial legislature;

⁽d) national Assembly or the national Council of provinces; or

⁽e) Parliament.

^{2"}Shareholder" means a person who owns shares in the company and is actively involved in the management of the enterprise or business and exercises control over the enterprise.

2.7	Are you or any person connected with the bidder presently employed by the state?	YES / NO
2.7.1	If so, furnish the following particulars:	
	Name of person / director / trustee / shareholder/ membe Name of state institution at which you or the person connected to the bidder is employed : Position occupied in the state institution:	r
	Any other particulars:	
2.7.2	If you are presently employed by the state, did you obtain the appropriate authority to undertake remunerative work outside employment in the public sector?	YES / NO
2.7.2.1	If yes, did you attach proof of such authority to the bid document?	YES / NO
	(Note: Failure to submit proof of such authority, where applicable, may result in the disqualification of the bid.	
2.7.2.2	If no, furnish reasons for non-submission of such proof:	
2.8	Did you or your spouse, or any of the company's directors trustees / shareholders / members or their spouses condubusiness with the state in the previous twelve months?	
2.8.1	If so, furnish particulars:	
		····· ····
2.9	Do you, or any person connected with the bidder, have any relationship (family, friend, other) with a person employed by the state and who may be involved with the evaluation and or adjudication of this bid?	YES / NO
2.9.1	If so, furnish particulars:	
2.10	Are you, or any person connected with the bidder, aware of any relationship (family, friend, other) between any other bidder and any person employed by the state who may be involved with the evaluation and or adjudicat of this bid?	YES/NO
2.10.1	If so, furnish particulars.	

2.11	Do you or any of the directors / trustees / shareholders / members of the company have any interest in any other related companies whether or not they are bidding for this contract?			
2.11.1	If so, furnish partic			
3.	Full details of dire	ectors / trustees / membe	rs / shareholders.	
	Full Name	Identity Number	Personal Income Tax Reference Number	State Employee Number / Persal Number
	DEGL 4 D 4 T 10 W			
4.	CERTIFY THAT T	THE INFORMATION FURN	NISHED IN PARAGRAPHS MAY REJECT THE BID OF BE FALSE.	2 and 3 ABOVE IS
		gnature		Date
	Po	osition		Name of bidder

DECLARATION FOR PROCUREMENT ABOVE R10 MILLION (ALL APPLICABLE TAXES INCLUDED)

For all procurement expected to exceed R10 million (all applicable taxes included), bidders must complete the following questionnaire:

1	Are you by law required to prepare annual financial statements for auditing?	
1.1	If yes, submit audited annual financial statements for the past three years or since the date of establishment if established during the past three years.	*YES / NO
2	Do you have any outstanding undisputed commitments for municipal services towards any municipality for more than three months or any other service provider in respect of which payment is overdue for more than 30 days?	
2.1	If no, this serves to certify that the bidder has no undisputed commitments for municipal services towards any municipality for more than three months or other service provider in respect of which payment is overdue for more than 30 days.	
2.2	If yes, provide particulars.	
* Dele	te if not applicable *YES / No	0

T2.2 - 53

RETURNABLE SCHEDULE

3	Has any contract been awarded to you state during the past five years, includ any material non-compliance or disput execution of such contract?	ling particulars of	*YES / NO
3.1	If yes, furnish particulars		
4.	Will any portion of goods or services be the Republic, and, if so, what portion a of payment from the municipality / mur transferred out of the Republic?	and whether any portion	*YES / NO
4.1	If yes, furnish particulars		
		CERTIFICATION	
	I, THE UNDERSIGNED (NAME)		
	CERTIFY THAT THE INFORMATION CORRECT.	N FURNISHED ON THIS DECI	LARATION FORM IS
	I ACCEPT THAT THE STATE MAY AC TO BE	T AGAINST ME SHOULD THIS D	ECLARATION PROVE
	FALSE.		
	Signature		Date
	Position		Name of Bidder

MBD 6.1

PREFERENCE POINTS CLAIM FORM IN TERMS OF THE PREFERENTIAL PROCUREMENT REGULATIONS 2022

This preference form must form part of all bids invited. It contains general information and serves as a claim form for preference points for Broad-Based Black Economic Empowerment (B-BBEE) Status Level of Contribution

NB: BEFORE COMPLETING THIS FORM, BIDDERS MUST STUDY THE GENERAL CONDITIONS, DEFINITIONS AND DIRECTIVES APPLICABLE IN RESPECT OF B-BBEE, AS PRESCRIBED IN THE PREFERENTIAL PROCUREMENT REGULATIONS, 2022.

1. GENERAL CONDITIONS

- 1.1 The following preference point systems are applicable to all bids:
 - the 80/20 system for requirements with a Rand value of up to R50 000 000 (all applicable taxes included); and
 - the 90/10 system for requirements with a Rand value above R50 000 000 (all applicable taxes included).
- a) The value of this bid is estimated to exceed/not exceed R50 000 000 (all applicable taxes included) and therefore the preference point system shall be applicable; or
 b) Either the 80/20 or 90/10 preference point system will be applicable to this tender (delete whichever is not applicable for this tender)
- 1.3 Preference points for this bid shall be awarded for:
 - (a) Price: and
 - (b) Specific Goals.
- 1.4 The maximum points for this bid are allocated as follows:

	POINTS
PRICE	80
SPECIFIC GOALS	20
Total points for Price and Specific Goals must not exceed	100

- 1.5 Failure on the part of a tenderer to submit proof or documentation required in terms of this tender to claim points for specific goals with the tender, will be interpreted to mean that preference points for specific goals are not claimed.
- 1.6 The organ of state reserves the right to require of a tenderer, either before a tender is adjudicated or at any time subsequently, to substantiate any claim in regard to preferences, in any manner required by the organ of state.

2. DEFINITIONS

- (a) "tender" means a written offer in the form determined by an organ of state in response to an
 invitation to provide goods or services through price quotations, competitive tendering process
 or any other method envisaged in legislation;
- (b) "price" means an amount of money tendered for goods or services, and includes all applicable taxes less all unconditional discounts;
- (c) "rand value" means the total estimated value of a contract in Rand, calculated at the time of bid invitation, and includes all applicable taxes;
- (d) "tender for income-generating contracts" means a written offer in the form determined by an organ of state in response to an invitation for the origination of income-generating contracts through any method envisaged in legislation that will result in a legal agreement between the organ of state and a third party that produces revenue for the organ of state, and includes, but is not limited to, leasing and disposal of assets and concession contracts, excluding direct sales and disposal of assets through public auctions; and
- (e) "the Act" means the Preferential Procurement Policy Framework Act, 2000 (Act No. 5 of 2000). bid invitations, and includes all applicable taxes.

3. POINTS AWARDED FOR PRICE

3.1 THE 80/20 OR 90/10 PREFERENCE POINT SYSTEMS

A maximum of 80 or 90 points is allocated for price on the following basis:

80/20 or 90/10

$$Ps = 80 \left(1 - \frac{Pt - P\min}{P\min} \right) \qquad \text{or} \qquad Ps = 90 \left(1 - \frac{Pt - P\min}{P\min} \right)$$

Where

Ps = Points scored for comparative price of bid under consideration

Pt = Price of bid under consideration

Pmin = Price of lowest acceptable bid

3. 4. POINTS AWARDED FOR SPECIFIC GOALS

- 3.1. In terms of Regulation 4(2); 5(2); 6(2) and 7(2) of the Preferential Procurement Regulations, preference points must be awarded for specific goals stated in the tender. For the purposes of this tender the tenderer will be allocated points based on the goals stated in table 1 below as may be supported by proof/ documentation stated in the conditions of this tender:
- 3.2. In cases where organs of state intend to use Regulation 3(2) of the Regulations, which states that, if it is unclear whether the 80/20 or 90/10 preference point system applies, an organ of state must, in the tender documents, stipulate in the case of—
 - (a) an invitation for tender for income-generating contracts, that either the 80/20 or 90/10 preference point system will apply and that the highest acceptable tender will be used to determine the applicable preference point system; or
 - (b) any other invitation for tender, that either the 80/20 or 90/10 preference point system will apply and that the lowest acceptable tender will be used to determine the applicable preference point system,

then the organ of state must indicate the points allocated for specific goals for both the 90/10

and 80/20 preference point system.

Table 1: Specific goals for the tender and points claimed are indicated per the table below.

(Note to organs of state: Where either the 90/10 or 80/20 preference point system is applicable, corresponding points must also be indicated as such.

Note to tenderers: The tenderer must indicate how they claim points for each preference point system.)

The specific goals allocated points in terms of this tender	Number of points allocated (90/10 system) (To be completed by the organ of state)	Number of points allocated (80/20 system) (To be completed by the organ of state)	Number of points claimed (90/10 system) (To be completed by the tenderer)	Number of points claimed (80/20 system) (To be completed by the tenderer)

8	DECLARATION WITH REGARD TO COMPANY/FIRM		
8.1	Name of company firm	·	
8.2	VAT registration number	<u></u>	

8.3	Compar	y registra	ation number:
8.4	TYPE O	F COMP	ANY/ FIRM
TICK	One per	son busir orporatior ny nited	Venture / Consortium ness/sole propriety
8.5	DESCR	IBE PRIN	ICIPAL BUSINESS ACTIVITIES
8.6	Manufactor Supplier Profession Other se	cturer onal serv	SSIFICATION vice provider viders, e.g. transporter, etc. BOX]
8.7	Municipa Register	ality wher	DRMATION re business is situated unt Number
8.8	Total nu	mber of y	vears the company/firm has been in business:
8.9	certify the paragra	nat the population	gned, who is / are duly authorised to do so on behalf of the company/firm, bints claimed, based on the B-BBE status level of contribution indicated in and 6.1 of the foregoing certificate, qualifies the company/ firm for the bwn and I / we acknowledge that:
	(i)	The inf	formation furnished is true and correct;
	(ii)	-	eference points claimed are in accordance with the General Conditions as ed in paragraph 1 of this form.
	(iii)	paragr	event of a contract being awarded as a result of points claimed as shown in aph 1.4 and 6.1, the contractor may be required to furnish documentary proof satisfaction of the purchaser that the claims are correct;
	(iv)	fraudu	B-BBEE status level of contributor has been claimed or obtained on a lent basis or any of the conditions of contract have not been fulfilled, the ser may, in addition to any other remedy it may have –
		(a)	disqualify the person from the bidding process;
		(b)	recover costs, losses or damages it has incurred or suffered as a result of that person's conduct;
		(c)	cancel the contract and claim any damages which it has suffered as a result of having to make less favourable arrangements due to such cancellation;

- (d) recommend that the bidder or contractor, its shareholders and directors, or only the shareholders and directors who acted on a fraudulent basis, be restricted by the National Treasury from obtaining business from any organ of state for a period not exceeding 10 years, after the audi alteram partem (hear the other side) rule has been applied; and
- (e) forward the matter for criminal prosecution

WITNESSES:	
1	
	SIGNATURE(S) OF BIDDER(S)
2	
	DATE:
	100000
	ADDRESS:

DECLARATION OF BIDDER'S PAST SUPPLY CHAIN MANAGEMENT PRACTICES

- 1. This Municipal Bidding Document must form part of all bids invited.
- 2. It serves as a declaration to be used by institutions in ensuring that when goods and services are being procured, all reasonable steps are taken to combat the abuse of the supply chain management system.
- 3. The bid of any bidder may be disregarded if that bidder, or any of its directors have
 - a) abused the institution's supply chain management system;
 - b) committed fraud or any other improper conduct in relation to such system; or
 - c) Failed to perform on any previous contract.
- In order to give effect to the above, the following questionnaire must be completed and submitted with the bid.

Item	Question	Yes	No
4.1	Is the bidder or any of its directors listed on the National Treasury's Database of Restricted	Yes	No
	Suppliers as companies or persons prohibited from doing business with the public sector? (Companies or persons who are listed on this Database were informed in writing of		
	this restriction by the Accounting Officer/Authority of the institution that imposed		Ш
	the restriction after the <i>audialterampartem</i> rule was applied)		
	The Database of Restricted Suppliers now resides on the National Treasury's website (www.treasury.gov.za) and can be accessed by clicking on its link at the bottom of the		
	home page.		
	. •		
4.1.1	If so, furnish particulars		
4.2	Is the bidder or any of its directors listed on the Register for Tender Defaulters in terms of	Yes	No
	section 29 of the Prevention and Combating of Corrupt Activities Act (No 12 of 2004)?		
	The Register for Tender Defaulters can be accessed on the National Treasury's		Ш
	website (www.treasury.gov.za) by clicking on its link at the bottom of the home		
	page.		
4.2.1	If so, furnish particulars:		
4.3	Was the bidder or any of its directors convicted by a court of law (including a court outside	Yes	No
	of the Republic of South Africa) for fraud or corruption during the past five years?		
4.3.1	If so, furnish particulars:		
4.4	Was any contract between the bidder and any organ of state terminated during the past	Yes	No
7.7	five years on account of failure to perform on or comply with the contract?		
4.4.1	If so, furnish particulars:		

RETURNABLE SCHEDULE

MBD 8

CERTIFICATION

I, THE UNDERSIGNED (FULL NAME) THAT THE INFORMATION FURNISHED ON THIS I I ACCEPT THAT, IN ADDITION TO CANCELLATION AGAINST ME SHOULD THIS DECLARATION PRO	DECLARATION FORM IS TRUE AND CORRECT. ON OF A CONTRACT, ACTION MAY BE TAKEN
Signature	Date
Position	Name of Bidder

Js365bW

CERTIFICATE OF INDEPENDENT BID DETERMINATION

- 1. This Municipal Bidding Document (MBD) must form part of all bids¹ invited.
- 2. Section 4 (1) (b) (iii) of the Competition Act No. 89 of 1998, as amended, prohibits an agreement between, or concerted practice by, firms, or a decision by an association of firms, if it is between parties in a horizontal relationship and if it involves collusive bidding (or bid rigging).² Collusive bidding is a per se prohibition meaning that it cannot be justified under any grounds.
- 3. Treasury Regulation 16A9 prescribes that accounting officers and accounting authorities must take all reasonable steps to prevent abuse of the supply chain management system and authorizes accounting officers and accounting authorities to:
- a) disregard the bid of any bidder if that bidder, or any of its directors have abused the institution's supply chain management system and or committed fraud or any other improper conduct in relation to such system.
- cancel a contract awarded to a supplier of goods and services if the supplier committed any corrupt or fraudulent act during the bidding process or the execution of that contract.
- 4. This MBD serves as a certificate of declaration that would be used by institutions to ensure that, when bids are considered, reasonable steps are taken to prevent any form of bid-rigging.
- 5. In order to give effect to the above, the attached Certificate of Bid Determination (MBD 9) must be completed and submitted with the bid:

¹ Includes price quotations, advertised competitive bids, limited bids and proposals.

² Bid rigging (or collusive bidding) occurs when businesses, that would otherwise be expected to compete, secretly conspire to raise prices or lower the quality of goods and / or services for purchasers who wish to acquire goods and / or services through a bidding process. Bid rigging is, therefore, an agreement between competitors not to compete.

CERTIFICATE OF INDEPENDENT BID DETERMINATION

I, the undersigned, in submitting the accompa	nying bid:
(Bid Number a	and Description)
in response to the invitation for the bid made t	ру:
(Name of	Institution)
do hereby make the following statements that respect:	I certify to be true and complete in every
I certify, on behalf	
of:	that:
(Name o	of Bidder)

- 1. I have read and I understand the contents of this Certificate;
- 2. I understand that the accompanying bid will be disqualified if this Certificate is found
 - to be true and complete in every respect;
- 3. I am authorized by the bidder to sign this Certificate, and to submit the accompanying bid, on behalf of the bidder;
- 4. Each person whose signature appears on the accompanying bid has been authorized by
 - the bidder to determine the terms of, and to sign the bid, on behalf of the bidder;
- 5. For the purposes of this Certificate and the accompanying bid, I understand that the word "competitor" shall include any individual or organization, other than the bidder, whether or not affiliated with the bidder, who:
- a) has been requested to submit a bid in response to this bid invitation; could potentially submit a bid in response to this bid invitation, based on
- b) their qualifications, abilities or experience; and
- c) provides the same goods and services as the bidder and/or is in the same line of business as the bidder
- 6. The bidder has arrived at the accompanying bid independently from, and without consultation, communication, agreement or arrangement with any competitor. However communication between partners in a joint venture or consortium³ will not be
 - construed
 - as collusive bidding.
- 7. In particular, without limiting the generality of paragraphs 6 above, there has been no consultation, communication, agreement or arrangement with any competitor regarding:
 - a) prices:
 - b) geographical area where product or service will be rendered (market allocation)
 - c) methods, factors or formulas used to calculate prices;
 - d) the intention or decision to submit or not to submit, a bid;

- e) the submission of a bid which does not meet the specifications and conditions of the bid; or
- f) bidding with the intention not to win the bid.
- 8. In addition, there have been no consultations, communications, agreements or arrangements with any competitor regarding the quality, quantity, specifications and conditions or delivery particulars of the products or services to which this bid invitation relates.
- The terms of the accompanying bid have not been, and will not be, disclosed by the tenderers, directly or indirectly, to any competitor, prior to the date and time of the official
 - bid opening or of the awarding of the contract.
 - ³ Joint venture or Consortium means an association of persons for the purpose of combining their expertise, property, capital, efforts, skill and knowledge in an activity for the execution of a contract.
- 10. I am aware that, in addition and without prejudice to any other remedy provided to combat any restrictive practices related to bids and contracts, bids that are suspicious will be reported to the Competition Commission for investigation and possible imposition of administrative penalties in terms of section 59 of the Competition Act No 89 of 1998 and or may be reported to the National Prosecuting Authority (NPA) for criminal investigation and or may be restricted from conducting business with the public sector for a period not exceeding ten (10) years in terms of the Prevention and Combating of Corrupt Activities Act No 12 of 2004 or any other applicable legislation.

Signature Date	 	
J		
Position Name of Bidder		

PART C1

AGREEMENT AND CONTRACT DATA

AGREEMENT AND CONTRACT DATA

C1 AGREEMENT AND CONTRACT DATA

C1.1 FORM OF OFFER AND ACCEPTANCE

OFFER

The Employer, identified in the acceptance signature block, has solicited offers to enter into a contract for the procurement of:

Project Name: RETROFITTING OF 6 sewer pump stations, INSTALLATION OF INLINE GRINDERS AND REPAIRS TO WASTE WATER TREATMENT PLANT IN HOOPSTAD AND TIKWANA

The tenderer, identified in the offer signature block, has examined the documents listed in the Tender Data and addenda thereto as listed in the returnable schedules, and by submitting this offer has accepted the conditions of tender.

By the representative of the tenderer, deemed to be duly authorized, signing this part of this form of offer and acceptance, the tenderer offers to perform all of the obligations and liabilities of the contractor under the contract including compliance with all its terms and conditions according to their true intent and meaning for an amount to be determined in accordance with the Conditions of Contract identified in the Contract Data.

THE OFFEDER TOTAL OF THE PRICES INCLUSIVE OF VALUE ARRED TAY IS:

		Rands (in
words);		·
R		(in figures)
and acceptan	ce and returning one copy of lity stated in the Tender Data,	er by signing the acceptance part of this form of offer this document to the tenderer before the end of the whereupon the tenderer becomes the party named act identified in the Contract Data.
Signature		
Date		
Name		
Capacity		
FOR THE TE	NDERER	
(Name and ad	ddress of organization)	
Name and sig	nature of witness	

Site information

AGREEMENT AND CONTRACT DATA

ACCEPTANCE

Part C4:

By signing this part of this form of offer and acceptance, the Employer identified below accepts the tenderer's offer. In consideration thereof, the Employer shall pay the contractor the amount due in accordance with the Conditions of Contract identified in the Contract Data. Acceptance of the tenderer's offer shall form an agreement between the Employer and the tenderer upon the terms and conditions contained in this agreement and in the contract that is the subject of this agreement. The terms of the contract, are contained in:

Part C1:	Agreements and Contract Data, (which includes this agreement)
Part C2:	Pricing data
Part C3:	Scope of work.

Deviations from and amendments to the documents listed in the Tender Data and any addenda thereto as listed in the tender schedules as well as any changes to the terms of the offer agreed by the tenderer and the Employer during this process of offer and acceptance, are contained in the schedule of deviations attached to and forming part of this agreement. No amendments to or deviations from said documents are valid unless contained in this schedule.

The tenderer shall within two weeks after receiving a completed copy of this agreement, including the schedule of deviations (if any), contact the Employer's agent (whose details are given in the Contract Data) to arrange the delivery of any bonds, guarantees, proof of insurance and any other documentation to be provided in terms of the Conditions of Contract identified in the Contract Data. Failure to fulfil any of these obligations in accordance with those terms shall constitute a repudiation of this agreement.

Notwithstanding anything contained herein, this agreement comes into effect on the date when the tenderer receives one fully completed original copy of this document, including the schedule of deviations (if any). Unless the tenderer (now contractor) within five working days of the date of such receipt notifies the Employer in writing of any reason why he cannot accept the contents of this agreement, this agreement shall constitute a binding contract between the parties.

Signature		Date	 	
Name				
Capacity				
FOR THE EN	IPLOYER			
Name and sig	gnature of witness		 	
Date			 	

RETROFITTING OF 6 sewer pump stations, INSTALLATION OF INLINE GRINDERS AND REPAIRS TO WASTE WATER TREATMENT PLANT IN HOOPSTAD AND TIKWANA

AGREEMENT AND CONTRACT DATA

Schedule of Deviations (To be filled in if there are any Deviations or Alternatives accepted)				
1.	Subject	:		
	Details	<u>:</u>		
2.	Subject	:		
	Details	<u>:</u>		
3.	Subject	:		
	Details	:		
4.	Subject	:		
	Details	:		
5.	Subject	:		
	Details	:		

By the duly authorised representatives signing this agreement, the Employer and the tenderer agree to and accept the foregoing schedule of deviations as the only deviations from and amendments to the documents listed in the Tender Data and addenda thereto as listed in the tender schedules, as well as any confirmation, clarification or changes to the terms of the offer agreed by the tenderer and the Employer during this process of offer and acceptance.

It is expressly agreed that no other matter whether in writing, oral communication or implied during the period between the issue of the tender documents and the receipt by the tenderer of a completed signed copy of this Agreement shall have any meaning or effect in the contract between the parties arising from this agreement.

RETROFITTING OF 6 sewer pump stations, INSTALLATION OF INLINE GRINDERS AND REPAIRS TO WASTE WATER TREATMENT PLANT IN HOOPSTAD AND TIKWANA

AGREEMENT AND CONTRACT DATA

(To be signed	only if there are any Dev	iations listed above)		
Signature			Date	
Name				
Capacity				
FOR THE TE	NDERER			
(Name and a	ddress of organization)			
Name and sig	gnature of witness			
Date				
Signature				
Date				
Name				
Capacity				
FOR THE EN	IPLOYER			
Name and sig	gnature of witness			
Date				

C1.2 CONTRACT DATA

The General Conditions of Contract for Construction Works (2010) published by the South African Institution of Civil Engineering, Second Edition, Print 3.1, is applicable to this contract.

Copies of these General Conditions of Contract may be obtained from the South African Institution of Civil Engineering:

Block 19, Thornhill Office Park Bekker Street, Vorna Valley, Midrand.

Private Bag X200, Halfway House. 1685

Tel: 011-805 5947 Fax: 011-805 5971

C1.2.1 CONTRACT SPECIFIC DATA.

The following contracts data are applicable to this contract:

REFERENCE TO:	CLAUSE.	DATA
Contractor.	1.1.1.9	To be appointed by Tswelopele Local Municipality
Defect liability Period	1.1.1.13	The defect liability period shall be 12 months. This includes 4 comprehensive maintenance visits on the works.
Due Completion Date	1.1.1.14	The Works shall be completed within 4 months Excluding year-end holiday as envisaged by the employer.
Employer.	1.1.1.15	Tswelopele Local Municipality
Contract Cessions	5.1	Contract Cessions will be approved by the Employer on this Project
Sub-Contracting 4.4		The appointed contractor will go out on tender to appoint local sub contractors with CIDB grading of 2 or 3 CE/GB/ME. The main contractor will allocate works worth 3 or 4 CE/GB/ME to the local sub contractor and will be required to assist the local contractor to upgrade their grading and as well as mentor the contractor throughout construction. This requirement will be added as an item on the bill to ensure effective implementation of local contractor development.
Documentation Required Before Commencement with Works	5.3.1	The Works are to be commenced within twenty one (21) days of the Commencement Date. The documents required before commencement with the Works execution are: Initial Programme (clause 5.6); Insurance (clause 8.6); and Health and safety plan (clause 4.3);
Submission of documents required in clause 5.3.1	5.3.2	The time to submit the documentation required before commencement with the Works execution is 21 days.

REFERENCE TO:	CLAUSE.	DATA		
Special Non-working days	5.8.1	The special non-working days are public holidays		
Penalty for delay	5.13.1	0.05% of the contract value per day		
Liability for any Latent Defects	5.16.3	The latent defect period is 10 years.		
Contract Guarantee	6.2.3	Within 14 days after appointment letter has been issued.		
Guarantee Sum	6.2.1/6.2.2	10% of the Contract Value		
Percentage Allowances	6.5.1.2.3	The percentage allowances shall be 7%.		
Time for Completion	5.6.2.1	4 months from Commencement Date EXCLUDING YEAR END BREAK		
Contract Price Adjustment	6.8.2	Refer to Page T2.2-51 on price adjustments formula applicable.		
Special Material	6.8.3	There are no special materials in this contract.		
Dispute Resolution	10.5.1	Adjudication or arbitration and the court will be acceptable		
Biopate Resolution	10.5.3	to resolve disputes.		

Signature	Date
Position	Name of bidder

C1.2.2 DATA PROVIDED BY THE CONTRACTOR

Clause 6.8.3 of the GCC:

Special Materials	Unit on which variation will be determined*	Price (ex-factory) for the base month (exc. Vat)**

Notes:

- * Indicate whether the material will be delivered in bulk or in containers.
- ** The price for special materials is only the price for the material ex-factory and does not include the cost of transport, labour or any other costs. When called upon to do so, the tenderer shall substantiate the above prices with acceptable documentary evidence for the base month and the month in which the increase is claimed.

RETROFITTING OF 6 sewer pump stations, INSTALLATION OF INLINE GRINDERS AND REPAIRS TO WASTE WATER TREATMENT PLANT IN HOOPSTAD AND TIKWANA

AGREEMENT AND CONTRACT DATA

Signature	Date
Position	Name of bidder

C1.2.3 EPWP SPECIFIC CONDITIONS OF CONTRACT.

NOTE THAT THIS PROJECT HAS NOT BEEN REGISTERED AS AN EPWP PROJECT, BUT WILL BE EXECUTED ACCORDING TO THE EPWP PRINCIPLES, SAVE FOR THE HOURLY LABOUR RATES WHICH SHALL BE AS PER THE CIVIL ENGINEERING WORKS DETERMINATION, GOVERNMENT GAZETTE 35634 OF 28 AUGUST 2012, AS REVISED FROM TIME TO TIME, AND WHICH LATEST REVISION SHALL APPLY FOR THIS PROJECT. THE LABOUR RATES REFERRED TO IN THIS PARAGRAPH SHALL SUPERSEDE ALL OTHER RATES THAT MAY BE DIRECTLY OR INDIRECTLY INFERRED FROM OTHER SECTIONS AND PARAGRAPHS OF THIS DOCUMENT.

Payment for the labour-intensive component of the works

Payment for works identified in the Scope of Work as being labour-intensive shall only be made in accordance with the provisions of the Contract if the works are constructed strictly in accordance with the provisions of the Scope of Work. Any non-payment for such works shall not relieve the Contractor in any way from his obligations either in contract or in delict.

Applicable labour laws

The Ministerial Determination, Extended Public Works Programmes, issued in terms of the Basic Conditions of Employment Act of 1997 by the Minister of Labour in Government Notice N° R63 of 25 January 2002, as reproduced below, shall apply to works described in the scope of work as being labour intensive and which are undertaken by unskilled or semi-skilled workers.

1. Introduction

- 1.1 This document contains the standard terms and conditions for workers employed in elementary occupations on an Extended Public Works Programme (EPWP). These terms and conditions do NOT apply to persons employed in the supervision and management of an EPWP.
- 1.2 In this document -
 - (a) "Department" means any department of the State, implementing agent or contractor;
 - (b) "employer" means any department, implementing agency or contractor that hires workers to work in elementary occupations on an EPWP;
 - (c) "Worker" means any person working in an elementary occupation on an EPWP;
 - (d) Elementary occupation" means any occupation involving unskilled or semi-skilled work;
 - (e) "Management" means any person employed by a department or implementing agency to administer or execute an EPWP;
 - (f) "Task" means a fixed quantity of work;
 - (g) "task-based work" means work in which a worker is paid a fixed rate for performing a task;
 - (h) "task-rated worker" means a worker paid on the basis of the number of tasks completed;
 - (i) "time-rated worker" means a worker paid on the basis of the length of time worked.

2. Terms of Work

2.1 Workers on an EPWP are employed on a temporary basis.

- 2.2 A worker may NOT be employed for longer than 24 months in any five-year cycle on an EPWP
- 2.3 Employment on an EPWP does not qualify as employment as a contributor for the purposes of the Unemployment Insurance Act 30 of 1966.

3. Normal Hours of Work

- 3.1 An employer may not set tasks or hours of work that require a worker to work-
 - (a) More than forty hours in any week
 - (b) On more than five days in any week; and
 - (c) For more than eight hours on any day.
- 3.2 An employer and worker may agree that a worker will work four days per week. The worker may then work up to ten hours per day.
- 3.3 A task-rated worker may not work more than a total of 55 hours in any week to complete the tasks allocated (based on a 40-hour week) to that worker.

4 Meal Breaks

- 4.1 A worker may not work for more than five hours without taking a meal break of at least thirty minutes duration.
- 4.2 An employer and worker may agree on longer meal breaks.
- 4.3 A worker may not work during a meal break. However, an employer may require a worker to perform duties during a meal break if those duties cannot be left unattended and cannot be performed by another worker. An employer must take reasonable steps to ensure that a worker is relieved of his or her duties during the meal break.
- 4.4 A worker is not entitled to payment for the period of a meal break. However, a worker who is paid on the basis of time worked must be paid if the worker is required to work or to be available for work during the meal break.

5 Special Conditions for Security Guards

- 5.1 A security guard may work up to 55 hours per week and up to eleven hours per day.
- 5.2 A security guard who works more than ten hours per day must have a meal break of at least one hour or two breaks of at least 30 minutes each.

6 Daily Rest Period

Every worker is entitled to a daily rest period of at least eight consecutive hours. The daily rest period is measured from the time the worker ends work on one day until the time the worker starts work on the next day.

7 Weekly Rest Period

Every worker must have two days off every week. A worker may only work on their day off to perform work which must be done without delay and cannot be performed by workers during their ordinary hours of work ("emergency work").

8 Work on Sundays and Public Holidays

8.1 A worker may only work on a Sunday or public holiday to perform emergency or security work.

- 8.2 Work on Sundays is paid at the ordinary rate of pay.
- 8.3 A task-rated worker who works on a public holiday must be paid -
 - (a) The worker's daily task rate, if the worker works for less than four hours;
 - (b) Double the worker's daily task rate, if the worker works for more than four hours.
- 8.4 A time-rated worker who works on a public holiday must be paid -
 - (a) The worker's daily rate of pay, if the worker works for less than four hours on the public holiday
 - (b) Double the worker's daily rate of pay, if the worker works for more than four hours on the public holiday.

9 Sick Leave

- 9.1 Only workers who work four or more days per week have the right to claim sick pay in terms of this clause.
- 9.2 A worker who is unable to work on account of illness or injury is entitled to claim one day's paid sick leave for every full month that the worker has worked in terms of a contract.
- 9.3 A worker may accumulate a maximum of twelve days' sick leave in a year.
- 9.4 Accumulated sick-leave may not be transferred from one contract to another contract.
- 9.5 An employer must pay a task-rated worker the worker's daily task rate for a day's sick leave.
 - 9.6 An employer must pay a time-rated worker the worker's daily rate of pay for a day's sick leave.
- 9.7 An employer must pay a worker sick pay on the worker's usual payday.
- 9.8 Before paying sick-pay, an employer may require a worker to produce a certificate stating that the worker was unable to work on account of sickness or injury if the worker is –
 - (a) Absent from work for more than two consecutive days; or
 - (b) Absent from work on more than two occasions in any eight-week period.
- 9.9 A medical certificate must be issued and signed by a medical practitioner, a qualified nurse or a clinic staff member authorised to issue medical certificates indicating the duration and reason for incapacity.
- 9.10 A worker is not entitled to paid sick-leave for a work-related injury or occupational disease for which the worker can claim compensation under the Compensation for Occupational Injuries and Diseases Act.

10 Maternity Leave

- 10.1 A worker may take up to four consecutive months' unpaid maternity leave.
- 10.2 A worker is not entitled to any payment or employment-related benefits during maternity leave.

- 10.3 A worker must give her employer reasonable notice of when she will start maternity leave and when she will return to work.
- 10.4 A worker is not required to take the full period of maternity leave. However, a worker may not work for four weeks before the expected date of birth of her child or for six weeks after the birth of her child, unless a medical practitioner, midwife or qualified nurse certifies that she is fit to do so.
- 10.5 A worker may begin maternity leave -
 - (a) four weeks before the expected date of birth; or
 - (b) On an earlier date -
 - (i) If a medical practitioner, midwife or certified nurse certifies that it is necessary for the health of the worker or that of her unborn child; or
 - (ii) If agreed to between employer and worker; or
 - (c) On a later date, if a medical practitioner, midwife or certified nurse has certified that the worker is able to continue to work without endangering her health.
- 10.6 A worker who has a miscarriage during the third trimester of pregnancy or bears a stillborn child may take maternity leave for up to six weeks after the miscarriage or stillbirth.
- 10.7 A worker who returns to work after maternity leave, has the right to start a new cycle of twenty-four months employment, unless the EPWP on which she was employed has ended.

11 Family responsibility leave

- 11.1 Workers, who work for at least four days per week, are entitled to three days paid family responsibility leave each year in the following circumstances -
 - (a) when the employee's child is born;
 - (b) when the employee's child is sick;
 - (c) in the event of a death of -
 - (i) the employee's spouse or life partner;
 - the employee's parent, adoptive parent, grandparent, child, adopted child, grandchild or sibling.

12 Statement of Conditions

- 12.1 An employer must give a worker a statement containing the following details at the start of employment
 - (a) the employer's name and address and the name of the EPWP;
 - (b) the tasks or job that the worker is to perform; and
 - (c) the period for which the worker is hired or, if this is not certain, the expected duration of the contract;
 - (d) the worker's rate of pay and how this is to be calculated;
 - (e) the training that the worker will receive during the EPWP.

- 12.2 An employer must ensure that these terms are explained in a suitable language to any employee who is unable to read the statement.
- 12.3 An employer must supply each worker with a copy of these conditions of employment.

13 Keeping Records

- 13.1 Every employer must keep a written record of at least the following
 - (a) the worker's name and position;
 - (b) in the case of a task-rated worker, the number of tasks completed by the worker;
 - (c) in the case of a time-rated worker, the time worked by the worker;
 - (d) Payments made to each worker.
- 13.2 The employer must keep this record for a period of at least three years after the completion of the EPWP.

14 Payment

- 14.1 An employer must pay all wages at least monthly in cash or by cheque or into a bank account.
- 14.2 A task-rated worker will only be paid for tasks that have been completed.
- 14.3 An employer must pay a task-rated worker within five weeks of the work being completed and the work having been approved by the manager or the contractor having submitted an invoice to the employer.
- 14.4 A time-rated worker will be paid at the end of each month.
- 14.5 Payment must be made in cash, by cheque or by direct deposit into a bank account designated by the worker.
- 14.6 Payment in cash or by cheque must take place -
 - (a) at the workplace or at a place agreed to by the worker;
 - (b) during the worker's working hours or within fifteen minutes of the start or finish of work;
 - (b) in a sealed envelope which becomes the property of the worker.
- 14.7 An employer must give a worker the following information in writing
 - (a) the period for which payment is made;
 - (b) the numbers of tasks completed or hours worked;
 - (c) the worker's earnings;
 - (d) any money deducted from the payment;
 - (e) the actual amount paid to the worker.
- 14.8 If the worker is paid in cash or by cheque, this information must be recorded on the envelope and the worker must acknowledge receipt of payment by signing for it.

14.9 If a worker's employment is terminated, the employer must pay all monies owing to that worker within one month of the termination of employment.

15 Deductions

- 15.1 An employer may not deduct money from a worker's payment unless the deduction is required in terms of a law.
- 15.2 An employer must deduct and pay to the SA Revenue Services any income tax that the worker is required to pay.
- 15.3 An employer who deducts money from a worker's pay for payment to another person must pay the money to that person within the time period and other requirements specified in the agreement law, court order or arbitration award concerned.
- 15.4 An employer may not require or allow a worker to
 - (a) repay any payment except an overpayment previously made by the employer by mistake;
 - (b) state that the worker received a greater amount of money than the employer actually paid to the worker or
 - (c) pay the employer or any other person for having been employed.

16 Health and Safety

- 16.1 Employers must take all reasonable steps to ensure that the working environment is healthy and safe.
- 16.2 A worker must -
 - (a) work in a way that does not endanger his/her health and safety or that of any other person;
 - (b) obey any health and safety instruction;
 - (c) obey all health and safety rules of the EPWP;
 - (d) use any personal protective equipment or clothing issued by the employer;
 - (e) report any accident, near-miss incident or dangerous behaviour by another person to their employer or manager.

17 Compensation for Injuries and Diseases

- 17.1 It is the responsibility of the employers (other than a contractor) to arrange for all persons employed on a EPWP to be covered in terms of the Compensation for Occupational Injuries and Diseases Act, 130 of 1993.
- 17.2 A worker must report any work-related injury or occupational disease to their employer or manager.
- 17.3 The employer must report the accident or disease to the Compensation Commissioner.
- 17.4 An employer must pay a worker who is unable to work because of an injury caused by an accident at work 75% of their earnings for up to three months. The employer will be refunded this amount by the Compensation Commissioner. This does NOT apply to injuries caused by accidents outside the workplace such as road accidents or accidents at home.

18 Termination

- 18.1 The employer may terminate the employment of a worker for good cause after following a fair procedure.
 - 18.2 A worker will not receive severance pay on termination.
- 18.3 A worker is not required to give notice to terminate employment. However, a worker who wishes to resign should advise the employer in advance to allow the employer to find a replacement.
- 18.4 A worker who is absent for more than three consecutive days without informing the employer of an intention to return to work will have terminated the contract. However, the worker may be re-engaged if a position becomes available for the balance of the 24-month period.
- 18.5 A worker who does not attend required training events, without good reason, will have terminated the contract. However, the worker may be re-engaged if a position becomes available for the balance of the 24-month period.

19 Certificate of Service

- 19.1 On termination of employment, a worker is entitled to a certificate stating –
- (a) the worker's full name;
- (b) the name and address of the employer;
- (c) the EPWP on which the worker worked;
- (d) the work performed by the worker;
- (e) any training received by the worker as part of the EPWP;
- (f) the period for which the worker worked on the EPWP;
- (g) any other information agreed on by the employer and worker.

C1.3 BLASTING INDEMNITY

Contract No.
Given by
*Company Registration No
Address
a *Company incorporated with limited liability according to the company laws of the Republic of South Afri *Partnership, *Close Corporation, *Public Company (hereinafter called the Contractor), represented here oy in his capacity as the Contractor duly authorised hereto by a resolution of the Contractor a certified copy of which resolution is attached to the company laws of the Republic of South Afri a *Company incorporated with limited liability according to the company laws of the Republic of South Afri partnership, *Close Corporation, *Public Company (hereinafter called the Contractor), represented here oy a capacity as the Contractor and a certified copy of which resolution is attached to the company laws of the Republic of South Afri a *Company incorporated with limited liability according to the company laws of the Republic of South Afri a *Company incorporated with limited liability according to the company laws of the Republic of South Afri a *Company incorporated with limited liability according to the company laws of the Republic of South Afri a *Company incorporated with limited liability according to the company laws of the Republic of South Afri a *Company laws of the Republic of South Afri a *Company laws of the Republic of South Afri a *Company laws of the Republic of South Afri a *Company laws of the Republic of South Afri a *Company laws of the Republic of South Afri a *Company laws of the Republic of South Afri a *Company laws of the Republic of South Afri a *Company laws of the Republic of South Afri a *Company laws of the Republic of South Afri a *Company laws of the Company laws of the Republic of South Afri a *Company laws of the Company laws of the Company laws of the Republic of South African laws of the Republic of South Africa
WHEREAS the Contractor has entered into a Contract with the Tswelopele Local Municipality (hereinaf called the Company) for,
and the Company requires this Indemnity from the Contractor
NOW THEREFORE THIS DEED WITNESSETH that the Contractor does hereby indemnify and he narmless the Company in respect of all loss or damage that may be incurred or sustained by the Company reason of or in any way arising out of or caused by blasting operations that may be carried out by the Contractor in connection with the aforementioned Contract and also in respect of all claims that may be managainst the Company in consequence of such blasting operations, by reason of or in any way arising out any accidents or damage to persons, life or properly or any other cause whatsoever, and also in respect all legal or other expenses that may be incurred by the Company in examining, resisting or settling any succlaims; for the due performance of which the Contractor binds itself according to law.
THUS DONE AND SIGNED for and on behalf of the Contractor at on t
witnesses.
AS WITNESSES
1.
SIGNATURE
2.
DESIGNATION OF SIGNATORY

*Delete which does not apply

C1.4 HEALTH AND SAFETY CONTRACT: GENERAL INFORMATION

- 1. The Occupational Health and Safety Act comprises Sections 1 to 50 and all un-repealed regulations promulgated in terms of the former Machinery and Occupational Safety Act No 6 of 1983 as amended, as well as other regulations which may be promulgated in terms of the OHS Act.
- 2. 'Mandatory' is defined as including an agent, a contractor or a subcontractor for work, but without derogating from his status in his own right as an employer or user of plant and machinery.
- 3. Section 37 of the Occupational Health and Safety Act potentially punishes employers (principals) for the unlawful acts or omissions of mandataries (contractors) save where a written agreement between the parties has been concluded containing arrangements and procedures to ensure compliance with the said Aid by the mandatory.
- 4. All documents attached or referred to in the above agreement from an integral part of the agreement.
- 5. To perform in terms of this agreement mandataries must be familiar with the relevant provisions of the Act.
- 6. Mandataries who utilise the services of their own mandataries (subcontractors) are advised to conclude a similar written agreement.
- 7. Be advised that this agreement places the onus on the mandatory to contact the employer in the event of inability to perform as per this agreement. The employer, however, reserves the right to unilaterally take any steps as may be necessary to enforce this agreement.
- The contractor shall be responsible for the full and proper implementation of the terms and provisions of the Act and its regulations in the area in which the work is to be undertaken by the contractor.
- The contractor shall be responsible for the well-being, in relation to health and safety, of all persons
 coming upon or into such area in accordance with that legislation, including the implementation of
 any directives issued by management of Tswelopele Local Municipality in this respect.

10. The work to be done is	
11. The area in which the work is to be conducted is	

12. The contractor shall familiarise himself with such area and all risks existing thereon and undertakes to report to the representative of Tswelopele Local Municipality any hazard or risk to health and safety which arises during the contract work in the area concerned and over which the contractor may have no control. All necessary and appropriate safety / health equipment shall be issued by the contractor to all persons working on or coming into the area.

C1.4.1 HEALTH AND SAFETY CONTRACT BETWEEN EMPLOYER AND CONTRACTOR IN TERMS OF SECTION 37(2) OF THE OCCUPATIONAL HEALTH AND SAFETY ACT NO 85 OF 1993.

Written ag	reement between Tswelope	ele Local Municipality (hereinafter referred to as "the Employer)
and		(hereinafter referred to as "the
mandatory	") as envisaged by Section 3	37(2) of the Occupational Health and Safety Act, No. 85, of 1993
as amend	ed.	
I		representing
		(mandatory) do hereby acknowledge that
		(mandatory) is an employer in its own right and shall
be regard	ed as the employer for purp	oses of the contract work specified in the body of the principal
agreemen	t with duties as prescribed	in the Occupational Health and Safety Act, No. 85 of 1993 as
amended	so as to ensure that all worl	k will be performed or machinery and plant used in accordance
with the pr	ovisions of the said Act. I fur	thermore agree to comply with the requirements of the Employer
as contain	ed in the Occupational Healt	h and Safety Specification included with the principal agreement
and to liai	se with the employer should	d I, for whatever reason, be unable to perform in terms of this
agreemen	t.	
Signed th	is day of	at
Signature	e on behalf of mandatory	
Signature	e on behalf of Employer	
Compen	sation Fund Registration N	lo. of mandatory
Good Sta	anding Certificate :	yes □ no (tick one box)

AGREEMENT AND CONTRACT DATA

C1.4.2 OCCUPATIONAL HEALTH AND SAFETY INDEMNITY UNDERTAKING

, the	undersi	gned:			
n my	capacit	y as:			
of the	firm:				
1.0		oy underta oyees -	ke to ensure that I/my firm	and/or employe	es and/or subcontractors and/or his
	1.1	comply s amended section 3 performa	d) and/or the regulations pr 37(2) of the said act, as w	omulgated in ter vell as any relev vice and/or worl	nal Health and Safety Act of 1993 (as ms thereof, with specific reference to vant legislation, in the course of the k in, to or on any Tswelopele Loca mises;
	1.2		to occupational health		vith any instructions and measures prescribed by Tswelopele Loca
	1.3		strictly with the statutorily ry and occupational health		rk systems, operational equipment litions;
2.0		rtakings, T in respec	swelopele Local Municipa at of any costs that I/my fir	lity - m and/or employ	ndemnify, in terms of the above yees and/or subcontractors and their th the above undertakings; and
	2.2	any liabi caused be employed of any inc	lity that Tswelopele Loca by me/my firm's employed es and visitors or Tswelope cidents related to my/my firm	I Municipality mes, agents, consele Local Municipm's activities and	swelopele Local Municipality and/or nay incur, whether instituted and/or sultants, subcontractors and/or their pality clients or neighbours in respect d as a result of which the occupational n detrimentally affected; and
	2.3	Tswelope		any damages for	tors of my firm may have agains which I, managers or directors of my
3.0	subcomn	ontractors'	fees have been paid u	p and obligation	confirm that my firm and its ns in respect of the compensation shall furnish proof thereof in writing
1.0			n that I have the authority to lity is not obliged to confirn		nity undertaking and that Tswelopele ion.
Signe	ed at			this	day
Of					
			Signature		Capacity
As wi	tnesses				
		1	Name		Signature
		2	Name		Signature
			. 101110		Cigitatai C

C1.5 INCLEMENT WEATHER

No extension of time for completion will be granted on account of normal inclement weather but extension of time shall be determined for abnormal rainfall or wet conditions. The extension request must be in accordance with the formula given below, separately for each calendar month or part thereof. It shall be calculated for the period from the Commencement Date to the Due Completion Date or the date of issue of the Certificate of Practical Completion, whichever is earlier, and excluding the Contractor's year-end recess.

$$V = (N_w - N_n) + (R_w - R_n) / X$$

The symbols shall have the following meanings:

V = Extension of time in calendar days in respect of the calendar month under consideration.

Nw = Actual number of days during the relevant calendar month on which Y mm or more of rainfall has been recorded.

Nn = Average number of days in the relevant calendar month on which Y mm or more of rainfall has been recorded, as derived from the rainfall records provided in the Project Specification.

Rw = Actual rainfall in mm for the calendar month under consideration.

Rn = Average rainfall in mm for the relevant calendar month, as derived from the rainfall records provided in the Project Specifications.

If V is negative and its absolute value exceeds Nn, then V shall be taken as equal to minus Nn.

For this Contract, X and Y shall have the following values:

X = 20 mm/d Y = 10 mm

Extensions of time for part of a month shall be calculated using pro rata values of Nn and Rn.

The total extension of time shall be the algebraic sum of the monthly totals for the period under consideration, but if the grand total is negative the time for completion shall not be reduced due to abnormal rainfall.

The factor (Nw - Nn) shall be considered to represent a fair allowance for variations from the average number of days during which rainfall exceeds Y mm.

The factor (Rw - Rn)/X shall be considered to represent a fair allowance for variations from the average in the number of days during which rainfall does not exceed Y mm but wet conditions prevented or disrupted work.

The formula does not take account of flood damage, which could cause further or concurrent delays, which shall be treated separately as far as extension of time is concerned.

Rainfall records of the nearest weather station can be obtained from South African Weather Services.

PART C2

PRICING DATA

C2 PRICING DATA

C2.1 PRICING INSTRUCTIONS

- Measurement and payment shall be in accordance with the relevant provisions of the SANS Standard Specification, The General Conditions of Contract, the Contract Data, the Scope of Work (including the Specifications), the Site Information and the Drawings are to be read in conjunction with the Bill of Quantities
- 2. The units of measurement described in the Bill of Quantities are metric units. Abbreviations used in the Bill of Quantities are as follows:

% = percent h = hour = hectare ha kg = kilogram = kilolitre kΙ = kilometer km = km-pass kilometre-pass kPa = kilopascal kW = kilowatt = liter = meter m = millimeter mm m² = square meter = square meter-pass m²-pass

m³ = cubic meter

m³-km = cubic meter-kilometer

MN = meganewton

MN.m = meganewton-meter

MPa = megapascal No. = number

Prov sum

PC sum = Prime Cost sum
R/only = Rate only
sum = lump sum
t = ton (1000 kg)
W/day = Work day

3. For the purpose of the Bill of Quantities, the following words shall have the meanings hereby assigned to them:

Unit: The unit of measurement for each item of work as defined in the SANS Standard Specification, The General Conditions of Contract, the Contract Data, the Scope

of Work (including the Specifications).

Quantity: The number of units of work for each item.

Provisional sum

Rate: The payment per unit of work at which the Tenderer tenders to do the work...

Amount: The product of the quantity and the rate tendered for an item.

Lump sum: An amount tendered for an item, the extent of which is described in the Bill of

Quantities, the Specifications or elsewhere but of which the quantity of work is

not measured in units.

- 4. Unless otherwise stated, items are measured net in accordance with the drawings, and no allowance is made for waste.
- 5. It will be assumed that prices included in the Bill of Quantities are based on Acts, Ordinances,

Regulations, By-laws, International Standards and National Standards that were published 28 days before the closing date for tenders. (Refer to www.iso.org for information on standards)

- 6. The prices and rates in the Bill of Quantities are fully inclusive prices for the work described under the items. Such prices and rates cover all costs and expenses that may be required in and for the execution of the Works described in accordance with the provisions of the Scope of Work, and shall cover the cost of all general risks, liabilities, and obligations set forth or implied in the Contract Data, as well as overhead charges and profit. These prices will be used as a basis for assessment of payment for additional work that may have to be carried out.
- 7. Where the Scope of Work requires detailed drawings and designs or other information to be provided, all costs associated therewith are deemed to have been provided for and included in the unit rates and sum amounts tendered under such items.
- 8. An item against which no price is entered will be considered to be covered by the other prices or rates in the Bill of Quantities. A single lump sum will apply should a number of items be grouped together for pricing purposes.
- 9. The quantities set out in the Bill of Quantities are approximate and do not necessarily represent the actual amount of work to be done. The quantities of work accepted and certified for payment will be used for determining payments due and not the quantities given in the Bill of Quantities.
- 10. The short descriptions of the items of payment given in the Bill of Quantities are only for the purposes of identifying the items. More details regarding the extent of the work entailed under each item appear in the Scope of Work.
- 11. The item numbers appearing in the Bill of Quantities refer to the corresponding item numbers in the SABS 1200 applicable specification. The work scheduled payment should be referred to the applicable payment items in SABS 1200, which must receive preference to the reference given in the Schedule of Quantities or if any such reference is not indicated.
- 12. Those parts of the contract to be constructed using labour-intensive methods have been marked in the Bill of Quantities with the letters LI in a separate column filled in against every item so designated. The works, or parts of the Works so designated are to be constructed using labour-intensive methods only. The use of plant to provide such Works, other than plant specifically provided for in the Scope of Work, is a variation to the contract. The items marked with the letters LI are not necessarily an exhaustive list of all the activities which must be done by hand, and this clause does not over-ride any of the requirements in the generic labour intensive specification in the Scope of Works.
- Payment for items, which are designated to be constructed labour-intensively (either in this schedule or in the Scope of Works), will not be made unless they are constructed using labour-intensive methods. Any unauthorised use of plant to carry out work which was to be done labour-intensively will not be condoned and any works so constructed will not be certified for payment.

PRICING DATA

C2.2 BILL OF QUANTITIES

SUMMARY OF SECTIONS

SECTION 1	PRELIMINARY AND GENERAL	R -
SECTION 2	MECHANICAL - PUMP STATION	R -
SECTION 3	ELECTRICAL - PUMP STATION	_R
SECTION 4	CIVIL AND STRUCTURAL	R -
SUB TOTAL 1		R -
10% CONTINGE	ENCIES	R -
SUB TOTAL 2		R -
15% VAT		R -
TENDER SUM (incl VAT)	R -
,	•	

ЕМ	PAYMENT	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	SANS	SECTION A: PRELIMINARY AND				
	1200	GENERAL				
		FIXED-CHARGE AND VALUE RELATED ITEMS				
1.1		Contractual Requirements	Sum	1		
1.2		Establishment of Facilities on the Site				
1.2.1		Offices and storage sheds	Sum	1		
1.2.2		Workers accommodation and transport	Sum	1		
1.2.3		Ablution and latrine facilities	Sum	1		
1.2.4		Tools and equipment	Sum	1		
1.2.5		Water, electrical and telecommunication connection	Sum	1		
1.2.6		Dealing with water	Sum	1		
1.2.7		Standby power	Sum	1		
1.2.8		Plant & Machinery	Sum	1		
1.2.9		Other fixed-charge obligations (Tenderer to specify) High Pressure unit	Sum	1		
.2.10		Site de-establishment and rehabilitation	Sum	1		
.2.11		Nameboard	Sum	1		
1.2		COMPLIANCE WITH OHS ACT AND	Sum	1		
		REGULATIONS (INCLUDING THE				
		CONSTRUCTION REGULATIONS 2003).				
		Cost breakdown to be provided in the tender.				
1.3		TIME RELATED ITEMS				
.3.1		Contractual Requirements	Months	6		
1.3.2		Operation and maintenance of site facilities	Months	6		

ITEM	PAYMENT	DESCRIPTION	UNIT	QUANTITY	<u> </u>	AMOUNT
TOTAL	BROUGHT	FORWARD				
1.3.3		Site Supervision and construction management				
			Months	6		
1.3.4		Company and Head Office overhead costs				
			Months	6		
		for the duration of the contract	IVIOITIIIO			
		lor the duration of the contract				
			Prov			
1.3.5		Community Liaison Officer	Sum	1		
1.3.6		Student	NA 41			
1.0.0		Cladent	Months	6		
407		Cita analysis				
1.3.7		Site security	Months	6		
4						
1.3.8		Accommodation & LOA	Months	6		
1.3.9		Other time related charge obligations (tenderer				
		to specify)	Months	6		
1.3.10		Communication for the Engineer (Prov)	Month	6,00		
		Communication for the Engineer (F10V)	WIGHT	0,00		
1.3.11			0,	40.000.00		
1.0.11		Profit on item (1.3.11) on above	%	12 000,00		
4 0 40			_			
1.3.12		Supply or Hire of specialised equipment for	Prov	•		
		the detection of existing services	Sum			
1.3.13		Accomodation of traffic	Prov	1		
			Sum			
1.3.14		Relocation of existing services	Prov	1		
			Sum			
1.3.15		Excavation by hand to expose existing	m ³	100		
		services				
		Shop/ Workshop drawings for all stations and				
		WWTW equipment	Sum	1		
		Decommisioning of old equipment in all stations and WWTW				
			Sum	1		
		Dewatering of all sumps during construction	Sum	1		
1.4		TRAINING SKILLS AND DEVELOPMENT	Prov	1		
			Sum			
1.5		LOCAL CONTRACTOR DEVELOPMENT	Months	6		
		MANAGEMENT				
	CAPPIED	O STIMMARY	<u> </u>	I		
IOIAL	CARKIED I	O SUMMARY				

ЕМ	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
2	MECHANICAL WORKS				
2.1	HOOPSTAD COMMANDO PUMP STATION				
	The Tenderer must read the drawings &				
	specifications when pricing this Bill.				
2.1.1	PUMPS SETS, GUAGES & FITTINGS	No	2		
	Supply, delivery, installation, testing				
	and commissioning of pumps,				
	pipework, fittings, bends, elbows, reducers				
	and other listed installations, complete with				
	flanges, gaskets, bolts, nuts and washers,				
	All Flanges to be SANS 1123.Refer to				
	Pipe schedule in the drawings book.				
	Hidrostal screw-centrifugal or similar approved		INCL		
	New submersible raw-sewage pump sets with				
	(one duty and the other standby),				
	Duckfoot type with guide rail.				
	Suitable for pumping of wastewater and sewage.				
	Water-pressure tight, encapsulated, IP68				
	flood-proof motor and X20Cr13 stainless steel shaft.				
	Bimetal switch for thermal protection and				
	conductivity probe for early detection of moisture				
	ingress in seal chamber.				
	duties: 14.4 l/s (51.84 m3/h) at a head of				
	13.97 metres				
	It is essential to read through the specifications				
	and to understand the system curves, when				
	pricing.				
	and Hydraulic efficiency shall be at least				
	59%. The engineer shall give prior approval				
	before a purchase order is placed.				
			1		

ITEM	DESCRIPTION	UNIT	QUANTITY	
TOTAL BRO	DUGHT FORWARD			-
2.1.2	Motor 380V - 420V, 50Hz, 4-pole, IE3, efficiency IP68, 3.5 kW at 1450 rpm; Continuous running duty; Class H insulation; PT100 probes for windings temperature.		INCL	
2.1.3	PIPING & VALVES			
2.1.3.1	Suction pipe, HDPE, 200 NB, with a wall thickness of	m	15	
	6mm, complete with specials, flanges,			
	puddle flanges, fittings and VJ coupling, crotch plate, FBE to 150 microns, and			
	painting, complete with fittings (Pipe			
	Reducers and bends) and suction bellmouth (with baffles), and installed into			
	forebay.			
2.1.3.2	Delivery pipe, HDPE 160 NB, complete with specials, flanges, fittings and VJ coupling, crotch plate, FBE to 150 microns, and painting, complete with fittings (pipe peducers and bends) connecting into main delivery manifold.	m	20	
2.1.3.3	Resilient gate valve, rising stem, Suction side : 200 NB, PN10, flanged to SABS 1123	No.	2	
2.1.3.4	Resilient gate valve metal, rising stem, Delivery side : 160 NB , PN16 , flanged to SABS 1123	No.	3	
2.1.3.5	Non-return valve, 160 NB, PN25 , tilted disc type with an operating stroke of not more than 40°, flanged to SABS 1123	No.	2	
TOTAL CAI	RRIED FORWARD			

RETROFITTING OF 6 SEWER PUMP STATIONS, INSTALLATION OF INLINE GRINDERS AND REPAIRS

TEM	DESERIPHENTE WATER TREATMENT PLANT IN	יישואטיי	TEUANTITY	VAIIA	
OTAL BROU	IGHT FORWARD				
2.1.4	DEWATERING PUMP				
2.1.4.1	Hidrostal compact submersible pump set or similar	No.	1		
	approved (pump and motor systems) for the				
	de-watering of the pump chamber each with a				
	capacity of 10.1 l/s at a head of 10.28 metres at				
	a hydraulic efficiency of at least 60%.				
	1.8kW, 400V, 50Hz, 3-phase				
	Free ball passage for solids-handling min. 50mm				
2.1.4.2	50 mm HDPE piping within sump, necessary supports	m	8		
2.1.4.3	50mm gate valve	No.	1		
245					
2.1.5	Pump Protection and Instrumentation				
2.1.5.1.	Supply and install an electronic pressure	No.	2		
	gauge (positioned after pump control or				
	throttling valve), and conduct pipe system				
	curve verification tests to determine actual				
	system curve when pumping into the				
	system. Sump Float valve. The successful bidder shall us	se a			
	portable ultrasonic flowmeter to do this test.				
	The pressure gauge shall be mounted in				
	the valve chamber, downstream of all valves				
	which may restrict flow, but upstream of the				
	final pipeline isolating valve. Note: Pump				
	duty (for new pumps) may require				
	adjustment on completion of this system				
	curve verification exercise.				
2.1.5.2.	Pressure transmitter, 0 to 1500kPa,	No.	2		
	non-intrusive type, with an integrated local				
	LCD display, and shall be mounted				
	downstream of each pump. The signal				
	shall also be routed to the MCC panel.				
.1.5.3.	No flow switch (non-intrusive to flow, e.g	No.	2		
	Doppler Effect type), which shall be used				
	for pump protection.				
2.1.5.4.	Temperature probe, PT100 for the DE and	Pair	2		
	NDE bearings, which shall be used for				1

		pump protection on electric motors		
TOTAL C	ARRIED F	FORWARD		

ITEM	DESCRIPTION	UNIT	QUANTITY	
TOTAL BR	OUGHT FORWARD			
2.1.5.5.	Vibration probe for the DE and NDE bearings, which shall be used for pump protection	Pair	2	
2.1.5.6.	Pressure Switch with alarm contacts, with minimum and maximum pressure limits as per the pump head complete with wiring to the MCC.	No.	2	
2.1.6. 2.1.6.1	CATHODIC ISOLATION Cathodic isolation for each pump	No.	2	
2.1.7	CORROSION PROTECTION Preparation of surfaces, fusion-bonded epoxy, 150µm dry film thickness, internal and externally on pipework, pumps and fittings, for existing installations being refurbished.	No.	1	
2.1.7.2	Painting of pipework, pumps and fittings in line with the set colour-coding convention	Sum	1	
2.1.8 2.1.8.1	GRINDERS Supply and install an in-channel grinder (counter-rotating)individually stacked with 17 & 17 tooth serrated wipe ready cutters double edge 4130 alloy steel fitted with knurled spacers. Both cutter and spacers are through hardened, and heat treated to 52-55 Rockwell C. Grinders are supplied with integrated Delta P® high flow side rails and Optimum Cut Control. Unit will be supplied with a 3kW/4P/380V/IP55 motor and PLC contol unit	No.	1	

ITEM	DESCRIPTION	UNIT	QUANTITY	
-	RIED FORWARD			
	and soft copies of the data packs			
2.1.9.6	Training of the staff and issuing of manuals	No.	1	
	and reports.			
	compliance, test & commissioning sheets			
	including issuing of certificates of			
	(contractor to supply all necessary equipment for testing) and the installation,			
2.1.9.5	Site acceptance testing on two new pumps	No.	1	
2.1.9.4	Pressure testing of all pipework	No.	1	
2.1.9.3	Manufacturer's works or factory acceptance testing	No.	1	
2.1.9.2	Compliance with the Quality Management Plan by an independent accredited specialist consultant	No.	1	
	Preparation of a Quality Management Plan and implementation thereof, as aligned with DWS and SANS.	No.	1	
2.1.9 2.1.9.1	QUALITY ASSURANCE			

TOTAL B	ROUGHT FORWARD			
2.2	TIKWANA PUMP STATION 1			
	The Tenderer must read the drawings &			
	specifications when pricing this Bill.			
2.2.1	PUMPS SETS, GUAGES & FITTINGS	No.	2	
	Supply, delivery, installation, testing		_	
	and commissioning of pumps,			
	pipework, fittings, bends, elbows, reducers			
	and other listed installations, complete with			
	flanges, gaskets, bolts, nuts and washers,			
	All Flanges to be SANS 1123.Refer to			
	Pipe schedule in the drawings book.			
	Hidrostal screw-centrifugal or similar approved		INCL	
	New submersible raw-sewage pump sets with			
	(one duty and the other standby),			
	Duckfoot type with guide rail.			
	Suitable for pumping of wastewater and sewage.			
	Water-pressure tight, encapsulated, IP68			
	flood-proof motor and X20Cr13 stainless steel shaft.			
	Bimetal switch for thermal protection and			
	conductivity probe for early detection of moisture			
	ingress in seal chamber.			
	duties: 34 l/s (122.4 m3/h) at a head of			
	21.37 metres			
	It is essential to read through the specifications,			
	and to understand the system curves, when pricing.			
	and Hydraulic efficiency shall be at least			
	59%. The engineer shall give prior approval			
	before a purchase order is placed.			
TOTAL C	ARRIED FORWARD			

RETROFITTING OF 6 SEWER PUMP STATIONS, INSTALLATION OF INLINE GRINDERS AND REPAIRS

ГЕМ	DESTRIPHENT PLANT IN	1 HUMP	THE UNINFITTY	VVAIVA	
OTAL BROU	IGHT FORWARD				
2.2.2	Motor 400V, 50Hz, 4-pole, IE3,		INCL		
	efficiency IP68, 11 kW at 2925 rpm;				
	Continuous running duty; Class H insulation;				
	PT100 probes for windings temperature.				
2.2.3	PIPING & VALVES				
2.2.3.1					
2.2.3.1	Suction pipe, HDPE,	m	15		
	160 NB,				
	complete with specials, flanges,				
	puddle flanges, fittings and VJ coupling,				
	crotch plate, FBE to 150 microns, and				
	painting, complete with fittings (Pipe				
	Reducers and bends) and suction				
	bellmouth (with baffles), and installed into				
	forebay.				
2020	Delivery sine UDDE				
2.2.3.2	Delivery pipe, HDPE	m	20		
	160 NB, complete with specials,				
	flanges, fittings and VJ coupling, crotch				
	plate, FBE to 150 microns, and painting,				
	complete with fittings (pipe peducers and				
	bends) connecting into main delivery				
	manifold.				
2.2.3.3	Desilient materialism stems Continu	 			
2.2.0.0	Resilient gate valve, rising stem, Suction	No.	2		
	side : 160 NB , PN10 , flanged to SABS 1123				
2.2.3.4					
2.2.3.4	Resilient gate valve metal, rising stem,	No.	3		
	Delivery side : 160 NB, PN16, flanged to				
	SABS 1123				
2.2.3.5	Non-return valve, 160 NB, PN25, tilted disc	No			
		No.	2		
	type with an operating stroke of not more				
	than 40°, flanged to SABS 1123				
2.2.4	DEWATERING PUMP				
2.2.4.1	Hidrostal compact submersible pump set or similar	No.			
	approved (pump and motor systems) for the	1.40.	'		
	de-watering of the pump chamber each with a				
	capacity of 10.1 l/s at a head of 10.28 metres at	1	1		

_			_
	a hydraulic efficiency of at least 60%.		
	1.8kW, 400V, 50Hz, 3-phase		
	Free ball passage for solids-handling min. 50mm		

		1		
2.2.4.2	50 mm HDPE piping within sump, necessary supports	m	8	
2.2.4.3	50mm gate valve	No.	1	
TOTAL C	ARRIED FORWARD			
TOTAL B	ROUGHT FORWARD	İ		
2.2.5	Pump Protection and Instrumentation			
2.2.5.1.	Supply and install an electronic pressure	No.	2	
	gauge (positioned after pump control or			
	throttling valve), and conduct pipe system			
	curve verification tests to determine actual			
	system curve when pumping into the			
	system.Sump float valve The successful bidder shall use	a		
	portable ultrasonic flowmeter to do this test.			
	The pressure gauge shall be mounted in			
	the valve chamber, downstream of all valves			
	which may restrict flow, but upstream of the			
	final pipeline isolating valve. Note: Pump			
	duty (for new pumps) may require			
	adjustment on completion of this system			
	curve verification exercise.			
2.2.5.2.	Pressure transmitter, 0 to 1500kPa,	No.	2	
	non-intrusive type, with an integrated local			
	LCD display, and shall be mounted			
	downstream of each pump. The signal			
	shall also be routed to the MCC panel.			
2.2.5.3.	No flow switch (non-intrusive to flow, e.g	No.	2	
	Doppler Effect type), which shall be used			
	for pump protection.			
2.2.5.4.	Temperature probe, PT100 for the DE and	Pair	2	
	NDE bearings, which shall be used for			
	pump protection on electric motors			
TOTAL C	ARRIED FORWARD			

ITEM	DESCRIPTION	UNIT	QUANTITY	
TOTAL BRO	UGHT FORWARD			
2.2.5.5.	Vibration probe for the DE and NDE bearings, which shall be used for pump protection	Pair	2	
2.2.5.6.	Pressure Switch with alarm contacts, with minimum and maximum pressure limits as per the pump head complete with wiring to the MCC.	No.	2	
2.2.6.	CATHODIC ISOLATION			
2.2.6.1	Cathodic isolation for each pump	No.	2	
2.2.7	CORROSION PROTECTION			
2.2.7.1	Preparation of surfaces, fusion-bonded epoxy, 150µm dry film thickness, internal and externally on pipework, pumps and fittings, for existing installations being refurbished.	No.	1	
2.2.7.2	Painting of pipework, pumps and fittings in line with the set colour-coding convention	No.	1	
TOTAL CAR	RIED FORWARD			

ITEM	DESCRIPTION	UNIT	QUANTITY	
TOTAL BE	ROUGHT FORWARD			
2.2.8 2.1.8.1	GRINDERS Supply and install an in-channel grinder (counterrotating)individually stacked with 17 & 17 tooth serrated wipe ready cutters double edge 4130 alloy steel fitted with knurled spacers. Both cutter and spacers are through hardened, and heat treated to 52-55 Rockwell C. Grinders are supplied with integrated Delta P® high flow side rails and Optimum Cut Control. Unit will be supplied with a 3kW/4P/380V/IP55 motor and PLC contol unit	No.	1	
2.2.9 2.2.9.1	QUALITY ASSURANCE Preparation of a Quality Management Plan and implementation thereof, as aligned with DWS and SANS.	No.	1	
2.2.9.2	Compliance with the Quality Management Plan by an independent accredited specialist consultant	No.	1	
2.2.9.3	Manufacturer's works or factory acceptance testing	No.	1	
2.2.9.4	Pressure testing of all pipework	No.	1	
2.2.9.5	Site acceptance testing on two new pumps (contractor to supply all necessary equipment for testing) and the installation, including issuing of certificates of compliance, test & commissioning sheets and reports.	No.	1	
2.2.9.6	Training of the staff and issuing of manuals and soft copies of the data packs	No.	1	
TOTAL CA	RRIED FORWARD			
ITEM	DESCRIPTION	UNIT	QUANTITY	

2.3	TIKWANA PUMP STATION 2 The Tenderer must read the drawings &			
	specifications when pricing this Bill.			
2.3.1	PUMPS SETS, GUAGES & FITTINGS Supply, delivery, installation, testing and commissioning of pumps, pipework, fittings, bends, elbows, reducers and other listed installations, complete with flanges, gaskets, bolts, nuts and washers, All Flanges to be SANS 1123.Refer to Pipe schedule in the drawings book. Hidrostal screw-centrifugal or similar approved New submersible raw-sewage pump sets with (one duty and the other standby), Duckfoot type with guide rail. Suitable for pumping of wastewater and sewage. Water-pressure tight, encapsulated, IP68 flood-proof motor and X20Cr13 stainless steel shaft. Bimetal switch for thermal protection and conductivity probe for early detection of moisture ingress in seal chamber. duties: 16.5 l/s (59.4 m3/h) at a head of 8.54 metres It is essential to read through the specifications, and to understand the system curves, when pricing. and Hydraulic efficiency shall be at least 59%. The engineer shall give prior approval before a purchase order is placed.	No.	INCL	
TOTAL CARRII	ED FORWARD			

RETROFITTING OF 6 SEWER PUMP STATIONS, INSTALLATION OF INLINE GRINDERS AND REPAIRS

ITEM	DESCRIPTION WASTE WATER TREATMENT PLANT IN	нөрүү	TABUANAITIKWANA	4
TOTAL BROUG	HT FORWARD			
2.3.2	Motor 380V -420V, 50Hz, 4-pole, IE3, efficiency IP68, 2.6 kW at 2760 rpm; Continuous running duty; Class H insulation; PT100 probes for windings temperature.		INCL	
2.3.3	PIPING & VALVES			
2.3.3.1	Suction pipe, HDPE, 160 NB, 6mm, complete with specials, flanges, puddle flanges, fittings and VJ coupling,	m	15	
	crotch plate, FBE to 150 microns, and painting, complete with fittings (Pipe Reducers and bends) and suction bellmouth (with baffles), and installed into forebay.			
2.3.3.2	Delivery pipe, HDPE 160 NB, complete with specials, flanges, fittings and VJ coupling, crotch plate, FBE to 150 microns, and painting, complete with fittings (pipe peducers and bends) connecting into main delivery manifold.	m	20	
2.3.3.3	Resilient gate valve, rising stem, Suction side : 160 NB , PN10 , flanged to SABS 1123	No.	2	
2.3.3.4	Resilient gate valve metal, rising stem, Delivery side: 160 NB, PN16, flanged to SABS 1123	No.	3	
2.3.3.5	Non-return valve, 160 NB , PN25 , tilted disc type with an operating stroke of not more than 40°, flanged to SABS 1123	No.	2	
2.3.4	DEWATERING PUMP			
2.3.4.1	Hidrostal compact submersible pump set or similar approved (pump and motor systems) for the de-watering of the pump chamber each with a capacity of 10.1 l/s at a head of 10.28 metres at a hydraulic efficiency of at least 60%. 1.8kW, 400V, 50Hz, 3-phase Free ball passage for solids-handling min. 50mm	No.	1	
2.3.4.2 2.3.4.3	50 mm HDPE piping within sump, necessary supports 50mm gate valve	m No.	8 1	

RETROFITTING OF 6 SEWER PUMP STATIONS, INSTALLATI TO WASTE WATER TREATMENT PLANT IN H	ON OF I	NLINE GRIN AD AND TIK	NDERS AND WANA	REPAIRS	
TOTAL CARRIED FORWARD					

ITEM	DESCRIPTION	UNIT	QUANTITY	
TOTAL BROU	IGHT FORWARD			
2.3.5	Pump Protection and Instrumentation			
2.3.5.1	Supply and install an electronic pressure	No.	2	
	gauge (positioned after pump control or			
	throttling valve), and conduct pipe system			
	curve verification tests to determine actual			
	system curve when pumping into the			
	system. The successful bidder shall use a			
	portable ultrasonic flowmeter to do this test.			
	The pressure gauge shall be mounted in			
	the valve chamber, downstream of all valves			
	which may restrict flow, but upstream of the			
	final pipeline isolating valve. Note: Pump			
	duty (for new pumps) may require			
	adjustment on completion of this system			
	curve verification exercise.			
2.3.5.2	Pressure transmitter, 0 to 1500kPa,	No.	2	
	non-intrusive type, with an integrated local			
	LCD display, and shall be mounted			
	downstream of each pump. The signal			
	shall also be routed to the MCC panel.			
2.3.5.3	No flow switch (non-intrusive to flow, e.g	No.	2	
	Doppler Effect type), which shall be used			
	for pump protection.			
2.3.5.4	Temperature probe, PT100 for the DE and	Pair	2	
	NDE bearings, which shall be used for			
	pump protection on electric motors			
TOTAL CARR	 ED FORWARD			

RETROFITTING OF 6 SEWER PUMP STATIONS, INSTALLATION OF INLINE GRINDERS AND REPAIRS

TEM	DESTRIPHONTE WATER TREATMENT PLANT IN H	TENNY	THE WENDER!	WANA	
OTAL BROU	GHT FORWARD				
2.3.5.5	Vibration probe for the DE and NDE	Pair	2		
	bearings, which shall be used for pump				
	protection				
2.3.5.6	Pressure Switch with alarm contacts,	No.	2		
	with minimum and maximum pressure				
	limits as per the pump head complete with				
	wiring to the MCC.				
2.3.7	CATHODIC ISOLATION				
2.3.7.1	Cathodic isolation for each pump	No.	2		
2.3.8.	CORROSION PROTECTION				
2.3.8.1.	Preparation of surfaces, fusion-bonded	No.	1		
	epoxy, 150µm dry film thickness, internal				
	and externally on pipework, pumps and				
	fittings, for existing installations being				
	refurbished.				
2.3.8.2	Painting of pipework, pumps and fittings	No.	1		
	in line with the set colour-coding				
	convention	4			
2.3.9	GRINDERS				
2.3.9.1	Simbling				
	Supply and install an in-channel grinder (counter-				
	rotating)individually stacked with 17 & 17 tooth serrated				
	wipe ready cutters double edge 4130 alloy steel fitted with knurled spacers. Both cutter and spacers are through				
	hardened, and heat treated to 52-55 Rockwell C.				
	Grinders are supplied with integrated Delta P® high flow				
	side rails and Optimum Cut Control. Unit will be supplied				
	with a 3kW/4P/380V/IP55 motor and PLC contol unit	N.			
		No.	'		
2.3.10	QUALITY ASSURANCE				
2.2.10.1	Preparation of a Quality Management Plan	No.	1		
	and implementation thereof, as aligned with	110.	'		
	DWS and SANS.				
	BWO and GANG.				
2.3.10.2	Compliance with the Quality Management	No.	1		
	Plan by an independent accredited				
	specialist consultant				
	openiano concentano				
2.3.10.3	Manufacturer's works or factory acceptance	No.	1		
	testing				
2.3.10.4	Pressure testing of all pipework	No.	1		
2.3.10.5	Site acceptance testing on two new pumps	No.	1		
	(contractor to supply all necessary				
	equipment for testing) and the installation,				
	including issuing of certificates of				

RETROFITTING OF 6 SEWER PUMP STATIONS, INSTALLATION OF INLINE GRINDERS AND REPAIRS COMPTION ASTER WATERS TREATINENT PLANT IN HOOPSTAD AND TIKWANA and reports. 2.3.10.6 Training of the staff and issuing of manuals No. and soft copies of the data packs **TOTAL CARRIED FORWARD** ITEM DESCRIPTION UNIT QUANTITY 2.4 TIKWANA PUMP STATION 3 The Tenderer must read the drawings & specifications when pricing this Bill. 2.4.1 **PUMPS SETS, GUAGES & FITTINGS** No. Supply, delivery, installation, testing and commissioning of pumps, pipework, fittings, bends, elbows, reducers and other listed installations, complete with flanges, gaskets, bolts, nuts and washers, All Flanges to be SANS 1123.Refer to Pipe schedule in the drawings book. INCL Hidrostal screw-centrifugal or similar approved New submersible raw-sewage pump sets with (one duty and the other standby), Duckfoot type with guide rail. Suitable for pumping of wastewater and sewage. Water-pressure tight, encapsulated, IP68 flood-proof motor and X20Cr13 stainless steel shaft. Bimetal switch for thermal protection and conductivity probe for early detection of moisture ingress in seal chamber. duties: 8.59 l/s (30.924 m3/h) at a head of 7.55 metres It is essential to read through the specifications, and to understand the system curves, when pricing. and Hydraulic efficiency shall be at least 59%. The engineer shall give prior approval before a purchase order is placed. 2.4.2 Motor 400V, 50Hz, 4-pole, IE3, INCL efficiency IP68, 1.2 kW at 2905 rpm; Continuous running duty; Class H insulation; PT100 probes for windings temperature. 2.4.3 **PIPING & VALVES** 2.4.3.1. Suction pipe, HDPE, m 15

160 NB,

complete with specials, flanges, puddle flanges, fittings and VJ coupling, crotch plate, FBE to 150 microns, and painting, complete with fittings (Pipe

	Reducers and bends) and suction bellmouth (with baffles), and installed into forebay.		
TOTAL C	CARRIED FORWARD		

1 1	TO WASTE WATER TREATMENT PLANT IN	нфорѕтаг	AND TIKWANA	1
2.4.3.2	Delivery pipe, HDPE 160 NB, complete with specials, flanges, fittings and VJ coupling, crotch plate, FBE to 150 microns, and painting, complete with fittings (pipe peducers and bends) connecting into main delivery manifold.	m	20	
2.4.3.3	Resilient gate valve, rising stem, Suction side : 160 NB, PN10 , flanged to SABS 1123	No.	2	
2.4.3.4	Resilient gate valve metal, rising stem, Delivery side: 160 NB, PN16, flanged to SABS 1123	No.	3	
2.4.3.5	Non-return valve, 160 NB, PN25, tilted disc type with an operating stroke of not more than 40°, flanged to SABS 1123	No.	2	
2.4.4	DEWATERING PUMP			
2.4.4.1	Hidrostal compact submersible pump set or similar approved (pump and motor systems) for the de-watering of the pump chamber each with a capacity of 10.1 l/s at a head of 10.28 metres at a hydraulic efficiency of at least 60%. 1.8kW, 400V, 50Hz, 3-phase Free ball passage for solids-handling min. 50mm	No.	1	
2.4.4.2	50 mm HDPE piping within sump, necessary supports	m	8	
2.4.4.3	50mm gate valve	No.	1	
2.4.5	Pump Protection and Instrumentation			
2.4.5.1	Supply and install an electronic pressure gauge (positioned after pump control or throttling valve), and conduct pipe system curve verification tests to determine actual system curve when pumping into the system. Sump float valve. The successful bidder shall us portable ultrasonic flowmeter to do this test. The pressure gauge shall be mounted in the valve chamber, downstream of all valves which may restrict flow, but upstream of the final pipeline isolating valve. Note: Pump duty (for new pumps) may require adjustment on completion of this system curve verification exercise.	No.	2	
2.4.5.2	Pressure transmitter, 0 to 1500kPa,non-intrusive type with an integrated local LCD display, and shall be mounted downstream of each pump. The signal	No.	2	

	shall also be routed to the MCC panel.				
2.4.5.3	No flow switch (non-intrusive to flow, e.g Doppler Effect type), which shall be used for pump protection.	No.	2		

2.4.5.4	Temperature probe, PT100 for the DE and	Pair	2	
	NDE bearings, which shall be used for			
	pump protection on electric motors			
	ED FORWARD			
ITEM	DESCRIPTION	UNIT	QUANTITY	
	GHT FORWARD			
2.4.5.5	Vibration probe for the DE and NDE	Pair	2	
	bearings, which shall be used for pump			
	protection			
2.4.5.6	Pressure Switch with alarm contacts,	No.	2	
	with minimum and maximum pressure			
	limits as per the pump head complete with			
	wiring to the MCC.			
2.4.6	CATHODIC ISOLATION			
2.4.6.1	Cathodic isolation for each pump	No.	2	
2.4.7	CORROSION PROTECTION			
2.4.7.1	Preparation of surfaces, fusion-bonded	No.	1	
	epoxy, 150µm dry film thickness, internal			
	and externally on pipework, pumps and			
	fittings, for existing installations being			
	refurbished.			
2.4.7.2	Painting of pipework, pumps and fittings	No.	1	
	in line with the set colour-coding			
	convention	_		
2.4.8	GRINDERS			
2.4.8.1				
	Supply and install an in-channel grinder (counter-			
	rotating)individually stacked with 17 & 17 tooth serrated			
	wipe ready cutters double edge 4130 alloy steel fitted with knurled spacers. Both cutter and spacers are through			
	hardened, and heat treated to 52-55 Rockwell C.			
	Grinders are supplied with integrated Delta P® high flow			
	side rails and Optimum Cut Control. Unit will be supplied			
	with a 3kW/4P/380V/IP55 motor and PLC contol unit	No.	1	
			1	

2.4.9	QUALITY ASSURANCE			
2.2.9.1	Preparation of a Quality Management Plan	No.	1	
	and implementation thereof, as aligned with			
	DWS and SANS.			
2.4.9.2	Compliance with the Quality Management	No.	1	
	Plan by an independent accredited			
	specialist consultant			
2.4.9.3	Manufacturer's works or factory acceptance	No.	1	
	testing	110.		
2.4.9.4	Pressure testing of all pipework	No.	1	
2.4.9.5	Site acceptance testing on two new pumps	No.	1	
	(contractor to supply all necessary			
	equipment for testing) and the installation,			
	including issuing of certificates of			
	compliance, test & commissioning sheets			
	and reports.			
2.4.9.6	Training of the staff and issuing of manuals	No.	1	
	and soft copies of the data packs			
TOTAL CARR	RIED FORWARD			

ITEM	DESCRIPTION	UNIT	QUANTITY	*******	AMOUNT
	JGHT FORWARD				
2.5	TIKWANA PUMP STATION 5				
	The Tenderer must read the drawings &	_			
	specifications when pricing this Bill.				
2.5.1	PUMPS SETS, GUAGES & FITTINGS	No.	2		
	Supply, delivery, installation, testing		_		
	and commissioning of pumps,				
	pipework, fittings, bends, elbows, reducers				
	and other listed installations, complete with				
	flanges, gaskets, bolts, nuts and washers,				
	All Flanges to be SANS 1123.Refer to				
	Pipe schedule in the drawings book.				
	Hidrostal screw-centrifugal or similar approved		INCL		
	New submersible raw-sewage pump sets with				
	(one duty and the other standby),				
	Duckfoot type with guide rail.				
	Suitable for pumping of wastewater and sewage.				
	Water-pressure tight, encapsulated, IP68				
	flood-proof motor and X20Cr13 stainless steel shaft.				
	Bimetal switch for thermal protection and				
	conductivity probe for early detection of moisture				
	ingress in seal chamber.				
	duties: 13.4 l/s (48.24 m3/h) at a head of				
	11.1 metres				
	It is essential to read through the specifications,				
	and to understand the system curves, when pricing.				
	and Hydraulic efficiency shall be at least				
	59%. The engineer shall give prior approval				
	before a purchase order is placed.				
2.5.2	Motor 400V, 50Hz, 4-pole, IE3,		INCL		
	efficiency IP68, 2.4 kW at 1450 rpm;				
	Continuous running duty; Class H insulation;				
	PT100 probes for windings temperature.				
2.5.3	PIPING & VALVES				
2.5.3.1	Suction pipe, HDPE,	m	15		
	160 NB,				
	complete with specials, flanges,				
	puddle flanges, fittings and VJ coupling,				
	crotch plate, FBE to 150 microns, and				
	painting, complete with fittings (Pipe				
	Reducers and bends) and suction				
	bellmouth (with baffles), and installed into				
	forebay.				
TOTAL CARF	RIED FORWARD				

1 1	TO WASTE WATER TREATMENT PLANT IN	HOOPSTAD	AND TIKWANA	1 1
2.5.3.2	Delivery pipe, HDPE 160 NB, complete with specials, flanges, fittings and VJ coupling, crotch plate, FBE to 150 microns, and painting, complete with fittings (pipe peducers and bends) connecting into main delivery manifold.	m	20	
2.5.3.3	Resilient gate valve, rising stem, Suction side : 160 NB, PN10 , flanged to SABS 1123	No.	2	
2.5.3.4	Resilient gate valve metal, rising stem, Delivery side: 160 NB, PN16, flanged to SABS 1123	No.	3	
2.5.3.5	Non-return valve, 160 NB, PN25 , tilted disc type with an operating stroke of not more than 40°, flanged to SABS 1123	No.	2	
2.5.4	DEWATERING PUMP			
2.5.4.1	Hidrostal compact submersible pump set or similar approved (pump and motor systems) for the de-watering of the pump chamber each with a capacity of 10.1 l/s at a head of 10.28 metres at a hydraulic efficiency of at least 60%. 1.8kW, 400V, 50Hz, 3-phase Free ball passage for solids-handling min. 50mm	No.	1	
2.5.4.2 2.5.4.3	50 mm HDPE piping within sump, necessary supports 50mm gate valve	m No.	8 1	
2.5.5 2.5.5.1	Pump Protection and Instrumentation Supply and install an electronic pressure gauge (positioned after pump control or throttling valve), and conduct pipe system curve verification tests to determine actual system curve when pumping into the system. The successful bidder shall use a portable ultrasonic flowmeter to do this test. Sump float valve. The pressure gauge shall be mounted in the valve chamber, downstream of all valves which may restrict flow, but upstream of the final pipeline isolating valve. Note: Pump duty (for new pumps) may require adjustment on completion of this system curve verification exercise.	No.	2	
2.5.5.2	Pressure transmitter, 0 to 1500kPa, non-intrusive type, with an integrated local LCD display, and shall be mounted	No.	2	

	downstream of each pump. The signal			
	shall also be routed to the MCC panel.			
0.5.5.0	No floor with the form to the floor	NI.		
2.5.5.3	No flow switch (non-intrusive to flow, e.g	No.	2	
	Doppler Effect type), which shall be used			
	for pump protection.			

		J	D AND TIKWANA	
OTAL CARE	RIED FORWARD			
2.5.5.4	Temperature probe, PT100 for the DE and NDE bearings, which shall be used for pump protection on electric motors	Pair	2	
2.5.5.5	Vibration probe for the DE and NDE bearings, which shall be used for pump protection	Pair	2	
2.5.5.6	Pressure Switch with alarm contacts, with minimum and maximum pressure limits as per the pump head complete with wiring to the MCC.	No.	2	
2.5.7	CATHODIC ISOLATION			
2.5.7.1	Cathodic isolation for each pump	No.	2	
2.5.8 2.5.8.1	CORROSION PROTECTION Preparation of surfaces, fusion-bonded epoxy 150µm dry film thickness, internal and externally on pipework, pumps and fittings, for existing installations being refurbished	No.	1	
2.5.8.2	Painting of pipework, pumps and fittings in line with the set colour-coding convention	No.	1	
2.5.9 2.5.9.1	GRINDERS Supply and install an in-channel grinder (counterrotating)individually stacked with 17 & 17 tooth serrated wipe ready cutters double edge 4130 alloy steel fitted with knurled spacers. Both cutter and spacers are through hardened, and heat treated to 52-55 Rockwell C. Grinders are supplied with integrated Delta P® high flow side rails and Optimum Cut Control. Unit will be supplied with a 3kW/4P/380V/IP55 motor and PLC contol unit	No.	1	
2.5.10 2.5.10.1	QUALITY ASSURANCE Preparation of a Quality Management Plan and implementation thereof, as aligned with DWS and SANS.	No.	1	
2.5.10.2	Compliance with the Quality Management Plan by an independent accredited specialist consultant	No.	1	
	Manufacturer's works or factory acceptance	No.	1	
2.5.10.3	testing			

2.5.10.5	Site acceptance testing on two new pumps	No.	1	1
	(contractor to supply all necessary			
	equipment for testing) and the installation,			
	including issuing of certificates of			
	compliance, test & commissioning sheets			
	and reports.			

2.5.10.6	Training of the staff and issuing of manuals	No.	1	
	and soft copies of the data packs			
TOTAL CARR	RIED FORWARD			
ITEM	DESCRIPTION	UNIT	QUANTITY	AMOUNT
TOTAL BROU	IGHT FORWARD			
		Ţ		
2.6	TIKWANA PUMP STATION 6	ļ		
	GRINDERS			
2.6.1	Supply and install an in-channel grinder (counter-rotating)individually stacked with 17 & 17 tooth serrated wipe ready cutters double edge 4130 alloy steel fitted with knurled spacers. Both cutter and spacers are through hardened, and heat treated to 52-55 Rockwell C. Grinders are supplied with integrated Delta P® high flow side rails and Optimum Cut Control. Unit will be supplied with a 3kW/4P/380V/IP55 motor and PLC contol unit	No.	1	
2.7	WASTE WATER TREATMENT PLANT EQUIPMENT Replacement of the following items Supply and			
	install including testing and commissioning of the following items			
2.7.1	FRS 800 x 700 Mechanical Front Rake Screen , 304 Stainless steel (see drawing)	No.	1	
2.7.2	Bio-Reactors vertical shaft mounted mixers 5.5kW (see drawing)	No	2	
2.7.3	Vertical Shaft Aerators at the Bio-Reactor 45kW (see drawing)	No	2	
2.7.4	Pump at the Gold-club pump station, 22kW at 83m capacity	No	1	
2.7.5	Berson Ultraviolet unit in the treated effluent pump station,2 x Inline 400+ Summit, 240/400V 3L+N 50Hz 600W.	No	1	

	(See drawing)				
2.7.6	Re-alignment of the scum skimmer or slut scrappers	No	1 1		
	with scum box (clarifiers), replace centre bearings				
	(clarifiers) and installation of a new complete				
	Drive Cage Assembly for the Clarifiers -new gearbox				
	drive with electrical motor, new end carriage				
2.7.7	New wheels, shafts and bearings				
2.1.1	Clarifier Centre Bearing (750mm), 0.25kW x 4P, 400V x 3pH motor	No	1 1		
2.8	Allowance of R25 000 for the decommisioning of				
	Hoopestad, Tikwana 1, 2, 3 and 5	Sum	1		
2.9	Temporary hire of pumping system to use during				
	construction for all pump stations	No.	5		
2.10.	Depletorment of the OFOm diameter metal hardest				
	Replacement of the 950m diameter metal basket/ mechanical screen (shown on the pump station layout				
	drawing)	No	5		
2.11	Shop/ workshop drawings for all stations	No	5		
2.12	Pressure testing of all pipework	No.	1		
TOTAL BROUGH	IT FORWARD			 	

SECTIO	N 3: ELECT	RICAL - PUMP STATIONS No.1 to 6 AND WASTE WATER	R TREAT	MENT PLAN	Т	
ITEM	PAYMENT	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
3		Electrical Works (Supply and Installation of the following items)				
3,1		HOOPSTAD COMMANDO PUMP STATION	i			
٥,.		The Tenderer must read the drawings &	1			
		specifications when pricing this Bill.				
		Excavation and Trenching				
		Allowance must be made for the sifting of				
		soil when required, removal and carting				
		away of all stones and rocks including				
		dumping off site. Backfilling and compaction				
		shall be carried out as specified for overall				
		siteworks.				
3.1.1		Excavation and backfilling in soft soil	m³	15		
3.1.2		Excavation and backfilling in hard rock	m³	15		
3,2		Power Supply				
3.2.1		Supply and install a power external main distribution board 500x850mm wall-mounted, with a 150kVA 3ph incomer CB weather-proof IP65, complete with LV surge arrestors	No.	1		
3,3		Low Voltage PVC Cables, Earth Wire				
		and Terminations				
		Supply and installation of PVC SWA PVC				
		cable and Earth Wire in trenches or racking				
		complete with terminations.				
3.3.1		35mm ² 4-core Cu PVC SWA Cable (From Main DB to new distribution board)	m	50		
		10mm ² 4-core Cu PVC SWA Cable (From Main DB to 2.2kW inline grinder, 2.4kW dewatering pump and new 3.5kW submersible raw sewage pump sets, duty and				
3.3.2		standby	m	200		
3.3.3		10mm ² 3 core Cu (LN&E) PVC SWA Cable	m	100		
		(Main DB to Sub-DBs for buildings & Outside lighting)				
3.3.4		16mm² Cu Insulated Earth Wire	m	50		
3.3.5		10mm² Cu Insulated Earth Wire	m	300		
TOTAL	L CARRIED F	I ORWARD				
	ı	DESCRIPTION	UNIT	QUANTITY		

TOTAL B	ROUGHT FORWARD			
3,4	Motor Control Panel (6kA.sec)			
3.4.1	Supply, delivery, installation, testing and	No.	1	
	commissioning of a 1mm Motor Control			
	Centre, complete with busbars,			
	switchgear, indication lamps, running/tripping/stop (on/off)			
	selector switch, ammeter, power meter,			
	hour meter readings, control gear. 20% spare space.			
	Schneider / similar switchgear			
	with switchgear coordination charts			
	submitted.			
3.5	Cable Trays			
	Supply and installation of heavy duty cable			
	tray below complete with accessories			
3.5.1	200mm width 1.5mm thickness heavy duty	m	50	
	cable tray, complete with fittings			
3.5.2	100mm width 1.5mm thickness heavy duty	m	30	
	cable tray, complete with fittings			
3.6	Building electrical services			
3.6.1	Surface-mounted 6kA domestic DB surge	No.	1	
	complete 60A 4P, 3x20A+E/L, 3x15A,			
	3x5A, 4P arrestor. 30% spare capacity.			
3.6.2	Sump facility - Indoor LED 40w weather-proof IP66	No.	2	
3.6.3	Indoor LED 20w vapour-proof IP65	No.	1	
3.6.4	Outdoor LED 100W flood light IP65	No.	4	
	Circular the seasonal district of			
3.6.5	Single phase welding socket out	No.	1	
366	Surface-mounted 16A domestic socket outlet	No	A	
3.6.6	ourlace-mounted for domestic socket outlet	No.	4	
	Surface-mounted 40A 3ph industrial waterproof isolator			
3.6.7	with lockable handle	No.	2	
3.6.8	Surface-mounted 30A 3ph industrial waterproof isolator with lockable handle	No.	2	
	ARRIED FORWARD	INO.		
LIGIAL	ANNIED I VINTAND			

ITEM	PAYMENT	DESCRIPTION	UNIT	QUANTITY	
TOTAL	BROUGHT I	FORWARD			
3.6.9		Surface-mounted 2 lever Light switch	No.	1	
3.6.10		16A Photocell (Day/night) switch	No.	1	
3.6.11		Metal conduits and fittings	m	200	
3.6.12		4mm2 General Purpose wires	m	500	
3.6.13		2.5mm2 General Purpose wires	m	500	
3.6.14		2.5mm2 Bare Copper Earth wires	m	500	
3.7		Others - Testing and Commissioning			
3.7.1		Making provision for the required inspection, tests and the commissioning of the tests and the commissioning of the complete installation and the issuing of the required certificates and handover documentation (test sheets, manuals, software, etc) including electronic datapacks.	No	1	
3.7.2		Provisional allowance for removal and disposal of electrical components involving: storing the electrical equipment in drums/containers for hazardous waste and safely disposed at a hazardous waste site	Sum	1	
3.7.3		Provisional allowance for Ligthning Protection system include installing surge arrestors class 2 or type 2 on the Distribution Boards as per SANS10142-1:2021 Ed.3	Sum	1	
3.7.4		Provisional allowance for Earthing and Bonding system	Sum	1	
3.7.5		Site training of the Client's Operations staff.	No	1	
TOTAL	CARRIED TO	O SUMMARY			

ITEM	PAYMENT	DESCRIPTION	UNIT	QUANTITY		
		Electrical Works (Supply and Installation of the				
3		following items)				
			Ī			
3,1		TIKWANA PUMP STATION 1	l			
		The Tenderer must read the drawings &	Ī			
		specifications when pricing this Bill.				
		Excavation and Trenching				
		Allowance must be made for the sifting of				
		soil when required, removal and carting				
		away of all stones and rocks including				
		dumping off site. Backfilling and compaction				
		shall be carried out as specified for overall				
		siteworks.				
3.1.1		Excavation and backfilling in soft soil	m³	10		
3.1.2		Excavation and backfilling in hard rock	m³	10		
3,2		Power Supply				
3.2.1		Supply and install a power external kiosk distribution				
3.2.1			No.	1		
		weather-proof IP65, complete with LV surge arrestors. The board will integrate a Motor Control Panel, complete				
		with busbars, indication lamps, running/tripping/stop				
		(on/off), selector switch, ammeter, power meter, hour				
		meter readings, control gear. 20% spare space.				
,,						
3,3		Low Voltage PVC Cables, Earth Wire				
		and Terminations				
		Supply and installation of PVC SWA PVC				
		cable and Earth Wire in trenches or racking				
		complete with terminations.				
		2				
3.3.1		35mm ² 4-core Cu PVC SWA Cable	m	Rate Only		
		16mm ² 4-core Cu PVC SWA Cable (From Main Kiosk DB				
		to new submersible raw sewage pump sets 11kW, duty	<u> </u>	100		
3.3.2		and standby)	m	100		
		10mm ² 4-core Cu PVC SWA Cable (From Main DB to				
3.3.3		2.2kW inline grinder and 2.4kW dewatering pump)	m	100		
3.3.4		10mm ² 3 core Cu (LN&E) PVC SWA Cable	m	20		
		(Kiosk DB to Kiosk Sub-DBs for outside lighting				
3.3.5		16mm² Cu Insulated Earth Wire	m	Rate Only		
3.3.6		10mm² Cu Insulated Earth Wire	m	220		
TOTAL	CARRIED F	ORWARD				
ITEM	PAYMENT	DESCRIPTION	UNIT	QUANTITY	•	

TOTAL BR	OUGHT FORWARD	T		
3,4	Cable Trays			
	Supply and installation of heavy duty cable			
	tray below complete with accessories			
3.4.1	200mm width 1.5mm thickness heavy duty cable tray, complete with fittings	m	50	
3.4.2	100mm width 1.5mm thickness heavy duty cable tray, complete with fittings	m	30	
3,5	Building electrical services			
3.5.1	Surface-mounted 6kA domestic DB surge	No.	1	
	complete 60A 4P, 3x20A+E/L, 3x15A,			
	3x5A, 4P arrestor. 30% spare capacity.			
3.5.2	Sump - Indoor LED 40w weather-proof IP66	No.	2	
3.5.3	Indoor LED 20w vapour-proof IP65	No.		
3.5.4	Outdoor LED 100W flood light IP65	No.	4	
3.5.5	Single phase welding socket out	No.	1	
3.5.6	Surface-mounted 16A domestic socket outlet	No.	4	
3.5.7	Surface-mounted 60A 3ph industrial waterproof isolator with lockable handle	No.	2	
3.5.8	Surface-mounted 30A 3ph industrial waterproof isolator with lockable handle	No.	2	
TOTAL CA	RRIED FORWARD			

ITEM PAYMENT	DESCRIPTION	UNIT	QUANTITY	AMOUNT
TOTAL BROUGHT	FORWARD			-
3.6.9	Surface-mounted 2 lever Light switch	No.	1	
3.6.10	16A Photocell (Day/night) switch	No.	1	
3.6.11	Metal conduits and fittings	m	200	
3.6.12	4mm ² General Purpose wires	m	500	
3.6.13	2.5mm² General Purpose wires	m	500	
3.6.14	2.5mm ² Bare Copper Earth wires	m	500	
3.7	Others - Testing and Commissioning			
3.7.1	Making provision for the required inspection, tests and the commissioning of the tests and the commissioning of the complete installation and the issuing of the required certificates and handover documentation (test sheets, manuals, software, etc) including electronic datapacks.	No	1	
3.7.2	Provisional allowance for removal and disposal of electrical components involving: storing the electrical equipment in drums/containers for hazardous waste and safely disposed at a hazardous waste site	Sum	1	
3.7.3	Provisional allowance for Ligthning Protection system include installing surge arrestors class 2 or type 2 on the Distribution Boards as per SANS10142-1:2021 Ed.3	Sum	1	
3.7.4	Provisional allowance for Earthing and Bonding system	Sum	1	
3.7.5	Site training of the Client's Operations staff.	No	1	
TOTAL CARRIED T	O SUMMARY			

ITEM	PAYMENT	DESCRIPTION	UNIT	QUANTITY	AMOUNT
		Electrical Works (Supply and Installation of the			
3		following items)			
3,1		TIKWANA PUMP STATION 2			
		The Tenderer must read the drawings &			
		specifications when pricing this Bill.			
		Excavation and Trenching			
		Allowance must be made for the sifting of			
		soil when required, removal and carting			
		away of all stones and rocks including			
		dumping off site. Backfilling and compaction			
		shall be carried out as specified for overall			
		siteworks.			
3.1.1		Everystics and healfilling inft!	m3	40	
3.1.1		Excavation and backfilling in soft soil	m³	10	
3.1.2		Excavation and backfilling in hard rock	lm³	10	
0.1.2		Executation and backlining in Hald fook	l'''		
3,2		Power Supply			
3.2.1		Supply and install a power external kiosk distribution	No.	1	
0.2		board 1500x950 mm ground-mount, 60A 3ph incomer CB,			
		weather-proof IP65, complete with LV surge arrestors.			
		The board will integrate a Motor Control Panel, complete			
		with busbars, indication lamps, running/tripping/stop (on/off), selector switch, ammeter, power meter, hour			
		motor readings, central aper 200% apers appea			
3,3		Low Voltage BVC Cables Forth Wire			
3,3		Low Voltage PVC Cables, Earth Wire and Terminations			
		Supply and installation of PVC SWA PVC			
		cable and Earth Wire in trenches or racking			
		complete with terminations.			
		complete with terminations.			
3.3.1		35mm² 4-core Cu PVC SWA Cable	m	Rate Only	
3.3.2		16mm ² 4-core Cu PVC SWA Cable	m	Rate Only	
		10mm ² 4-core Cu PVC SWA Cable (From Main DB to			
		2.2kW inline grinder, 2.4kW dewatering pump and new			
		2.6kW submersible raw sewage pump sets, duty and			
3.3.3		standby	m	200	
3.3.4		10mm ² 3 core Cu (LN&E) PVC SWA Cable (Kiosk DB to			
		Kiosk Sub-DBs for outside lighting	m	20	
3.3.5		16mm² Cu Insulated Earth Wire	m	Rate Only	
3.3.6		10mm² Cu Insulated Earth Wire	m	220	
TOTAL	CARRIER	DDWADD			
IUIAL	CARRIED FO	UKWAKU			

ITEM	PAYMENT	DESCRIPTION	UNIT	QUANTITY	AMOUNT
TOTAL	BROUGHT I	FORWARD			
3,4		Cable Trays Supply and installation of heavy duty cable tray below complete with accessories			
3.4.1		200mm width 1.5mm thickness heavy duty cable tray, complete with fittings	m	50	
3.4.2		100mm width 1.5mm thickness heavy duty cable tray, complete with fittings	m	30	
3,5 3.5.1		Building electrical services Surface-mounted 6kA domestic DB surge complete 60A 4P, 3x20A+E/L, 3x15A, 3x5A, 4P arrestor. 30% spare capacity.	No.	1	
3.5.2		Sump - Indoor LED 40w weather-proof IP66	No.	2	
3.5.3		Indoor LED 20w vapour-proof IP65	No.		
3.5.4		Outdoor LED 100W flood light IP65	No.	4	
3.5.5		Single phase welding socket out	No.	1	
3.5.6		Surface-mounted 16A domestic socket outlet	No.	4	
3.5.7		Surface-mounted 60A 3ph industrial waterproof isolator with lockable handle	No.	Rate Only	
3.5.8		Surface-mounted 30A 3ph industrial waterproof isolator with lockable handle	No.	4	
TOTAL	CARRIED F	ORWARD			

ITEM PAYMENT	DESCRIPTION	UNIT	QUANTITY	AMOUNT
TOTAL BROUGHT	FORWARD			-
3.6.9	Surface-mounted 2 lever Light switch	No.	1	
3.6.10	16A Photocell (Day/night) switch	No.	1	
3.6.11	Metal conduits and fittings	m	200	
3.6.12	4mm ² General Purpose wires	m	500	
3.6.13	2.5mm² General Purpose wires	m	500	
3.6.14	2.5mm ² Bare Copper Earth wires	m	500	
3.7	Others - Testing and Commissioning			
3.7.1	Making provision for the required inspection, tests and the commissioning of the tests and the commissioning of the complete installation and the issuing of the required certificates and handover documentation (test sheets, manuals, software, etc) including electronic datapacks.	No	1	
3.7.2	Provisional allowance for removal and disposal of electrical components involving: storing the electrical equipment in drums/containers for hazardous waste and safely disposed at a hazardous waste site	Sum	1	
3.7.3	Provisional allowance for Ligthning Protection system include installing surge arrestors class 2 or type 2 on the Distribution Boards as per SANS10142-1:2021 Ed.3	Sum	1	
3.7.4	Provisional allowance for Earthing and Bonding system	Sum	1	
3.7.5	Site training of the Client's Operations staff.	No	1	
TOTAL CARRIED T	O SUMMARY			

ITEM	PAYMENT	DESCRIPTION	UNIT	QUANTITY	AMOUNT
		Electrical Works (Supply and Installation of the			
3		following items)			
			ļ		
3,1		TIKWANA PUMP STATION 3	ļ		
		The Tenderer must read the drawings &			
		specifications when pricing this Bill.			
		Excavation and Trenching			
		Allowance must be made for the sifting of			
		soil when required, removal and carting			
		away of all stones and rocks including			
		dumping off site. Backfilling and compaction			
		shall be carried out as specified for overall			
		siteworks.			
3.1.1		Excavation and backfilling in soft soil	lm³	10	
"		Executation and buotiming in soft soil	'''		
3.1.2		Excavation and backfilling in hard rock	m³	10	
3,2		Power Supply			
		Supply and install a power external kiosk distribution			
		board 1500x950 mm ground-mount, 60A 3ph incomer CB,			
3.2.1		weather-proof IP65, complete with LV surge arrestors. The board will integrate a Motor Control Panel, complete			
		with busbars, indication lamps, running/tripping/stop			
		(on/off), selector switch, ammeter, power meter, hour	No.	1	
		meter readings, control gear. 20% spare space.	INO.	'	
3,3		Low Voltage PVC Cables, Earth Wire			
'		and Terminations			
		Supply and installation of PVC SWA PVC			
		cable and Earth Wire in trenches or racking			
		complete with terminations.			
		35mm ² 4-core Cu PVC SWA Cable (From Main DB to new			
3.3.1		distribution board)	m	Rate Only	
3.3.2		16mm ² 4-core Cu PVC SWA Cable	m	Rate Only	
		10mm ² 4-core Cu PVC SWA Cable (From Main DB to			
		2.2kW inline grinder, 2.4kW dewatering pump and new			
222		1.2kW submersible raw sewage pump sets, duty and standby	 	200	
3.3.3		Joianupy	m	200	
3.3.4		10mm² 3 core Cu (LN&E) PVC SWA Cable	l _m	20	
		(Kiosk DB to Kiosk Sub-DBs for outside lighting	['''	20	
		Traces, DD to Mosik Gub-DDs for outside lighting			
3.3.5		16mm² Cu Insulated Earth Wire	m	Rate Only	
				_	
3.3.6		10mm² Cu Insulated Earth Wire	m	220	
TOTAL	CARRIED F	ORWARD			

ITEM	PAYMENT	DESCRIPTION	UNIT	QUANTITY	AMOUNT
TOTAL	BROUGHT I	FORWARD			
3,4		Cable Trays Supply and installation of heavy duty cable tray below complete with accessories			
3.4.1		200mm width 1.5mm thickness heavy duty cable tray, complete with fittings	m	50	
3.4.2		100mm width 1.5mm thickness heavy duty cable tray, complete with fittings	m	30	
3,5 3.5.1		Building electrical services Surface-mounted 6kA domestic DB surge complete 60A 4P, 3x20A+E/L, 3x15A, 3x5A, 4P arrestor. 30% spare capacity.	No.	1	
3.5.2		Sump - Indoor LED 40w weather-proof IP66	No.	2	
3.5.3		Indoor LED 20w vapour-proof IP65	No.		
3.5.4		Outdoor LED 100W flood light IP65	No.	4	
3.5.5		Single phase welding socket out	No.	1	
3.5.6		Surface-mounted 16A domestic socket outlet	No.	4	
3.5.7		Surface-mounted 60A 3ph industrial waterproof isolator with lockable handle	No.	Rate Only	
3.5.8		Surface-mounted 30A 3ph industrial waterproof isolator with lockable handle	No.	4	
TOTAL	CARRIED F	ORWARD			

ITEM	PAYMENT	DESCRIPTION	UNIT	QUANTITY	AMOUNT
TOTAL	BROUGHT I	FORWARD			
3.6.9		Surface-mounted 2 lever Light switch	No.	1	
3.6.10		16A Photocell (Day/night) switch	No.	1	
3.6.11		Metal conduits and fittings	m	200	
3.6.12		4mm ² General Purpose wires	m	500	
3.6.13		2.5mm ² General Purpose wires	m	500	
3.6.14		2.5mm ² Bare Copper Earth wires	m	500	
3.7		Others - Testing and Commissioning			
3.7.1		Making provision for the required inspection,tests and the commissioning of the tests and the commissioning of the complete installation and the issuing of the required certificates and handover documentation (test sheets, manuals, software, etc) including electronic datapacks.	No	1	
3.7.2		Provisional allowance for removal and disposal of electrical components involving: storing the electrical equipment in drums/containers for hazardous waste and safely disposed at a hazardous waste site	Sum	1	
3.7.3		Provisional allowance for Ligthning Protection system include installing surge arrestors class 2 or type 2 on the Distribution Boards as per SANS10142-1:2021 Ed.3	Sum	1	
3.7.4		Provisional allowance for Earthing and Bonding system	Sum	1	
3.7.5		Site training of the Client's Operations staff.	No	1	
TOTAL	CARRIED TO	O SUMMARY			

ITEM	PAYMENT	DESCRIPTION	UNIT	QUANTITY	AMOUNT
		Electrical Works (Supply and Installation of the			
3		following items)			
3,1		TIKWANA PUMP STATION 5	l		
		The Tenderer must read the drawings &	Ī		
		specifications when pricing this Bill.			
		Excavation and Trenching			
		Allowance must be made for the sifting of			
		soil when required, removal and carting			
		away of all stones and rocks including			
		dumping off site. Backfilling and compaction			
		shall be carried out as specified for overall			
		siteworks.			
3.1.1		Excavation and backfilling in soft soil	m³	10	
• • • • • • • • • • • • • • • • • • •		Executation and packnining in soft soil	'''	10	
3.1.2		Excavation and backfilling in hard rock	m³	10	
3,2		Power Supply			
",_		Supply and install a power external kiosk distribution			
		board 1500x950 mm ground-mount, 60A 3ph incomer CB,			
204		weather-proof IP65, complete with LV surge arrestors.			
3.2.1		The board will integrate a Motor Control Panel, complete			
		with busbars, indication lamps, running/tripping/stop (on/off), selector switch, ammeter, power meter, hour			
		motor readings central aper 200/ energy appear	No.	1	
3,3		Low Voltage BVC Cables Forth Wire			
3,3		Low Voltage PVC Cables, Earth Wire			
		and Terminations			
		Supply and installation of PVC SWA PVC			
		cable and Earth Wire in trenches or racking			
		complete with terminations.			
		35mm ² 4-core Cu PVC SWA Cable (From Main DB to new			
3.3.1		distribution board)	m	Rate Only	
		,		,	
3.3.2		16mm ² 4-core Cu PVC SWA Cable	l _m	Rate Only	
				,	
		10mm ² 4-core Cu PVC SWA Cable (From Main DB to			
		2.2kW inline grinder, 2.4kW dewatering pump and new			
		2.4kW submersible raw sewage pump sets, duty and			
3.3.3		standby	m	200	
3.3.4		10mm ² 3 core Cu (LN&E) PVC SWA Cable (Kiosk DB to			
		Kiosk Sub-DBs for outside lighting)	m	20	
3.3.5		16mm² Cu Insulated Earth Wire	m	Rate Only	
3.3.6		10mm² Cu Insulated Earth Wire	m	220	
TOTAL	CARRIED F	ORWARD			

ITEM	PAYMENT	DESCRIPTION	UNIT	QUANTITY	AMOUNT
TOTAL	BROUGHT I	FORWARD			
3,4		Cable Trays Supply and installation of heavy duty cable tray below complete with accessories			
3.4.1		200mm width 1.5mm thickness heavy duty cable tray, complete with fittings	m	50	
3.4.2		100mm width 1.5mm thickness heavy duty cable tray, complete with fittings	m	30	
3,5 3.5.1		Building electrical services Surface-mounted 6kA domestic DB surge complete 60A 4P, 3x20A+E/L, 3x15A, 3x5A, 4P arrestor. 30% spare capacity.	No.	1	
3.5.2		Sump - Indoor LED 40w weather-proof IP66	No.	2	
3.5.3		Indoor LED 20w vapour-proof IP65	No.		
3.5.4		Outdoor LED 100W flood light IP65	No.	4	
3.5.5		Single phase welding socket out	No.	1	
3.5.6		Surface-mounted 16A domestic socket outlet	No.	4	
3.5.7		Surface-mounted 60A 3ph industrial waterproof isolator with lockable handle	No.	Rate Only	
3.5.8		Surface-mounted 30A 3ph industrial waterproof isolator with lockable handle	No.	4	
TOTAL	CARRIED F	ORWARD			

ITEM	PAYMENT	DESCRIPTION	UNIT	QUANTITY	AMOUNT
TOTAL	BROUGHT I	FORWARD			
3.6.9		Surface-mounted 2 lever Light switch	No.	1	
3.6.10		16A Photocell (Day/night) switch	No.	1	
3.6.11		Metal conduits and fittings	m	200	
3.6.12		4mm ² General Purpose wires	m	500	
3.6.13		2.5mm ² General Purpose wires	m	500	
3.6.14		2.5mm ² Bare Copper Earth wires	m	500	
3.7		Others - Testing and Commissioning			
3.7.1		Making provision for the required inspection, tests and the commissioning of the tests and the commissioning of the complete installation and the issuing of the required certificates and handover documentation (test sheets, manuals, software, etc) including electronic datapacks.	No	1	
3.7.2		Provisional allowance for removal and disposal of electrical components involving: storing the electrical equipment in drums/containers for hazardous waste and safely disposed at a hazardous waste site	Sum	1	
3.7.3		Provisional allowance for Ligthning Protection system include installing surge arrestors class 2 or type 2 on the Distribution Boards as per SANS10142-1:2021 Ed.3	Sum	1	
3.7.4		Provisional allowance for Earthing and Bonding system	Sum	1	
3.7.5		Site training of the Client's Operations staff.	No	1	
TOTAL	L CARRIED TO	D SUMMARY			

ITEM	PAYMENT	DESCRIPTION	UNIT	QUANTITY	AMOUNT
		Electrical Works (Supply and Installation of the			
3		following items)			
3,1		TIKWANA PUMP STATION 6			
, .		The Tenderer must read the drawings &			
		specifications when pricing this Bill.			
		Excavation and Trenching			
		Allowance must be made for the sifting of			
		soil when required, removal and carting			
		away of all stones and rocks including dumping off site. Backfilling and compaction			
		shall be carried out as specified for overall			
		siteworks.			
			_	_	
3.1.1		Excavation and backfilling in soft soil	m³	3	
3.1.2		Excavation and backfilling in hard rock	m³	3	
3,2		Power Supply			
		Supply and install a power external main distribution board 500x850mm wall-mounted, with 150A 3ph incomer CB,			
3.2.1		weather-proof IP65, complete with LV surge arrestors, and			
0.2.1		introduce a 40A 3ph CB to feed power to the 5.5kW inline			
		grinder	No.	1	
3,3		Low Voltage PVC Cables, Earth Wire and Terminations			
		Supply and installation of PVC SWA PVC			
		cable and Earth Wire in trenches or racking			
		complete with terminations.			
3.3.1		35mm ² 4-core Cu PVC SWA Cable	m	Rate Only	
3.3.2		16mm ² 4-core Cu PVC SWA Cable	m	Rate Only	
		10mm ² 4-core Cu PVC SWA Cable (From Main DB to			
3.3.3		2.2kW inline grinder)	m	100	
3.3.4		10mm ² 3 core Cu (LN&E) PVC SWA Cable	m	Rate Only	
		(Kiosk DB to Kiosk Sub-DBs for outside lighting			
3.3.5		16mm² Cu Insulated Earth Wire	m	Rate Only	
		Tomm Sa modicion Editi FFIIO		a.c omy	
3.3.6		10mm² Cu Insulated Earth Wire	m	100	
TOTAL	CARRIED FO	ORWARD			

ITEM	PAYMENT	DESCRIPTION	UNIT	QUANTITY	AMOUNT
TOTAL	BROUGHT I	FORWARD			
3,4		Cable Trays Supply and installation of heavy duty cable tray below complete with accessories			
3.4.1		200mm width 1.5mm thickness heavy duty cable tray, complete with fittings	m	Rate Only	
3.4.2		100mm width 1.5mm thickness heavy duty cable tray, complete with fittings	m	8	
3,5 3.5.1		Building electrical services Surface-mounted 6kA domestic DB surge complete 60A 4P, 3x20A+E/L, 3x15A, 3x5A, 4P arrestor. 30% spare capacity.	No.		
3.5.2		Sump - Indoor LED 40w weather-proof IP66	No.	Rate Only	
3.5.3		Indoor LED 20w vapour-proof IP65	No.	Rate Only	
3.5.4		Outdoor LED 100W flood light IP65	No.	Rate Only	
3.5.5		Single phase welding socket out	No.	Rate Only	
3.5.6		Surface-mounted 16A domestic socket outlet	No.	Rate Only	
3.5.7		Surface-mounted 60A 3ph industrial waterproof isolator with a lockable handle	No.	Rate Only	
3.5.8		Surface-mounted 30A 3ph industrial waterproof isolator with lockable handle with lockable handle	No.	1	
TOTAL	CARRIED F	ORWARD			

ITEM	PAYMENT	DESCRIPTION	UNIT	QUANTITY	AMOUNT
TOTAL	BROUGHT	FORWARD			
3.6.9		Surface-mounted 2 lever Light switch	No.	Rate Only	
3.6.10		16A Photocell (Day/night) switch	No.	Rate Only	
3.6.11		Metal conduits and fittings	m	Rate Only	
3.6.12		4mm ² General Purpose wires	m	Rate Only	
3.6.13		2.5mm ² General Purpose wires	m	Rate Only	
3.6.14		2.5mm ² Bare Copper Earth wires	m	Rate Only	
3.7		Others - Testing and Commissioning			
3.7.1		Making provision for the required inspection, tests and the commissioning of the tests and the commissioning of the complete installation and the issuing of the required certificates and handover documentation (test sheets, manuals, software, etc) including electronic datapacks.	No		
3.7.2		Provisional allowance for removal and disposal of electrical components involving: storing the electrical equipment in drums/containers for hazardous waste and safely disposed at a hazardous waste site Provisional allowance for Ligthning Protection system include installing surge arrestors class 2 or type 2 on the	Sum	1	
3.7.3		Distribution Boards as per SANS10142-1:2021 Ed.3	Sum	1	
3.7.4		Provisional allowance for Earthing and Bonding system	Sum	1	
3.7.5		Site training of the Client's Operations staff.	No	1	
TOTAL	CARRIED T	 O SUMMARY			

ITEM	PAYMENT	DESCRIPTION	UNIT	QUANTITY	AMOUNT
		Electrical Works (Supply and Installation of the			
3		following items)			
3,1		WASTE WATER TREATMENT PLANT EQUIPMENT			
		Replacement of the following items			
		Supply and install, including testing and			
		commissioning of the following items			
		Replace a 3 x soft starters for 45kW Aerators at the Bio-			
3.1.1		Reactor	No.	3	
3,2		Control and Instrumentation Works			
		Provisional sum of 300,000 for repair/replace of PLC			
		system, including CPU, I/O modules (digital and analogue), communication modules, DIN-rail power			
		supplies, SD card, monitoring accessories, and all			
		associated wiring and terminal components. Configuration			
3.2.1		of the HMI and testing of all communication links between			
		the HMI, the main PLC, and any interlinked PLCs (via Wi- Fi or other existing media). Full system commissioning in			
		collaboration with the Client's representative. Handover of			
		all project documentation, PLC software, configuration			
		files, and backups upon finalcompletion.	_		
			Sum	1	
3,3		Others - Testing and Terminations			
		Making provision for the required inspection,tests and the			
		commissioning of the tests and the commissioning of the			
		complete installation and the issuing of the required			
		certificates and handover documentation (test sheets, manuals, software, etc) including electronic datapacks.			
		iniandais, soliware, etc) including electronic datapacks.	No.	1	
TOTAL	CARRIED F	I ORWARD			
			l		

Section 4: Civil and Structural

ITEM NO	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	DEMOLITIONS AND REMOVAL				
1.1	External fence and gate				
1.1.1	Existing wire fence approx 1,5 to 2m high	m	300		
1.1.2	Gate approximately 4,50m wide including concrete base	No	6		
1.2	Existing gantry structure				
1.2.1	Existing steel columns including bases	No	12		
1.2.2	Existing steel beam	No	6		
2	EARTHWORKS				
2.1	Site preparation clear and strip site				
2.1.1	Clear site including vegetation, etc	m²	900		
2.1.2	Remove topsoil to a depth of 150mm and stockpile on site within freehaul distance	m ³	135		
2.1.3	Excavations for chambers	m ³	102		
3	INLET MANHOLE				
3.1	Breaking into and connecting into existing manhole	No.	6		
	Supply and install manholes & slabs (SABS 1294)				
3.2	Precast concrete manholes 1200mm diameter, exceeding 1250mm and not exceeding 1500m deep, complete with precast concrete heavy duty cover and frame TYPE 4A	No.	12		
4	CONCRETE (STRUCTURAL)				
4.1	FORMWORK				
	Provide for the fabrication, erection, use and dismantling of formwork for				
	Rough formwork to				
4.1.1	Inside of chamber and gantry footings	m²	60		
	Smooth formwork to				
4.1.2	Sides of chamber	m²	48		
4.1.3	Edges of walls, slabs, forming openings in walls, etc. not exceeding 300mm wide or high	m	30		
Total Carrie	l d Forward				

RETROFITTING OF 6 SEWER PUMP STATIONS, INSTALLATION OF INLINE GRINDERS AND REPAIRS TO WASTE WATER TREATMENT PLANT IN HOOPSTAD AND TIKWANA

Section 4: Civil and structural

ITEM NO	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
Amount brought forward					
4.2	REINFORCEMENT				
	Mild Steel				
4.2.1	Bars not exceeding 16mm diameter	t	0,20		
	High Tensile Steel				
4.2.2	Bars not exceeding 16mm diameter	t	0,60		
4.3	CONCRETE				
	Concrete Class 20MPa/19mm in				
4.3.1	Blinding	m³	0,6		
	Strength reinforced concrete Class 25MPa/19mm in				
4.3.2	Bases, walls and roof	m³	6		
4.3.3	Bases	m³	4		
4.4	EXPANSION / ISOLATION JOINTS				
	Expansion joints, including all intersections and necessary formwork, holes, etc.				
4.4.1	Form expansion joint with 10mm thick high density foam board between vertical concrete and brickwork surfaces not exceeding 300mm high / wide	m	36		
5	OUTLET CHAMBER				
5.1	Composite manhole cover				
5.1.1	Cover to suit opening 800 x 1000mm including bedding on concrete (galvanised mild steel frame elsewhere)	No	6		
5.1.2	Cover suit opening 1400 x 1400mm including bedding on concrete (galvanised mild steel frame elsewhere)	No	6		
5.1.3	Extra for hinges	pair	24		
5.1.4	Extra for latch	No	12		
Total Carrie	d Forward				

Section 4: Civil and Structural

ITEM NO	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
Amount bro	ught forward				
6	METALWORK:				
6.1	Hot dipped galvanised manhole frames				
6.1.1	75 x 50 x 8mm Frames epoxied in position	t	0,20		
6.2	<u>Gantries</u>				
	Hot dipped galvanised mild steel columns and beams including baseplates, gussets, etc.				
6.2.1	152 x 152 x 23kg/m H-section columns	t	0,30		
6.2.2	152 x 152 x 23kg/m H-section beams	t	0,10		
6.3	Erection bolts to structural steel and concrete, etc.				
6.3.1	Graded 8,8 bolts, nuts and washers	t	0,02		
6.3.2	16mm Chemical anchors	No	16		
6.3.3	20mm Chemical anchors	No	16		
7	PALISADE FENCE				
7.1	Erect 2,05m High hot dipped galvanised palisade fence				
7.1.1	Palisade fence with palisades at not exceeding 125mm centres in 3m wide panels with posts	m	300		
7.1.2	Extra over posts for 100 x 100mm corner or gate posts 2,6m long in concrete 450 x 450 x 600mm	No	48		
7.1.3	Pedestrian gate to suit opening 1,0m wide	No	6		
7.1.4	Sliding gate 4,5m wide including guides, bottom track in concrete, etc.	No	6		
8	HOISTING EQUIPMENT				
8.1	Design, manufacture, factory test and deliver hoisting equipment, including fixing detail				
8.1.1	Manual hoisting equipment, block and chain, plus slings and beam cradle installed <u>permanently</u> . Safe Working Load 3 tons	No	5		
9	ROOF SLAB				
9.1	Allow for lifting and re-alignment of existing 8 tons slabs				
9.1.1	Lift and remove roof slabs and re-position to required angle on the same sump. Safe Working Load 8 tons	No	4		
	TOTAL COST FOR CIVIL/STRUCTURAL WORKS (EXCL VAT)				

PART C3

SCOPE OF WORK

C3 SCOPE OF WORK

C3.1 DESCRIPTION OF WORKS

- The Contractor to be appointed will undertake the full scope of work which comprises the retrofitting of 6 sewer pump stations and repairs of waste water treatment plant.
- Mechanical Scope of Work Rehabilitate the mechanical existing installation.
 Two submersible raw sewage pump sets (pumps and motors), would be installed to replace existing pump sets. The new pumps will be configured as one duty pump and one standby pump, which roles will be rotated amongst the two pumps, to achieve equitable hours of operation throughout their life cycle.
- For the purpose of the pump selections we have considered the requirements to be one pump on duty and the second on standby.
- Repair and replace mechanical existing equipment.
- Civil and Struactuaral Rehabilitation of the civil and structural integrity of the sump, chamber, and Wastewater Treatment Works (WWTW) building facilities, including the installation of new steel palisade fencing and the construction of new manholes to accommodate inline grinder installations.
- Electricity Scope of Work Rehabilitate the electrical existing equipment including LV cabling and small power and lighting. Install DoL motors and automation of the pumping system and upgrade the MCPs (motor control Panels).
 Repair and replace PLC system and installation of 3 x soft starters for 45kW Aerators at the Bio-reactor.

C3.1.1 LOCATION OF WORKS

Location of Sites:

The sites of the works are the existing at Hoopstaad and Tikwana pump stations, which are situated along R700 provincial road between Bloemfontein and the North West Province. The main town is Hoopstad and its twonship is Tikwana.

C3.1.2 NATURE OF WORKS

The description of the project contained in this section is merely an outline of the contract works and shall not limit the work to be carried out by the Contractor under this contract. Approximate quantities of each type of work to be carried out in accordance with the contract documents are listed in the Bill of Quantities bound in this volume.

C3.1.3 SCOPE

C3.1.3.1 Mechanical Scope of Work

Scope Statement

Replacement, installation, and commissioning of mechanical equipment and associated ancillary systems for 6 sewer pump stations and repairs of waste watertreatment plant. The scope of facilities and activities includes but is not limited to the following items:

Install low lift equipment comprising:

- Two submersible raw sewage pump sets (pumps and motors), would be installed to replace existing pump sets. The new pumps will be configured as one duty pump and one standby pump, which roles will be rotated amongst the two pumps, to achieve equitable hours of operation throughout their life cycle. high lift pump sets (pumps and motors), would be installed to replace existing pump sets. The new pumps will be configured as one duty pump and one standby pump, which roles will be rotated amongst the two pumps, to achieve equitable hours of operation throughout their life cycle.
- a. For the purpose of the pump selections we have considered the requirements to be one pump on duty and the second on standby.
- b. Installation of inline grinders;
- c. Suction side and delivery side pipework, complete with fittings;
- d. Suction and delivery side isolating valves;
- e. Non-return valves;
- f. Electromagnetic flowmeter;
 - Pump protection probes, comprising no flow switches, pressure switches, vibration probes; temperature probes; and related control wiring to the MCPs;
 - Painting and demarcation of floors; and
 - Plinths for each low lift pump.

Waste Water Treament Plant

- a. Repair/replace of the Berson Ultraviolet unit in the treated effluent pump station;
- b. Repair/replace Mechanical Screen;
- c. Replace 2 x 5.5 kw mixers at the Bio-Reactor;
- d. Replacement of 2 x Kw Aerators at the Bio-Reactor;
- e. Replace a close couple 1 x 45 Kw pump in the Golf-club pump station;
- f. Installation of new complete Drive Cage Assembly for the clarifiers;
- g. Replacement of Centre bearings (clarifiers); and
- h. Re-alignment of the Scum Skimmer with the Scum Box (clarifiers).

i.

C3.1.3.2 Civil and Building Scope of Work

Scope Statement

Replacement, installation, and commissioning of civil and building infrastructure for 6 sewer pump stations and repairs of waste watertreatment plant. The scope of facilities and activities includes but is not limited to the following items:

- a) Repairs of the existing inlet and outlet chambers for various manholes;
- b) Pump station building rehabilitation and upgrade works;
- c) Construction of new manholes to accommodate inline grinders installations;
- d) New installation of steel palisade fencing;
- e) Clear and glub within site boundary;
- f) Reconfigure roof slab layout for ease of access/maintenance; and
- g) Install gantry structures and hoisting equipment

C3.1.3.3 Electrical, Control and Instrumentation Scope of Work

Scope Statement

Replacement, installation, and commissioning of Electrical and C&I equipment associated ancillary systems for 6 sewer pump stations and repairs of waste watertreatment plant. The scope of facilities and activities includes but not limited to the following items:

- h) Installation of a new 630kVA pole-mounted;
- i) Installation of new motor supply cables, LV cables;
- j) Supply, rigging into position and commissioning of new low lift pump sets;
- k) Installation of supply cables to new pumps;
- I) Supply and installation of cable trays;
- m) Pump efficiency measurement and monitoring;
- n) Installation pump stations electrical services
- o) Testing and commissioning of the entire installation;
- p) Training of the staff; and
- q) Issuing certificate of compliance according SANS 10142.

Waste Water Treament Plant

- r) Installation of 3 x soft starters for 45 Aerators at the Bio-Reactor;
- s) Repair/replace of PLC system, including CPU, I/O modules (digital and analogue), communication modules, DIN-rail power supplies, SD card, monitoring

accessories, and all associated wiring and terminal components. Configuration of the HMI and testing of all communication links between the HMI, the main PLC, and any interlinked PLCs (via Wi-Fi or other existing media). Full system commissioning in collaboration with the Client's representative. Handover of all project documentation, PLC software, configuration files, and backups upon finalcompletion.

C3.1.4 TIME FOR COMPLETION

The construction period for this project is estimated to take 6 months.

C3.1.5 GENERAL INFORMATION

C3.1.5.1 Drawings

The reduced drawings contained in C5 that form part of the tender document shall be used for tender purposes only. Further drawings are to be provided on an on-going basis by the engineer.

Any information in the possession of the contractor, which the resident engineer requires to complete the as-built drawings, shall be supplied to the resident engineer before a certificate of completion will be issued.

Only figured dimensions shall be used and drawings shall not be scaled unless so instructed by the engineer. The engineer will supply all figured dimensions omitted from the drawings.

C3.1.5.2 Power, Water Supply and Other Services

The contractor shall make his own arrangements concerning the supply of electrical power and all other services. No direct payment will be made for the provision of electrical and other services. The cost of providing these services will be deemed to be included in the rates and amounts tendered for the various items of work for which these services are required.

C3.1.5.3 Contractor's Camp Site and Security

The contractor shall make his own arrangements regarding the establishment of a camp site and housing for his construction personnel and all regulations stipulated by the local authority shall be adhered to.

It is anticipated that the contractor's choice of a camp site will be influenced by the availability of telephone and electrical connections as well as the supply of potable water. Provision is made in these specifications for the erection of a security fence around the site offices. The contractor shall be responsible for the security of his personnel and constructional plant on and around the site of the works and for the security of his camp, and the employer will consider no claims in this regard.

C3.1.5.4 Additional Requirements for Construction Activities

- C3.1.5.4.1 The contractor may not commence constructional activities before adequate provision has been made to accommodate traffic in accordance with the requirements of this document and the South African Road Traffic Signs Manual.
- C3.1.5.4.2 The contractor shall submit proposals in connection with directional signs to the engineer for approval.

C3.1.5.5 Programme Requirements for Construction Activities

C3.1.5.5.1 The contractor shall programme his activities to be suitable in terms of his resources to complete the contract inside the stipulated time period.

C3.1.5.6 Construction in Confined Areas

It may be necessary for the contractor to work in confined areas. The method of construction in these confined areas depends on the contractor's construction plant. However, the contractor must note that measurement and payment will be in accordance with the specified cross-sections and dimensions, irrespective of the method used to achieve these cross-sections and dimensions, and that the rates and amounts tendered will be deemed to include full compensation for any special equipment or construction methods or for any difficulty encountered in working in confined areas and narrow widths, and at or around obstructions, and that no extra payment will be made nor will any claim for payment be considered on account of these difficulties.

C3.1.6 BARRICADING OF EXCAVATIONS

All excavations in close proximity to pedestrian and vehicular traffic are to be barricaded to the satisfaction of the Engineer. Barricading shall consist of a minimum of two strands of parallel and horizontal wire of at least 2mm gauge, the topmost strand being fixed at least 1m above ground level. These wires shall be fixed to the approved fence posts, which shall be securely fixed in a vertical position.

The visibility of these barricades shall be enhanced by the attachment of high visibility construction tape to the posts and wire strands and by the placing of reflective signing to the Engineer's satisfaction. All costs arising from these requirements are to be included in the tendered rates for excavation.

C3.1.7 CONTINUITY OF WATER SUPPLY

It is an important aspect of this project to keep the plant in operation. Thus, continuous water supply to the final consumer must take preference to any construction action affecting the supply of water, i.e.

- The water supply may only be stopped intermittently (4 hours per day) at a time, but
 with one week's written notice to the Engineer and his subsequent approval after
 consulting with the Client prior to a shutdown. The main criteria for consideration will
 be the percentage of full water capacity of the main service reservoirs.
- The Contractor will have to continually co-ordinate his operation concerning the water

availability and usage with the Resident Engineer on site.

C3.1.8 ENGINEERING

C3.1.8.1 DESIGN

- C3.1.8.1.1 The Employer is responsible for the design of the permanent Works as reflected in these Contract Documents unless otherwise stated.
- C3.1.8.1.2 The Contractor is responsible for the design of the temporary Works and their compatibility with the permanent Works.
- C3.1.8.1.3 The Contractor shall supply all details necessary to assist the engineer in the compilation of the as-built drawings.

C3.1.8.1.4 Employer's Design

Detail Description of Works (General Works)

C3.1.8.1.5 Contractor's Design

Where contractor is to supply the design of designated parts of the permanent Works or temporary Works he shall supply full working drawings supported by a professional engineer's design certificate.

C3.1.8.2 DESIGN PROCEDURES

All designs and modifications thereto shall be communicated in writing and the contractor and engineer shall maintain master lists to record and track all transactions.

C3.1.8.3 EQUIVALENCY OF STANDARDS AND CODES

Wherever reference is made in the Contract to specific standards and codes to be met by the goods and materials to be furnished, and work performed or tested, the provisions of the latest current edition or revision of the relevant standards and codes in effect shall apply, unless otherwise expressly stated in the Contract. Where such standards and codes are national, or relate to a particular country or region, other authoritative standards which ensure an equal or higher quality than the standards and codes specified will be accepted subject to the Engineer's prior review and written approval. Differences between the standards specified and the proposed alternative standards must be fully described in writing by the Contractor and submitted to the Engineer at least 7 days prior to the date when the Contractor desires the Engineer's approval. In the event the Engineer determines that such proposed deviations do not ensure equal or higher quality, the Contractor shall comply with the standards specified in the documents.

C3.2 STANDARD SPECIFICATIONS

C3.2 STANDARD SPECIFICATIONS – MECHANICAL, ELECTRICAL, CONTROL AND INSTRUMENTATION ENGINEERING

The following ISO and SANS electromechanical specifications shall apply for the construction of the works:

ID	Standard ID	Title
1	BS 159	Bus bars
2	BS 89	Ammeters
3	BS 3938	Current Transformers
4	BS 639	Welding cables
5	ISO 5210:1991	Industrial valves Multi-turn valve actuator attachments
6	ISO 5211:2001	Industrial valves - Part-turn actuator attachments
7	ISO9905:1994	Technical specifications for centrifugal pumps
8	NRS 002 -	Graphical symbols for electrical power, telecommunications and electronic diagrams
9	NRS 029	Current Transformer
10	SANS 10142-1:2012	The Wiring of Premises, Part 1: Low-voltage installations
11	SANS 10292	Earthing of low voltage distribution systems
12	SANS 1091	Paint Colour
13	SANS 119	Bus bars
14	SANS 1213 -	Mechanical cable glands
15	SANS 1433-1	Terminal blocks having screws and screw less terminals
16	SANS 1433-2	Flat push-on connectors
17	SANS 1473-1	Low voltage switchgear and control gear assemblies: Type-tested and partially type-tested assemblies
18	SANS 1473-2	Low voltage switchgear and control gear assemblies: Bus bar trunking systems.
19	SANS 156	Moulded Case Circuit Breakers
20	SANS 1574	Electric cables and flexible cords
21	SANS 1576	Welding cables
22	SANS 1619	Small power distribution units (ready boards) for single-phase 230 V service connections.
23	SANS 1765	Safety of distribution boards
24	SANS 60044	Current Transformers
25	SANS 60439-2	Low voltage switchgear and control gear assemblies: particular requirements for bus bar trunking systems

ID	Standard ID	Title
26	SANS 60439-4	Low voltage switchgear and control gear assemblies: particular requirements for assemblies for construction sites
27	SANS 60947-2	Low voltage switchgear and control gear: Circuit breakers
28	SANS 60947-3	Low voltage switchgear and control gear: switches and disconnects
29	SANS 60947-4-1	Low voltage switchgear and control gear: Contractors and motor starters (Electromechanical)
30	SANS 60947-4-2	Low voltage switchgear and control gear: Contractors and motor starters (semiconductor motor controller)
31	SANS 60947-4-3	Low voltage switchgear and control gear: Contractors and motor starters (for non-motor loads)
32	SANS 60947-5.1	Low voltage switchgear and control gear: Electromechanical control circuit devices
33	SANS 60947-5.2	Low voltage switchgear and control gear: Electrical emergency stop device with mechanical latching function
34	SANS 62-1:2013	Steel pipes Part 1: Pipes suitable for threading and of nominal size not exceeding 150 mm
35	SANS 62-2:2013	Steel pipes Part 2: Screwed pieces and pipe fittings of nominal size not exceeding 150 mm
36	SANS 664-1:2011	Wedge gate and resilient seal valves for waterworks Part 1: General
37	SANS 664-1:2011	Wedge gate and resilient seal valves for waterworks Part 2: Wedge gate valves
38	SANS 719:2011	Electric welded low carbon steel pipes for aqueous fluids (large bore)
39	SANS 767	Earth leakage protection units

C 3.3 TECHNICAL SPECIFICATIONS – MECHANICAL WORKS

C3.3 TECHNICAL SPECIFICATIONS – MECHANICAL WORKS

C3.3.1 CONTRACTOR'S ESTABLISHMENT ON SITE AND GENERAL CHARGES

C3.3.1.1 SCOPE

The Tenderer shall allow under Schedule 1 for all preliminary and general charges associated with the Contract as a whole and shall thus include the relevant charges associated with any/all sub-contractors and suppliers appointed under the Contract.

C3.3.1.2 NOTICES, SIGNS AND ADVERTISEMENTS

The Tenderer shall allow for the supply and erection of one (1No) contract notice board in terms of the issued drawing. The notice board shall be erected at a suitable location as confirmed by the Engineer.

C3.3.1.3 COMPLIANCE WITH OCCUPATIONAL HEALTH AND SAFETY ACT, ITS REGULATIONS AND THE EMPLOYER'S HEALTH AND SAFETY SPECIFICATION

The Tenderer shall refer to relevant sections included within this document for the Employer's Health and Safety Specification and shall make adequate allowance in the tendered fixed and time-related rates for compliance to the said Specification.

C3.3.1.4 COMPLIANCE WITH ENVIRONMENTAL MANAGEMENT PLAN

The Tenderer shall refer to relevant sections included within this document for the applicable Environmental Management Plan (EMP) and shall make adequate allowance in the time-related rates for compliance to the said Specification during the period of installation on Site.

C3.3.2 SCOPE

C3.3.2.1 Hoopstaad Commando

ID	Item	Specification
1	Туре	Submersible – Duck foot type (Guide Rail)
2	Capacity (m³/hr)	51.84
3	Head (m)	13.97
4	Pump Speed (rpm)	1450
5	Motor Size	3.5 kW, 400 V, 4 Pole
6	Impeller	Stainless steel
7	Shaft	Chrome steel

Table 1 Hoopstaad Commando

C3.3.2.2 Tikwana No.1

ID	Item	Specification
1	Туре	Submersible – Duck foot type (Guide Rail)
2	Capacity (m³/hr)	122.4
3	Head (m)	21.37
4	Pump Speed (rpm)	2925
5	Motor Size	11 kW, 400 V, 4 Pole
6	Impeller	Stainless steel
7	Shaft	Chrome steel

Table 2 Tikwana No.1

C3.3.2.3 Tikwana No.2

ID	Item	Specification
1	Туре	Submersible – Duck foot type (Guide Rail)
2	Capacity (m³/hr)	59.4
3	Head (m)	8.54
4	Pump Speed (rpm)	2760
5	Motor Size	2.6 kW, 400 V, 4 Pole
6	Impeller	Stainless steel
7	Shaft	Chrome steel

Table 3 Tikwana No.2

C3.3.2.4 Tikwana No.3

ID	Item	Specification
1	Туре	Submersible – Duck foot type (Guide Rail)
2	Capacity (m³/hr)	30.924
3	Head (m)	7.55
4	Pump Speed (rpm)	2905
5	Motor Size	1.2 kW, 400 V, 4 Pole
6	Impeller	Stainless steel
9	Shaft	Chrome steel

Table 4 Tikwana No.3

C3.3.2.5 Tikwana No.5

ID	Item	Specification
1	Туре	Submersible – Duck foot type (Guide Rail)
2	Capacity (m³/hr)	48.24
3	Head (m)	11.1
5	Pump Speed (rpm)	1450
6	Motor Size	2.4 kW, 400 V, 4 Pole
7	Impeller	Stainless steel
8	Shaft	Chrome steel

Table 5 Tikwana No.5

C3.3.2.6 Dewatering pumps for all stations

ID	Item	Specification
1	Туре	Submersible
2	Capacity (m³/hr)	34.2
3	Head (m)	9.5
5	Pump Speed (rpm)	1450
6	Motor Size	1.2 kW, 400 V, 4 Pole
7	Impeller	Stainless steel
8	Shaft	Chrome steel

Table 6 Dewatering pumps for all stations

C3.3.3.1 FLOW METERS

Each flow meter supplied under this contract shall be equipped with separate mountable signal converter unit complete with sufficient length of signal cable. The signal converter shall be locally programmable and shall be supplied complete with programmer unit. The signal converter shall furthermore have a LCD display for instantaneous flow and totalize flow and shall have a 4-20mA and pulsed output for remote indications. The signal converter unit will be mounted in an outdoor type cubicle.

C3.3.3.2 Electromagnetic flow meters

The following meter(s) shall be supplied and installed:

a) LLPS delivery side magflow meter Operating range: (0 - 300 l/s)

Each flow meter shall be able to record reverse flow.

C3.3.4 VALVE CONSTRUCTION AND OPERATIONAL REQUIREMENTS

Bodies

Hubs for shaft-bearing housings shall form an integral part of the valve body.

Valves bodies shall have adjustable mechanical stops to prevent over travel of the valve disc in the open or closed position. These stops may be incorporated in an actuator.

Discs

Discs shall be a single casting of approved hydrofoil section with a smooth continuous surface. The maximum combined stresses in the disc shall not exceed 20% of the minimum yield stress of the material used when the specified unbalanced pressure is applied on any of the two sides.

Retaining Rings

Stainless steel retaining rings shall be coated to reduce galvanic corrosion (Refer to Standard Specification DWS 9900 Section C3). Any recess for the retaining ring in the disc or body shall be coated and the retaining rings assembled whilst the coating is still wet.

Seats and Seals

Preference shall be given to resilient seal arrangements that are removable, replaceable and adjustable from the downstream side of the valve, without having to remove the valve from the pipeline.

Resilient seals shall have non-weathering, non-sticking, long life properties and shall be compatible with the quality of water to be conveyed.

The seat profile shall be smooth and continuous and shall provide adequate "lead in" for the resilient seal to open and to close on the stainless steel seat only.

Seats and seals shall be of a design that would prevent them from becoming loose and obviate water seepage under the seals or seats during all conditions of operation and test.

Shafts

Shafts can either be continuous or a stub-shaft design configuration. Stub shafts shall extend into the disc hub for a distance of at least 1.5 shaft diameters and shall not protrude from the hubs i.e. exposing the shaft.

Shafts shall be attached to discs by means of keys, dowel pins, taper pins or any combination of the three and the connection shall be designed to transmit shaft torque equivalent to at least 75% of the torsional strength of the shaft. Dowel and taper pins shall be mechanically secured.

Bearings

Self-lubricating sleeve type bearings shall be fitted in the hubs in the valve body.

Each valve shall be fitted with at least one adjustable thrust bearing set to hold the disc securely concentric with the body or seat.

C3.3.4.1 Non-return valves

Non-return valves at pump stations shall be of a tilted disc type

ID	Item	Specification
1	Туре	Tilted Disc
2	Body	SG Iron or Cast Steel
3	Disc Material	Cast Steel BS 1504-161
4	Disc Seat Material	Stainless Steel, Grade 308
5	Body Seat Material	Stainless Steel, Grade 304L
6	Stroke of Operation	Not more than 40 degrees
7	Dashpot	Not required
8	Valve Position Indicator	Yes
9	Pressure rating	PN25
10	Flanges	To SANS 1123
11	End cover O-ring	Nitrile Rubber 70 NBR
12	Corrosion Protection	Fusion Bonded Epoxy, to 150 microns

Table 7 Non-return Valve Specifications

C3.3.4.2 Wedge Gate valves (delivery)

ID	Item	Specification
1	Body	SG Iron or Cast Steel
2	Spindle	Stainless Steel, Rising type
3	Gate Nut	Bronze
4	Body Seat	Stainless Steel, Grade 304L
6	Gate Seat	Stainless Steel, Grade 316
7	Pressure rating	PN25
8	Flanges	To SANS 1123
9	Corrosion Protection	Fusion Bonded Epoxy (FBE), to 150 microns

Table 8 Wedge Gate Valves (Delivery Side of Pumps)

C3.3.4.3 Wedge Gate Valves (Suction Side of Pumps)

Technical specifications for wedge gate valves on the suction side of pumps are listed hereunder.

ID	Item	Specification
1	Body	SG Iron
2	Spindle	Stainless Steel, Rising type
3	Gate Nut	Bronze
4	Body Seat	Stainless Steel, Grade 304L
6	Gate Seat	Stainless Steel, Grade 316
7	Pressure rating	PN10
8	Flanges	To SANS 1123
9	Corrosion Protection	Fusion Bonded Epoxy (FBE), to 150 microns

Table 9 Wedge Gate Valves (Suction Side of Pumps)

C3.3.4.4 Pump Control Valves

Pump control valves shall meet specifications that are listed in the schedule below.

ID	Item	Specification
1	Туре	Hydraulically operated, diaphragm- actuated, active check valve that opens fully or shuts off in response to electric signals
2	Body	Ductile Iron, Globe Valve, Angle Pattern Design
3	Fail safe mechanism	Yes
4	Double chamber	Yes
4	Operation	Hydraulic, electric and Spring operated, for start-up control, normal shutdown control, as well as power failure shutdown control
5	Control System	3-way solenoid pilot, check valves, limit switch, isolating cock valves
6	Seat	Replaceable, raised stainless steel ring seat
7	Flow Patch	Unobstructed
8	Actuator	Double-chamfered with an inherent separating partition
9	Valve shaft	Stainless Steel
10	Pressure Rating	PN25
11	Flange	To SANS 1123
	Internals	Stainless Steel and Brass

ID	Item	Specification
12	Elastomers	NBR (Acrylonitrile butadiene rubber)
Table '	10 Pump Control Valves	
19	Integral heater to avoid conde	ensation Yes
20	LED Indicators (colour-coded) Open, Closed and Failure

Table 11 Actuator Specifications

C3

3.3.5	}	SCHEDULE OF EQUIPMENT AND MATERIALS EQUIPMENT)	OFFERED (MECHANICAL
C3.3	.5.1	Low Lift Pumps	
	Pum	p Designation	
	Man	ufacturer	
	Туре	e of Centrifugal Pump	
	Num	ber of Stages	
	Mak	9	
	Mod	el Number	
	Spee	ed (RPM)	
	Pow	er Requirements (V/ph/A/kW)	
	Mas	s (kg)	
	Pow	er Consumed at duty point (kW)	
	Cou	ntry of origin	
	Deliv	very lead time (sea freight)	
	Deliv	very lead time (air freight)	
	TSW	ere a workshop to repair pump in South Africa? /ELOPELE LOCAL MUNICIPALITY may need to y this information.	
		there technicians to effect repairs and to provide sales service in South Africa?	

RETROFITTING OF 6 sewer pump stations , INSTALLATION OF INLINE GRINDERS AND REPAIRS TO WASTE WATER TREATMENT PLANT IN HOOPSTAD AND TIKWANA

SCOPE OF WORK

Name reference sites vinstalled in South Afric	where similar pumps are a	
Site	Year installed	Contact Person and Tel No.
a.		
b.		
C.		
d.		
Pump Performance		***************************************
One Duty Pump		
Duty point flow spec	cified (I/s)	91.45
Duty point head specified (m)		190.5
Duty point flow offer	red (I/s)	
Duty point head offe	ered (m)	
Hydraulic efficiency (%)		
Overall efficiency (%	6)	
$NPSH_{R}\left(m\right)$		

C 3.4 TECHNICAL SPECIFICATIONS – ELECTRICAL WORKS

C3.4 TECHNICAL SPECIFICATIONS – ELECTRICAL, CONTROL AND INSTRUMENTATION WORKS

PREAMBLE

AMENDMENTS TO THE STANDARD AND PARTICULAR SPECIFICATIONS (PROJECT SPECIFICATIONS – ELECTRICAL, CONTROL AND INSTRUMENTATION WORKS)

INDEX

UPS

MSS	MINIATURE SUBSTATIONS
мсс	MOTOR CONTROL CENTRES
EC	ELECTRICAL CABLES
EDS	ELECTRICAL DISTRIBUTION SYSTEM
TMS	TELEMETRY SYSTEMS
PLC	PROGRAMMABLE LOGIC CONTROLLERS

UN-INTERRUPTED POWER SUPPLY

C3.4.1 MINIATURE SUBSTATIONS

No miniature substation shall be required.

C3.4.2 MOTOR CONTROL CENTRES AND DISTRIBUTION BOARDS

INDEX

ITEM	DESCRIPTION
MCC 01	SCOPE
MCC 02	CONDITIONS TO SERVICE
MCC 03	STANDARDS AND TESTS
MCC 04	CONSTRUCTION
MCC 05	GENERAL REQUIREMENTS
MCC 06	MOTOR STARTERS AND ACCESSORIES FOR SWITCHBOARDS
MCC 07	DANGER SIGN
MCC 08	ELECTRONIC LEVEL CONTROL
MCC 09	EMERGENCY STOP PUSH BUTTONS AND WEATHERPROOF ISOLATORS
MCC 10	EARTHING
MCC 11	INFORMATION TO BE SUBMITTED WITH TENDERS IN RESPECT OF THE 400 VOLT DISTRIBUTION BOARDS AND MOTOR CONTROL BOARDS
MCC 12	INFORMATION TO BE SUBMITTED BY THE SUCCESSFUL TENDERER
MCC 13	INSPECTIONS AND TESTS
MCC 14	TESTING OF DISTRIBUTION/MOTR CONRTOL BOARDS AT THE MANUFACTURER'S WORKS
MCC 15	CONCRETE PLINTHS FOR OUTDOOR STARTER PANELS AND PEDESTALS
MCC 16	INSTALLATION OF DISTRIBUTION BOARDS AND MOTOR CONTROL BOARDS
MCC 17	TESTING AND COMMISSIONING OF DISTRIBUTION/MOTOR CONTROL BOARDS AFTER INSTALLATION ON SITE
MCC 18	OPERATING AND MAINTENANCE INSTRUCTIONS
MCC 19	MEASUREMENT AND PAYMENT

C3.4.2.1 MCC 01: SCOPE

This specification includes the design, manufacturing, delivery, transport, handling, protection, storage, installation, successful commissioning and upholding during the Defects Liability Period.

The following information regarding the switch- and distribution boards shall be submitted with each tender

- a) The name and address of the switchboard manufacture.
- Full technical details and descriptive literature regarding all equipment and instruments offered.
- c) Three paper prints of an outline drawing of each board indicating the main overall dimensions and general lay-out of the boards; and
- d) Three paper prints of an outline drawing of the front end processor cabinet indicating the main overall dimensions, general layout and type of material employed on the face of the panel.

C3.4.2.2 MCC 02: CONDITIONS TO SERVICE

The motor control centres shall be installed indoors and outdoors on an industrial plant.

C3.4.2.3 MCC 03: STANDARDS AND TESTS

The motor control centres shall conform to and be in accordance with the latest applicable South African Bureau of Standards Codes and Standards.

C3.4.2.4 MCC 04: CONSTRUCTION

Distribution and motor control boards with a short-circuit withstand current rating of 10kA and higher shall comply with all type test requirements by either self-certification by the manufacturer, type test certification of the manufacturers must be submitted, or by means of a Certificate of Compliance issued by an accredited person for type-tested assemblies.

The board shall be of the free standing floor mounted cubicle type with IP 55 insect proofed enclosure, constructed of at least 2 mm steel on a rigid channel iron or similar frame, and shall be bolted down in position by means of M16 high tensile stainless steel bolts grouted into the concrete floor of the pump station building. The bolts shall be inside the board.

The overall height of the board shall not exceed 2400mm and overall depth shall not be less than 450mm and shall not exceed 600mm. The construction of the board shall be such that future extension panels may be fitted on both sides and alterations can be done without major changes to the board. (Modular construction will be preferred.)

The board shall be provided with readily removable covers on the sides and hinged panels on the front.

All removable covers shall be suitably braced and reinforced to ensure rigidity.

All hinged panels shall be reinforced to ensure rigidity and shall be provided with heavy duty rust proof hinges.

Each door shall be supplied with completely hinges, each fastened with not less than four (two on each side) brass bolts and nuts. In the case of double doors the first door shall be locked with two slides on the inside, onto the kiosk shell. The second door shall close over a drip proof gutter shaped lip on the first one.

The doors shall be provided with a locking system suitable for padlocking. The locking system shall consist of a 3 way locking mechanism locking the door at the top, middle and bottom.

All switchgear, instruments and equipment for the control of any specific motor or other electrical device shall be mounted flush behind a common hinged panel, with only operating handles, push buttons and instrument faces protruding through neatly machine punched holes in the panel.

Motor starter panes shall be a segregated system with each motor starter housed in a separate panel complete with door interlocked main switch. Where motor starter panels are installed on top of a common cable marshalling panel. Provision shall be made for prewiring between the starter panel and cable connectors inside cable marshalling panel to facilitate site cable connections.

The board shall be provided with readily removable, sectionalized, rigidly supported unpainted 3 CR12 cable end support gland plates along the entire length of the board and at least 230mm above floor level.

Space shall be provided for future switchgear and equipment where specified.

The board shall be suitably sized to accommodate without cramping, all the switchgear and equipment specified.

Screwed-on engraved labels in English shall be provided below all switchgear and equipment on and in the panels to facilitate identification.

The board shall be provided with one set of four solid, copper bus bars in the top section and extending over the entire length of the board. Provision shall be made at the end of each bus bar for future extensions.

Bus bars shall comply with the requirements of BSS 1433 and the relevant clauses of BSS 159.

Bus bars shall be rigidly supported at suitable intervals to prevent undue damage resulting under short circuit conditions. Ceramic or other approved bus bar insulators shall be used. The bus bar shall be arranged horizontally with the longer sides of the cross-sections in the vertical plane and one behind the other, in the horizontal plane, at 90 mm centres.

Bus bars shall be clearly and indelibly marked in the middle of the bus bar Red, White and Blue for the three phases and Black for Neutral.

Connections to bus bars shall be effected by means of cable lugs and suitably sized cadmium-plated, high tensile steel bolts and nuts with cadmium-plated cup washers or lock washers. Spare connections shall be provided complete with bolts, nuts, washers and spring washers.

All screws, studs, bolts, nuts and washers used for these boards shall be Cadmium plated. The use of self-tapping screws will not be permissible. A solid copper earth bar shall be provided inside the board above the gland plate along the entire length of the board.

The earth bar shall have a cross-section of at least 150mm depending on the main bus bar sizes.

The earth bars shall be drilled and provide with 6mm dia and 10mm dia cadmium plated, high tensile steel bolts and nuts, complete with cadmium-plated washers and cup washers

or lock washers for making the earth connections. The earthing positions shall be evenly spaced along the entire length of each bus bar.

The outdoor motor control boards shall be constructed of at least 2mm powder coated 3CR12 steel complying with the specification for indoor boards, but shall be not more than 1500mm high. Vermin proofed IP 54 rated ventilation openings shall be provided in doors and side panels.

Where electronic equipment such as transmitting I/O units are incorporated in an outdoor distribution and motor control board, this equipment shall be installed in a separate and special compartment and all wiring shall be terminated on rail mounted terminal strips for field connection of all monitoring and control cables.

This compartment shall if necessary consist of an outer and inner shell with at least 10mm insulation or polystyrene between the inner and outer shell all round to keep the temperature inside the compartment at least 5 decree C below the temperature surrounding the compartment in summer complete with ventilation fans.

The doors of this compartment must be labelled "Electronic Equipment"

Sufficient provision for breathing and heat dissipation must be made in this compartment.

C3.4.2.5 MCC 05: GENERAL REQUIREMENTS

Internal Wiring

The internal wiring of the boards shall consist of coloured PVC –insulated conductors of adequate copper cross-section, which shall be neatly installed horizontally and vertically in PVC trunking. Numbered ferrules of an approved type (clip on type not acceptable), shall be provided on each end of each wire to facilitate the tracing of circuits.

Control circuit shall be colour coded as follows:

A.C Live Red

A.C. Neutral Black

110 V D.C Positive Grey

110 V D.C. Negative Grey

24 V D.C +ve Brown

24 V D.C –ve Orange

4-20mA Purple

All other voltages Violet

Status Signals Pink

Earth Green and yellow

Electronic Equipment

Where electronic equipment such as transmitting I/O units are incorporated in a distribution – and motor control board, this equipment shall be installed in a separate and special compartment.

Sufficient room shall be provided for all rail mounted terminal strips and all wiring shall be terminated on these rail mounted terminal strips for field connection of all monitoring and control cables.

The door must be labelled "ELECTRONIC EQUIPMENT"

Cable Terminations

Cable terminations shall be suitable to accommodate the cable or cables for each circuit as specified. This applies not only to the number of cores, size and conductor material, but also to the type and construction of the cables.

Cable terminations shall be complete with the necessary clamps, glands, terminating and other accessories. Heat shrink cable ends must be complete with all accessories.

Mechanical cable glands for control and auxiliary cables shall be suitable for PVC/PVC/SWA/PVC type cables. The armouring shall be clamped firmly to ensure reasonably good electrical connection and to prevent the cables from being pulled out easily. Each gland shall be complete with a neoprene shroud and one locknut.

Labelling of Switchboards and Motor Control Boards

A screwed on engraved label of the black and white "trefolite" type shall be provided below each item of equipment of the front panel of each board as well as on the chasis in close proximity to the relevant equipment to identify such equipment in the English language in 6mm high lettering.

Each board shall further be provided with a screwed on reverse engraved yellow Perspex nameplate with black 20mm high lettering to identify the board in the English language on the outside of the door at the top thereof.

Motor starter panels

All metal parts shall be treated before powder coating in accordance with standard corrosion protection standards and the appropriate coating system shall be selected for the specific application. Motor control centre outer surfaces shall be powder coated colour B26, SANS 1091. (Electric orange)

C3.4.2.6 Mcc 06: MOTOR STARTERS AND ACCESSORIES FOR SWITCHBOARDS

Direct- on- line starters (380 V motors)

These starters shall be of the manually operated (locally and remotely) type and each starter shall be contained in its own separate compartment on the relevant motor control board.

Each of these units shall comprise amongst other the following components:

- a) 1 Only mains fused switch/circuit breaker connected to the bus bars of the board and interlocked with the door of the compartment to prevent opening of the door with the switch closed and to prevent closing of the switch with the door open.
- a) 1 Set of HRC control fused links with carriers and basis where necessary;
- b) All necessary relays as required.
- c) 1 Only mains contractor
- d) 1 Set of START and STOP push buttons
- e) 1 Only mains operated timing device to limit starts per hour; and

f) 1 Only power factor correction capacitor unit for motors of 5kW and more.

The following protective and indicating devices complete with the necessary suitably rated potential fuses, current transformers, test blocks and auxiliary relays:

- a) 1 Only electronic type motor protection relay for motors of 7, 5kW or more or as specified
- b) 1 Only motor under current relay (Where specified)
- c) 1 Only instantaneous indicating ammeter for motor current
- d) 1 Only ammeter selector switch for motors of 5kW or ore
- e) 3 Only Current transformers for motors of 5kW or more;
- f) 1 Only running hour meter;
- g) 1 Only anti-cycle timer and
- h) 1 Only thermister relay for motors of 22kW or more
- i) 1 Only Start delay timer for motors of 15kW and higher
- j) 1 Only blue LED type indicator light to indicate the time delayed starting period.
- k) 4 Only LED type indicator light as follows "Supply on Green Motor Running;
 Amber Motor Tripped and blue Motor start delay red Emergency stop engaged.

It shall further be possible trip and lock out the starter by means of a remote stop button to be provided at the relevant motor.

Provision shall also be made for locking the mains fused switch handle in the OFF position

Star/Delta Starters (380 V motors)

These starters shall be of the automatic star/delta type and each starter shall be contained in its own separate compartment on the relevant motor control board.

Each of these units shall comprise amongst others provided for direct on line starters the following components as:

- a) 1 Only Mains Contactor
- b) 1 Only Star Contactor
- c) Only Delta Contactor
- d) 1 Only Star to Delta timer of the clockwork or electromagnetic type
- e) 1 Only Mains operated timing device to limit the starts per hour
- f) 1 Set START and STOP pushbuttons
- g) 1 Only Three phase Power Factor Correction Capacitor unit for motors of 5kW or more
- h) All necessary relays

Variable Speed Drives

These variable speed drives shall each be contained in its own separate panel, manufactured and equipped to the satisfaction of the variable speed drive manufacturer to suit their own requirements with regard to ventilation of the variable speed drive. Small drives below 1kW can be combined into one panel but sufficient ventilation by means of extractor fans must always be allowed for.

The variable speed drive panel shall be equipped with ventilation fans and air filters. The ventilation fan shall be interlocked with the relevant motor and shall only be in operation when the motor is running. Failure of the ventilation fan shall stop the motor and a visible indication of the cause of the failure shall be provided on the panel.

The frequency converter shall make use of flux vector control without encoder or tacho generator feedback and shall incorporate direct torque control technology so that the overall effectiveness of the drive shall only be limited by the performance of the motor.

Semi-conductor switching shall be determined by the values of flux and torque and shall not have a predetermined pattern as in conventional pulse width modulation flux vector drives.

Each of these drives shall comprise amongst other the following components:

- a) 1 Only main isolator/circuit breaker that shall be interlocked with the door of the panel to prevent opening of the door with the switch closed and to prevent closing of the switch with the door open
- b) 30 Only ultra-rapid fuses rigidly connected to the load side of the above mentioned mains isolator and the rating of which shall comply with the manufacturers specifications for the drive.
- c) 1 Only direct torque control frequency converter
- d) 1 Only door mounted control panel complete with cable connections (also for small drives)
- e) 1 Set of START and STOP push buttons for manual control of small drives
- f) One dial type potentiometer for manual speed control
- g) 1 Only manual/off/auto selector switch for manual control of small drives
- h) 1 Only thermister relay for motors of 22kW or more
- i) 1 Only external EMC line filter
- j) All equipment necessary for remote emergency stop device
- All bus system interface equipment necessary for remote speed control via a monitoring and control SCADA system as well as PLC control.
- I) All equipment necessary for remote motor status and speed monitoring.
- m) LED type red "Emergency stop engaged" indicator light.

A 3 CR12 steel gland plate must be provided at least 250 mm above floor level for cable connections.

The control panel shall be the user interface for monitoring, adjusting parameters and controlling the drive operation. It shall be possible to:

- a) Enter start-up data into the drive
- b) Control the drive with start, stop and reference signals
- c) Display actual values of motor performance
- d) Display information on at least the five most recent faults

The drive shall satisfy the following technical requirements.

- a) The static speed control error shall not exceed +- 0,5% of motor nominal speed
- b) Fundamental power factor shall be at least 0,97 at nominal load.
- c) Efficiency shall be at least 98% at nominal power level

- d) The drive shall operate satisfactorily under all ambient temperature conditions between -5 degree Celsius and 40 degrees Celsius at an altitude of 1260m above sea level and humidity up to saturation point.
- e) The drive shall provide output protection for motor overload, over current, short circuit at start, earth fault, missing motor phase and over frequency.
- f) The drive shall satisfy the following minimum harmonic voltage limits. Total harmonic distortion of 6%, odd harmonic distortion of 4% and even harmonic distortion of 2%. The Contractor shall measure these harmonic distortion parameters after commissioning of the system and if the equipment fails to comply with this requirement, the Contractor will have to rectify the same to the satisfaction of the Engineer.
- g) The drive shall be equipped with an AC choke for harmonic current reduction and shall be placed of the AC side of the rectifier bridge in order to protect the rectifier semiconductors against power line transients.
- h) Torques step rise time shall typically be less than 5ms
- i) Stringent precautions must be taken in the design of the protection equipment to assure adequate lightning and surge protection.

Electronic Soft Starters

The soft starter shall be installed in the relevant motor starter panel but sufficient ventilation by means of extractor fans must always be allowed for and shall be interlocked with the relevant motor and shall only be in operation when the motor is running. A bypass contractor for motor running conditions is a requirement and shall either form part of the soft starter or shall be a separate unit.

The soft starter shall have soft start and stop programmable capabilities with torque and current control. The normal motor protection facilities such as over/under-current, start limit, long start time, electronic overload, phase loss and phase sequence and load shall be available.

At least a 2 line 16 character LCD display unit with control function keys shall form part of the soft starter and shall preferably be separate motor starter front panel mountable. The LCD unit shall display all statistical data and trip conditions and shall allow functional key changes to programmable parameters.

The full motor protection capabilities shall be maintained when motor is operating in bypass contractor mode.

RS 485, MODBUS, PROFIBUS communication shall be possible.

Induction Soft Starters

The induction type soft starter shall be installed in the relevant motor starter panel but sufficient ventilation by means of extractor fans must always be allowed for and shall be interlocked with the relevant motor and shall only be in operation when the motor is running. A bypass contractor shall be provided to bypass the soft starter.

The series impedance type starter shall incorporate reduced starting current and ensure gradual increase in the motor terminal voltage in smooth step-less manner.

The design of the induction soft starter shall allow the motor to generate adequate starting torque to overcome the load torque and friction to ensure smooth acceleration.

The soft starter shall allow five starts per hour.

Mains Surge Arrestors

The surge arrestors shall be Type 2 and voltage compatible to the relevant installation and shall be able to withstand a lightning impulse current wave form 8/20µs at a maximum discharge current of 40kA.

Each distribution board shall be equipped with mains surge arrestors.

Moulded Case Circuit Breakers

All moulded case circuit breakers shall be as specified in the schedules of equipment for distribution boards and shall comply with the requirements of SANS Specification no. 156

The required frame sizes or rupturing capacities required are specified in the schedules for each board.

Each circuit breaker shall be provided with non-adjustable time delayed trips.

These circuit breakers shall be fitted with copper terminal collector bars where more than one cable tail has to be terminated on the same terminal.

Fused Switches

All fused switches shall be of the load breaking and fault making type complying with BS-5419 where applicable and fitted with HRC cartridges fused links to BSS-88. Auxiliary contacts shall be provided where relevant for signal purposes.

Current limiting circuit breakers

The current limiting circuit breakers shall be capable of remaining in service and of carrying their normal rated current after have interrupted the maximum short circuit current of 200kA rms at least three times.

The current limiting circuit breaker shall be equal and similar to the specified **Merlin Gerin type**.

Current Transformers

All current transformers shall be of the air insulated type complying in all respects with the requirements laid down in BS 3938: 1973.

The contractor shall carefully select the ratio, burden and accuracy class to suit its specific application in accordance with the recommendations and requirements of BS 3938.

Indicating Instruments

All indicating instruments shall comply with the requirements laid down in BS 89: Part I: 1970 for instruments of a 2.5 Accuracy Class. All indicating instruments shall have 96mm square dials.

The maximum demand ammeters shall be of the 6A combined maximum demand registering and instantaneous indicating type having MISC movement and thermal demand indication with an integrating time lag of 15 minutes. The ammeter scales shall be direct reading with a full-scale deflection corresponding to 120% of the rated primary current of

the relevant current transformer. Each ammeter shall be clearly and indelibly marked to indicate the colour of the phase to which it is connected.

The ammeters for motor starters shall be 5A instantaneous indicating meters with MISC movement and direct reading scales. The meters shall be able to withstand over currents resulting under starting conditions and the full load current of the relevant motor shall be clearly marked in red on the face of the meter.

Voltmeters shall be of the direct reading moving iron suppressed zero type.

The running hour meters shall have cyclometer dials indicating up to 5 digits and two decimals (123345, 67).

Instrument selector switch

A four-position rotary type instrument selector switch shall be mounted directly below the relevant instrument in such a way that only the selector knob and indicator plate are on the panel, and the switch itself is behind the panel.

The selector knob shall consist of Bakelite and shall have the positions for the three phases and "OFF" engraved on it in 5mm high lettering.

Contactors

All contactors hall be of the totally enclosed, three pole, double air break per pole, automatic magnetic type complying with the requirements of BS 775 for "CLASS UR" contactors of the CLASS 11 MECHANICAL DUTY CLASS" and A3 make and Break.

All contactors shall be provided with arc extinguishers, and readily replacements silver or silver-alloy contacts rated for at least 2-million "on and off" switching operations at rated current.

Each contactor shall be provided with an AC closing coil suitable for continuous operating and at least 15 closing operations per hour at system voltage. The contactor may not hum or chatter in service and the contacts may not bounce on closing.

Time Switches

The time switches shall be suitable for use on a 230V, 50 cycles per second AC supply and shall be of the microprocessor type.

The time switches shall be digital timers suitable for rail or surface mounting and shall be programmable with daily and weekly programs, switching intervals of 1 minute and switching accuracy precise to the second.

The time base shall be of the quartz type with LED display for time, weekday, holiday, program, switching position and manual override and shall have a power reserve of 250 hours at full operation. The time switches shall have a switching capacity of 16A at 230 V.

Isolators

All isolators shall be of the "Load-breaking" and fault making type and shall comply with the requirements of BS 5419-1977 where applicable. Where relevant, isolators shall be provided with auxiliary contacts for signal purposes.

400 Volt air-break contactors

All contactors shall be of the totally enclosed, three pole, double air break per pole, automatic magnetic type complying with the requirements of IEC 158-1 for Class AC 3 contactors of Intermittent Duty Class 0,3.

All contactors shall be provided with arc extinguisher and readily replaceable silver or silver-alloy contacts rated for at least 2 million "on " and off switching operations at rated current.

Each contactor shall be provided with a 250 Volt, 50 Hz closing coil suitable for continuous operation and at least 15 closing operations per hour. In rural areas contactor coils must be rated to operate satisfactorily between 75% and 130% of nominal voltage.

An adequate number of auxiliary contacts shall be fitted.

The contactor may not hum or chatter in service and the contacts may not bounce on closing.

Earth Leakage Units

The earth leakage units shall consists of a combination of an earth leakage relay and a moulded case circuit breaker and shall have sensitivity as specified; it shall conform to SANS 767.

Terminals

Terminals may be of the bolted type otherwise they shall be of rail mounted clamp type.

All types of terminals and their insulation shall have a minimum comparative creep index of 500 to BS 3781.

Clamp type terminals

These terminals shall be not less than 8 mm wide.

Screws and connectors shall be electroplated to prevent corrosion. The connectors shall be such that the screws will not loosen due to vibration. Current carrying parts shall be of serrated silver plated copper or brass. Only one connection shall be allowed by connector. For more connections the number of terminals shall be increased and bridge pieces shall be used.

Surge Protection

Surge Arrestors

Surge arrestors shall be supplied and installed under its contract where applicable.

Main Supply Protection

Surge arrestors as specified shall be installed at the main incomer of each distribution board, motor control centre or any type of kiosk.

Power factor correction capacitors for 380 Volt motors

Each of these capacitors shall be of the indoor switchboard mounting 400 Volt 50 cps three-phase self contained type with a dead casing and shall fully comply with the requirements laid down in BS 1650-1971.

Each capacitor unit shall be of carefully selected rating to correct the power factor of its associated motor to 0.95 at full load and should not exceed a value which compensates for 85% of the no-load magnetizing current.

The dielectric shall consist of plastic film and low-loss paper situated between aluminium foil and impregnated with a synthetic liquid agent with scavenger additive.

The capacitor losses shall not exceed 1 Watt/kVAr.

The capacitor units shall have the following admissible overloads at an ambient temperature of 40 degrees C and an altitude 260m above sea level.

- 10% excess volts continuously;
- 50% excess current continuously; and
- 30% excess kVAr continuously

Each of these capacitor units shall be provided with discharge resistors and a fuse in each winding element that will disconnect the affected element in event of a dielectric breakdown. A time controlled contactor shall connect and disconnect the capacitors to the starter control circuit.

C3.4.2.7 MCC 07: DANGER SIGNS

Danger signs on aluminium plates shall be supplied on each door of an outdoor motor control centre or distribution board and shall be in accordance with the Occupational Health and Safety Act, Act 85 of 1993.

C3.4.2.8 MMC08: ELECTRONIC LEVEL CONTROL

- a) The micro based electronic controllers which will be mounted in the starter panels shall be easy to calibrate and reliable in service.
- b) The power units for all the pumps in a specific pump station shall be installed in a separate compartment of the starter panel and clearly labelled in accordance with the pumps controls.
- c) These level controls shall be designed to automatically select the pump sequence to ensure that all the pumps will at random be a duty pump.
- d) Where a controller controls only two pumps and one pump is always a standby pump, the standby pump shall automatically become the next duty pump after each duty cycle, unless one pump is taken down for service. When that occurs, the duty pump shall remain on duty until the normal operation is restored.
- e) When a pump selected for duty fails to respond to the start signal from the control, and then the next duty pump shall automatically start-up after five minutes.
- f) The level controller must also stop all the pumps, whether on manual or automatic selection, when the pump has reached a predetermined low level.
- g) The transducers shall be designed to operate in air, been capsulated, of rugged construction and impervious to submergence. The transducer shall not form part of the MCC scope of supply.
- h) The coaxial cable between the transducer and power unit shall be of sufficient length to avoid any joints in this cable, as no joints will be permissible.

C3.4.2.9 MCC 09: EMERGENCY STOP PUSH BUTTONS AND WEATHERPROOF ISOLATORS

Each of these units shall consist of a totally enclosed outdoor type heavy duty "push and turn lock" stop push button station with a cable gland entry at the bottom to accommodate a 4 core 2.5mm LT PVC SWA PVC cable.

Where installed at motor positions the emergency stop push buttons shall not form part of the MCC scope of supply.

C3.4.2.10 MCC 10: EARTHING

The contractor shall do all the bonding and earthing in accordance with the latest addition of the "Code of Practise for the Wiring of Premises" SABS 10142.

The substation and HT switch room earthing shall consist of a 70mm² bare copper earth wire installed in the same trench as the HT supply cables. Earth resistivity measurements of less than 1 ohm will be acceptable.

C3.4.2.11 MCC 11: INFORMATION TO BE SUBMITTED WITH THE TENDERS IN RESPECT OF THE 380 VOLT DISTRIBUTION BOARDS AND MOTOR CONTROL BOARDS

The following information shall be submitted with each Tender in respect of all boards offered:

- a) Full technical details and descriptive literature regarding all equipment and instruments offered.
- b) Three paper prints of an outline drawing of each board indicating the main overall dimensions and general lay-out of the boards; and
- c) Three paper prints of an outline drawing of the front end processor cabinet indicating the main overall dimensions, general layout and type of material employed on the face of the panel.

C3.4.2.12 MCC 12: INFORMATION TO BE SUBMITTED BY THE SUCCESSFUL TENDERER

The successful Tenderer shall submit three prints of the under mentioned drawings to the Engineer for approval, before manufacturing.

- Outline and general layout drawings showing dimension and construction details.
- A wiring diagram
- A schematic single line diagram

After completion of the work, the contractor shall submit three final copies of each of the above-mentioned drawings showing the final layout and wiring diagram of the boards.

C3.4.2.13 MCC 13: INSPECTIONS AND TESTS

All equipment will be inspected by the Engineer and tested in his presence both in the factory during manufacturing and on site during installation. The Engineer will do all inspections accompanied by the Contractor and the Contractor will do all tests with the Engineer as witness.

The Engineer will require seven (7) days notification to avail himself for any test or inspection and the Contractor must arrange for the maximum number of inspections and tests to be done on the same day. The Contractor must provide all testing facilities and instruments, all equipment required for a test or inspection.

The instruments must have a valid test certificates issued by an acceptable testing authority and the results of the test done must be recorded on a test certificate, of which the Engineer must receive two copies. The Engineer reserves the right to call for a collaboration test on any instruments used during the test.

The cost of all tests must be included in the tender price.

C3.4.2.14 MCC 14: TESTING OF DISTRIBUTION / MOTOR CONTROL BOARDS AT THE MANUFACTURER'S WORKS

- a) Each distribution / motor control board shall be carried out to ensure compliance with the specification and approved drawings and wiring diagrams and to ascertain that all connections are properly made.
- b) A high voltage test on all primary connections to check the insulation between phases mutually and between each phase and earth.
- c) The polarities and ratios of all potential and current transformers shall be checked
- d) Primary and secondary injection tests shall be carried out on all switching, protection, metering interlocking and indication circuits.

The manufacturer shall submit three copies of test certificates giving details of conditions and results of tests carried out to the Engineer.

C3.4.2.15 MCC 15: CONCRETE PLINTH FOR OUTDOOR STARTER PANELS AND PEDESTALS

The plinth shall be cast 150mm below as well as 150mm above the ground level. It shall have neatly bevelled edges and shall be 75mm wider than the panels all round.

An opening of sufficient width to allow for cable entry shall be provided under the starter panels.

The grade 304 stainless steel foundation bolts for mounting of the panels shall be cast or grouted into the plinth. The plinth shall be in Class 20/19 concrete and shall be suitably reinforced if necessary.

It is recommended that the casting of these foundations must be carried out by the Civil Contractor at the cost of the Contractor under this Contract in accordance with his instructions and under his supervision.

C3.4.2.16 MCC 16: INSTALLATION OF DISTRIBUTION BOARDS AND MOTOR CONTROL BOARDS

Each of the relevant distribution boards and motor control boards shall be built on walls or securely bolted down on the floor or plinth, as may be required, by means of the requisite number of foundation bolts grouted into the floor in the positions indicated on the drawings.

These positions shall be confirmed with the Engineer on site, prior to installation.

C3.4.2.17 MCC 17: TESTING AND COMMISSIONING OF DISTRIBUTION / MOTOR CONTROL BOARDS AFTER INSTALLATION ON SITE

After installation on site but prior to commissioning the following inspections and tests shall be performed on each distribution / motor control board.

- a) Check all components to ensure that they are free from dust and protective packing material;
- b) Check the operation of all components liable to damage in transit such as meter and protection measured;
- c) The insulation of all primary circuits between phases mutually and between each phase and earth shall be measured;
- d) All fused links shall be checked for electrical continuity; and
- e) All control supplies shall be checked.

f) All adjustable protection devices shall then be set and the boards commissioned all in consultation with and to the instruction of the Engineer.

C3.4.2.18 MCC 18: OPERATING AND MAINTENANCE INSTRUCTIONS

Before completion of the testing of the plant, the Contractor shall provide the Employer with adequate and complete working, operating and maintenance instructions in triplicate, with the necessary drawings and diagrams clarifying the instructions.

Instructions are to be made up in book form and particular reference is to be made to:

- a) Maintenance of equipment;
- b) Precautions to be taken in running the plant;
- All instruments and components must be fully described in data sheets supplied by the relevant suppliers;
- d) Wiring diagrams of the complete electrical installation.

The manual must be specific for the plant supplied and all extraneous material not connected with the relevant plant shall be deleted, leaving the manual as a comprehensive coherent document, bound in a professional way such that this may be used frequently without falling apart. Standard pamphlets may be supplied as addendums, bound separately in a good quality file to serve as reference but will not be allowed as part of the main manual.

C3.4.2.19 MCC 19: MEASUREMENT AND PAYMENT

Measurement and payment will be done in accordance with the methods stated below and reference should be made to the Bill of Quantities included elsewhere in the document.:

Design, Drawings and General

Pay Item

- Provide MCC design drawings and wiring diagrams as specified.
- Provide operating and maintenance manuals and "as built" drawings as specified.

Supply and Delivery to Site

Pay Item

Supply and delivery to site of complete MCC.

Installation

Pay Item

Site installation of MCC

Commissioning

Pay Item

Commissioning of MCC

C3.4.3 ELECTRICAL CABLES

Cables and Accessories

General

The electrical contractor shall supply and install all cables and bare copper earth wires in the positions as indicated on the Drawings.

All cables and accessories shall comply with the relevant SABS and other applicable Specifications and shall be suitable for continued use in the conditions as specified previously.

Cables

The Electrical Contractor shall supply and install all cables and bare copper earth wires in the positions as indicated on the Drawings.

The supply cables shall be connected to circuit breakers in the existing LT Room or Distribution Boards, as described elsewhere and/or indicated on the Drawings.

Cable Markers

Suitable and approved cable route markers shall be installed along all cable routes.

These cable markers shall be installed at intervals of at least 100m along straight runs, at each change of direction in the cable route and immediately above each cable joint

C3.4.4 ELECTRICAL DISTRIBUTION SYSTEM

Scope

Equipment shall be provided as specified and indicated on the drawings on the site of works.

Pressure Transmitters

A pressure transmitter with display unit 10mbar-40bar shall be installed in both the common delivery and suction pipeline of the pump sets.

Pressure transmitters shall be equal and similar to Endress and Hauser PMC41 as specified.

No-Flow Sensors

A no-flow sensor shall be installed in each of the pump set delivery pipelines all in accordance with the manufacturer's requirements. The weld stub supplied with the no-flow sensor shall be welded onto the delivery pipeline by the mechanical contractor. Tenderer shall make sufficient provision for the costs of welding the stub in the position.

No-flow sensors shall be equal and similar to Endress and Hauser Magphant DTI200 all as specified

Electronic Level Control

Electronic level monitoring equipment shall be provided at the following locations:

An electronic intelligent level transducer shall be supplied and installed on a grade 304 stainless steel bracket and inside a ventilated grade 304 stainless steel enclosure on top of the reservoirs (as specified below) at:

Clear Water Reservoir, on a 304 stainless steel bracket on the reservoir.

A ball type level sensor shall be installed complete with local surge protection and earthing system.

RETROFITTING OF 6 sewer pump stations, INSTALLATION OF INLINE GRINDERS AND REPAIRS TO WASTE WATER TREATMENT PLANT IN HOOPSTAD AND TIKWANA

SCOPE OF WORK

Emergency Stop Push Buttons and Weatherproof Isolators

Grade 304 stainless steel pedestal mounted emergency stop station shall be provided at all motor installation as specified.

Lightning Protection

The lightning protection at the pump stations forms part of this contract.

C3.4.5	TELEMETRY SYSTEMS
ITEM	DESCRIPTION
TMS 01	SCOPE
TMS 02	CONDITIONS TO SERVICE
TMS 03	STANDARDS AND TESTS
TMS 04	OUTSTATION CABINETS
TMS 05	RADIO
TMS 06	GSM AND GPRS MODULES
TMS 07	SOLAR PANEL AND BATTERIES
TMS 08	SURGE PROTECTION
TMS 09	EARTHING
TMS 10	SOLENOID VALVES
TMS 11	NUMBERING OF CONDUCTOR ENDS
TMS 12	CONNECTION OF CONDUCTOR ENDS
TMS 13	MONITORING SYSTEM
TMS 14	TRANSDUCERS AND INTERFACES
TMS 15	CIRCUIT BOARDS AND COMPONENTS
TMS 16	FAULT FINDING AND TEST FACILITIES
TMS 17	MODULAR DESIGN
TMS 18	ANTENNAE
TMS 19	OUTSTANDING HARDWARE
TMS 20	MEASUREMENT AND PAYMENT

TMS TELEMETRY SYSTEM

C3.4.5.1 TMS1: SCOPE

This specification includes the manufacturing, delivery, transport, handling, protection, storage, installation, successful commissioning and upholding during the Defects Liability Period.

The applicable scope of the works covered by this section shall be defined in the Variations and Additions to the Standard and Particular Specifications Section C3.4.2 and relevant Tender drawings.

C3.4.5.2 TMS 2: CONDITIONS TO SERVICE

The electrical distribution system will be installed in an industrial plant environment.

C3.4.5.3 TMS 3: STANDARDS AND TESTS

All materials and equipment to be supplied and installed under this contract shall be new and of the best quality available.

All materials and equipment shall comply with the requirements laid down in the latest editions of the BS, SABS and IEC specifications and their amendments (if any) as well as those laid down in this specification. Where items bearing the SABS mark are available for any of those materials and equipment specified, only materials bearing the said mark, will be acceptable.

C3.4.5.4 TMS 4: OUTSTATION CABINETS

All equipment shall be housed in epoxy coated 2.0 mm thick 3 CR 12 steel dust and vermin proof cabinets. The cabinets shall have front access only. Cable entrance shall be possible from the bottom. The doors must be fitted with tamper proof locking catches with padlock facilities and shall be of the 3point type equal and similar to BARKER AND NELSON SERIES 25. Concealed chromed steel hinges shall be used on the front door.

All doors shall be fitted with intrusion detectors and all door handles shall be chromed.

Sufficient room shall be provided for rail mounted terminals strips, equal and similar to Kippon Type SAKR, which must be installed for all field equipment connections.

If the extremely high summer temperatures will present a problem to the electronic equipment, then the cubicle shall consist of an outer and inner shell with at least 10mm insulation or polystyrene between inner and outer shell all round to keep the temperature inside the compartment at least 5°C below the surrounding temperature. The doors of this compartment must also be of a similar double wall construction.

All ventilation openings shall be covered with copper gauze wire properly secured to inside surface of the cabinet, glued on gauze will not be acceptable. The cabinet shall be suitably sized to accommodate without cramping, all the equipment specified and shall be equipped with an unpainted 3 CR 12 steel cable end support at the bottom of the cabinet.

Outdoor cabinets shall be of the freestanding plinth mounted cubicle type with IP 55 insect proofed enclosure and shall be bolted down to a concrete plinth. Solar panel powered outdoor system cabinets shall consist of two separate compartments one for the telemetry system and the other to house the batteries. Reservoir roof mounted outdoor cubicles shall be frame mounted with frame secured to reservoir roof. Solar panels shall always be frame mounted and secured at the required angles for optimum solar energy utilization.

The plinth shall be cast 150mm below as well as 150mm above the ground level. It shall have neatly bevelled edges and shall be 75mm wider than the cubicle all around. The plinth shall be a class 20/19 concrete and shall be suitably reinforced if necessary.

Sufficient provision for breathing and heat dissipation must be made in this compartment. A danger sign manufactured from durable non-plastic corrosion resistant material must be installed on the access door of outdoor cubicles with a 230V supply of electricity.

C3.4.5.5 TMS 5: RADIO

The radio transceivers shall be of robust construction with digital signal processing communication technology for increased data throughput. No extra software or programming shall be needed to implement communications using standard asynchronous protocols. On an upgrade on an existing telemetry system similar radio communications system shall be incorporated.

C3.4.5.6 TMS 6: GSM AND GPRS MODULES

For low I/O count and lower power consumption GSM and GPRS modules shall be used for communication purposes. The Module shall be used for date communication via the available GSM cellular service provider networks.

The communication option available on the module shall be dial-up, SMS, GPRS and HSCSD. The module shall be provided with RS232 ports with MODBUS communication facilities. The cellular communication hardware module and sim card holder shall be on board mounted.

C3.4.5.7 TMS 7: SOLAR PANEL AND BATTERIES

When no electricity supply is available solar panels shall be used to charge batteries via a voltage regulator. A fully operational back up time of 96 hours (4 days) is required unless otherwise specified. At least two 85 Watt solar panels shall be installed at a radio communication solar panel installation or two 65watt solar power panels at GSM and GPRS installations.

The regulator shall be specifically designed for the telemetry use, where radio current draw varies from 0.1 to 5A for short durations of transmission. Allowance shall be made for at least 4 station interrogations per hour.

The regulator shall provide

- Over voltage cut-out of load if battery voltage is greater than 16 V.
- Cyclic charge to keep battery voltage falls below 10V for more than 30 seconds. Low voltage cut-out of load if battery voltage falls below 10V for more than 60 seconds. Load is reinstated when battery is recharged to more than 12V DC.

Batteries less than 6.5Ah capacity shall not be used due to the high peak discharge current during radio transmission. Nickel Cadmium batteries shall not be used.

Sealed lead-acid batteries shall be used for capacities up to 65Ampere Hour, and vented lead-acid (Plant) storage cells designed for standby applications shall be used for larger capacities. Liquid based storage cells shall be housed in a separate vented lockable enclosure.

C3.4.5.8 TMS 8: SURGE PROTECTION

In addition to the surge protection already specified the following surge protection units shall be installed.

Main supply protection

The surge arrestors shall be Type 2 and voltage compatible to the relevant installation and shall be able to withstand a lightning impulse current wave form 8/20µs at a maximum discharge current of 40kA.

Each telemetry outstation shall be equipped with mains surge arrestors.

Solar power protection

The surge arrestors shall be a 24 V DC quick responding surge arrestor for use according to the lighting protection zones concept at boundaries 1-2 and higher and shall be able to withstand a lighting impulse current wave form 8/20µs at a normal discharge current of 1KA.

Antenna cables

The surge arrestors shall be suitable for multi frequency applications and shall have excellent RF endurance performance for use according to the lightning protection zones concept at boundaries 0A-1 and higher and shall be able to withstand a lightning impulse current wave form 8/20µs at a normal discharge current of 20kA.

C3.4.5.9 TMS 9: EARTHING

Outstations

Outstations in building and on manholes and valve chambers shall be connected to a 70 mm² bare copper ring earth installed 500mm below ground level around the circumference of the building or structure.

The ring earth shall be connected to the outstation by means of a 70mm² bare copper earths. At the four corners of the ring earth 2M long spurs consisting 0f 70mm² bare copper conductors shall be Cad welded to the ring earth and the bare copper conductor ends of the spurs shall be connected to 1.5m long earth spike driven into the ground at each end.

All earth connections at the outstations shall be connected to this ring earth.

C3.4.5.10 TMS 10: SOLENOID VALVES

Solenoid valves complete with hydraulic pipe couplings shall be provided where indicated for telemetry control of hydraulic controlled valves at reservoir sites. These units shall operate from a 24V DC supply and shall be of the low energy consumption type. The open/close status of the hydraulic valve shall be monitored where possible by means of a limit switch mounted on the hydraulic valve casing. A weatherproof cable termination box must be supplied and installed next to the control valve and provision must be made for connection cables between the termination box, solenoid and limit switch. The control valve will be controlled by means of the level sensor at relevant reservoir and must be a fail safe operation (valve must be close in the event of a power failure)

C3.4.5.11 TMS 11: NUMBERING OF CONDUCTOR ENDS

Every conductor end whatsoever, with exception of AC power cables at any terminal shall be numbered. The alphanumeric numbering shall be in accordance with – BS 158 – 1961.

These numbers shall correspond with those on the circuit diagram and shall consist of the slip on type numbering system (clipped on numbering system will not be accepted). It shall not be possible to remove the number holder damaging it or cutting off the lug.

C3.4.5.12 TMS 12: CONNECTION OF CONDUCTOR ENDS

All conductors whatsoever shall be connected at terminals by means of lugs and/or ferrules suitable for the specific conductor.

C3.4.5.13 TMS 13: MONITORING SYSTEM

System Organisations

The system will consist of the following organisation which may in future increase in size. The system shall be suitable to be modified to a decentralised type of control with intelligent outstations.

Monitoring

The system shall provide plant information to the following display devices:

· Mimic Display units

Analog readings shall be in close proximity to related devices on the display screens showing flow rates and shall be continuously updated after outstation scans.

The following indications are catered for:

- Indications of status of all motors and pumps;
- Indication of which relay or any other device caused changes in the system.
- Alarms are indicated visually and audible. When the alarm is accepted the audible indication is cancelled:
- · Indication of internal faults in the supervisory system;
- When selected, indication of analog signals at specific points in the system as specified in the relevant clause; and;
- When selected, indication of time, the control equipment and outstations shall give the indications

Data and Event Recording

The following information shall be recorded by the system:

- Automatic recording of events when a change of status takes place in the system and at the same time, recording time, date, outstation, item, alarm and identification.
- Automatic log all analogue values at present intervals from a particular outstation;
- Automatically log any number of selected analogs at preset intervals.
- Record keeping of the real time operation of all motors; and
- Keep records of all controls transmitted.
- The data logging will be such that it can also be done by manual selection at any time.

Measuring accuracies

Measuring accuracies of 2.5% full-scale are required on all analog signals.

C3.4.5.14 TMS 14: TRANSDUCERS AND INTERFACES

Transducers shall be supplied and installed by the contractor and any other associated devices where it may be necessary in order that supervisory analog quantities can be measured by the telemetry. The monitoring and control system contractor will be responsible for all interfaces between his equipment and that of other contractors.

C3.4.5.15 TMS 15: CIRCUIT BOARDS AND COMPONENTS

Printed circuit boards shall be of epoxy glass fibre or seminar high quality fungus resistant, non-hygroscopic material.

All the through connecting holes shall be plated through.

Contacts on printed circuit boards and connector pins shall be gold plated.

C3.4.5.16 TMS 16: FAULT FINDING AND TEST FACILITIES

The equipment shall be designed in such a manner that staff of the employer with the minimum training in electronics, can do the maintenance on the equipment.

The contractor shall specify all the standard and special test equipment required for normal maintenance and testing purpose.

A rail mounted terminal strip equal or similar to Klippon Type SAKR shall be mounted in the supervisory panels for the connection between the plant equipment signals and electronic equipment.

C3.4.5.17 TMS 17: MODULAR DESIGN

The system shall be of modular design in order to facilitate expansion to the system by simple plug-in of additional modules and minimum wiring changes. All modules shall be DIN rail mounted and shall be interconnected by means of bus connectors.

C3.4.5.18 TMS 18: ANTENNAE

A list must be provided showing which mast is allowed for at each station. These shall be either:

- (a) Wall mounted: A 5mm tubular mast shall be fixed to the wall with a heavy-duty gauge galvanised offset bracket for 500mm roof overhang. The mast shall be either aluminium 50 mm diameters, 5mm thick, or steel galvanised 50mm diameter, 2mm thick.
- (b) Self-supporting 9m: A 9m flag pole type mast suitable for the size of antenna used, to withstand 140 km/h with loading shall be provided.
- (c) Self-supporting 12 to 18m: Mast above 12m should be lattice type construction. The mast plinth shall be supplied by the contractor. The contractor shall provide the concrete base with plinth and wire way. A sketch of the civil works must be provided by the contractor.

C3.4.5.19 TMS 19: OUTSTATIONS HARDWARE

Operational Requirements

- (a) General: The outstation shall comprise of a central processor unit with interface modules, a power supply, standby battery and plant input and output modules and commissioning system. All equipment shall be housed in a steel cabinet as specified. Apart from any other modules being necessary to operate and control the system satisfactory, the following modules shall be made available on the outstations.
- (b) Power Supply: The stabilized power supply and battery charger unit shall be capable of re-charging a drained 15Ah sealed lead acid battery and shall operate from 230 V-AC. Battery backup for at least 24 hours of normal operation shall be provided for.
- (c) The CPU module shall have a high speed RAM for executable program sections with a RAM size that will match the requirements of the application. Sufficient memory shall be equipped with a CPU watchdog timer circuit that will automatically restart the system in case of severe electrical disturbance. The CPU shall be auto-configuring and shall determine automatically which I/O modules are connected, do data addressing and mode of operation to run. Use of programmer at outstation shall not be necessary.
- (d) Relay Interface Cards: Relay interface cards shall be available to connect control outputs to outside plant. LED monitors shall be fitted to this card to aid with faultfinding.
- (e) Input/output modules: The digital I/O modules shall accept inputs from plant controls and auxiliary multiple operations and provide control outputs to plant operations. These modules shall also be capable to accept floating alarms of duration of 20ms as well as steady alarms from normally closed controls. All inputs and outputs shall be 2.5 kV isolated from logic components. Inputs and Outputs shall be protected against over voltage and over current. These I/O's shall be isolated from field equipment by means of interface relays in the outstation.
- (f) Anolog modules: These modules shall accept analog inputs from plant transducers and provide control analog outputs to plant operations and shall be capable of converting 0-5 V DC, 4-20 MA or 0-5 V AC signals by using external converters. All analog inputs and outputs shall be galvanic isolated.
- (g) RS 232 Bus connectors: These modules shall accept data from an external source. The baud rate shall be adjustable from 300, 1200, 2400, 9600 or 19200-baud handshake protocol shall include XON/XOFF, CTS/RTS and direct.

Outstation General: This outstation shall be capable of scanning all inputs and storing data in memory for collection by the mother station. It must also be possible to perform sequence control and interlocking of plant equipment.

- (h) Outstation Antenna: 10 dB Yagi antennas shall be installed at all outstations.
- (i) Time Jagging: Events shall be time stamped at the outstations. Only a real time clock at the outstation will be acceptable which shall is hardware based with a crystal. Accuracy of time tagged events should be 20ms between events and 100ms between events at different outstations.
- (j) Digipeating: The telemetry system shall have the facility to repeat commands destined from or to a remote station, via another station (Digipeating, or Store-and-forward). The digipeat "map" shall be stored in E2PROM (non-volatile memory) at relevant stations, and be able to be programmed with local programmer (e.g. LAP-TOP) or remotely via the communications medium. The dipigeat map shall allow for input/output data to be transferred from any remote site to any other remote site and/or Central Station.
- (k) Programmable Logic Controllers: Where logic control is required at an outstation for pump control programmable logic controllers shall be used. These PLCs shall be of reputable brand name, to allow after sales programming support by specialist vendors. The telemetry interface to PLC will be serial communications.

C3.4.5.20 TMS20: MEASUREMENT AND PAYMENT

Measurement and payment will be done in accordance with the methods stated below and reference must be made to the drawings and Bills of Quantities elsewhere in this document:

	Pay Item	<u>Unit</u>
	Supply and Delivery to Site	
a)	Supply and delivery to site of flow meters	Sum
b)	Supply and delivery to site of level transducers	Each
c)	Supply and Delivery to Site	
d)	Installation of flow meters	Sum
e)	Installation of level transducers	Each
f)	Commissioning	
g)	Commissioning of flow meters	Sum
h)	Commissioning of flow meters	Sum
i)	Commissioning the telemetry link to the Control Room	Sum

C3.4.6 INDEX	PROGRAMMABLE LOGIC CONTROLLERS
ITEM	DESCRIPTION
PLC 1	SCOPE
PLC 2	CONDITIONS TO SERVICE
PLC 3	STANDARDS AND TESTS
PLC 4	PROGRAMMABLE LOGIC CONTROLLER HARDWARE
PLC 5	PLC GENERAL
PLC 6	COMMUNICATION
PLC 7	PLC SOFTWARE DEVELOPMENT

PROGRAMMABLE LOGIC CONTROLLERS

C3.4.6.1 PLC 1: SCOPE

This specification includes the manufacturing, delivery, transport, handling protection, storage, installation, successful commissioning and upholding during the Defects Liability Period.

C3.4.6.2 PLC 2: CONDITIONS TO SERVICE

The programmable logic controllers will be installed inside motor control centres and programmable logic controller cabinets on the package plant and high lift pump.

PLC	Programmable logic controller
SFC	Sequential function chart
SRS	Software requirements specification
CF	Control function
CFS	Control function section
CSCI	Computer Software configuration item
CSC	Computer Software Component
CSU	Computer Software Unit

C3.4.6.3 PLC 3: STANDARDS AND TESTS

The programmable logic controllers shall conform to and be in accordance with the latest applicable South African Bureau of Standards Codes and Standards as well as International Electrotechnical Commissioner Standards.

The following Standard Specifications and drawings shall apply:

SANS 10142 - Code of Practice for the wiring of premises

SANS 156 Moulded Case Circuit Breakers

SANS 1574 - Electric cables and flexible cords

NRS 002 - Graphical symbols for electrical power, telecommunication and electronic diagrams

SANS 1433-1- Terminal blocks having screws and screwless terminals

SANS 1433-2 Flat push on connectors

IEC 68 Shock and vibration resistance

IEC 1000 Electrostatic discharge and electromagnetic interference

IEC 1131 Standard Software

C3.4.6.4 PLC 4: PROGRAMMABLE LOGIC CONTROLLER HARDWARE

PLC 4.1 Hardware configuration

Normally the hardware configuration will be a single CPU with I/O modules as required mounted on a 19 inch rack backplane.

Remote I/O drops are permitted provided the remote I/O s are geographically close to the Programmable logical controllers (PLC)

PLC 4.2 General

The unit shall comprise of a programmable logical controller with interface modules, a power supply, plant input and output modules all suitable for 19 inch rack mounting. All equipment shall be housed in a steel cabined that will form part of that specific motor control centre unless the application requires a separate cabinet.

Apart from any other modules being necessary to operate and control the system satisfactory, the following modules shall be made available on the units.

PLC 4.3 Power Supply

The standalone single slot rack mounted power supplies shall operate from 230 V-AC and shall have sufficient capacity for the application. The power supply shall provide all regulated DC back plane power necessary for the installed modules. The power supply shall have over and under voltage protection for added security.

PLC 4.4 Processor

The CPU module shall be a back plane slot mounted controller containing on board executive memory, application memory and communication ports. It shall be possible to perform field upgrades through a field bus communication port. The front panel of the CPU shall be equipped with status and fault LED's to facilitate fault diagnostic procedures. The CPU shall have a multipoint interface for an external programming device as well as a field bus port.

For math-intensive application math-coprocessor hardware shall be included in the CPU.

Sufficient programming memory shall be made available to ensure at least 50% memory available after completion of application building for future expansion. The controller shall support at least of 32 I/O drops.

Ladder logic instruction performance shall be between 0,3 and 1,4ms per 1000. Clock speed shall be at least 20 MHz The CPU shall support at least the following IEC 1131-3 programming languages.

- a) Sequential Function Chart
- b) Function Block Diagram
- c) Ladder Diagram
- d) Structure Text
- e) Instruction List

The CPU shall be equipped with a lithium battery for battery backed RAM to hold application programs.

PLC 4.5

The communications processor shall provide communication links with other programmable controllers through process Field Bus or Ethernet systems.

The CPU shall have a real time clock for the generation of time related information.

PLC 4.6 Interface Modules

Interface modules shall connect I/O modules in multi-tier configurations.

LED monitors shall be fitted to this card to aid with fault finding.

PLC 4.7 Digital input/output modules

The digital I/O modules shall accept inputs from plant controls and auxiliary multiple operation and provide control outputs to plant operations. The modules shall be complete with I/O connectors. 24V DC input and output modules will be preferred.

These modules shall also be capable to accept floating alarms of duration of 20ms as well as steady alarms from normally closed controls. A typical response time of 11ms for change of state shall be acceptable.

All inputs and outputs shall be 2.5kV isolated from the logic components.

PLC 4.8 Analog modules

These modules shall accept analog inputs from plant transducers and provide control analog outputs to plant operations and shall be capable of converting 0-5V, 0-10VDC or 4-20 mA signals as may be required. All analog inputs and outputs shall be galvanic isolated.

The input module shall have a typical accuracy of at least \pm 0.05% of full scale while the accuracy of the output modules shall not exceed \pm 0.2% of full scale.

The input modules shall have broken wire fault detection capabilities.

PLC 4.9 RTD modules

These modules shall accept inputs from plant transducers. All inputs shall be galvanic isolated.

The temperature range shall be indicated in degrees Celsius and the modules shall accept RTD units of the American PT, IEC Platinum and Nickel N series.

The modules shall have out of range and broken wire fault detection capabilities.

Typical update time of 640ms for 2 or 4 wire systems and 1.2s for 3 wire systems will be acceptable.

PLC 4.10 Ethernet network interface

These modules shall accept data from an external source. The network speed shall be 10/100Mhz and higher. These modules shall be backplane mounted and shall receive and transmit field bus commands. Fibre optic connection through SP connectors shall be possible.

PLC 4.11 Optical Link Modules

The backplane mounted optical link modules for fibre optic cables shall allow networks to be configured in linear, ring and star structures and shall be supplied complete with the necessary cable connectors, interface cards and bus connectors.

PLC 4.12 Switches

The 10/100Mb Switch modules shall have a fibre optic Ethernet port and sufficient UTP connector ports with at least two spare ports for future use.

PLC 4.13 Fibre optic splicing

Fibre optic splicing shall be performed by a specialist contractor. The fibre optic connection between the splicing box and the fibre optic module shall be patch leads and not splicing leads.

PLC 4.14 Fibre optic to UTP converters

Where specified fibre optic to UTP converters shall be installed. These units shall be secured in an acceptable manner.

PLC 4.15 Distributed I/O

The distributed I/O module shall be a standalone unit with an integral 230V AC power supply and equipped with digital and analog I/O as may be required. The module shall have an Ethernet port.

PLC 4.16 Uninterruptible Power Supply (UPS)

ON-LINE transformer based (isolation transformer shall form part of UPS system) UPS system shall provide power to all PLC equipment with standby capacity of at least 2 hours.

RS232 interface shall be provided to relay UPS status (battery voltage, mains voltage, power failure alarm, battery low) to the SCADA system.

Bypass switch shall be provided to enable operating of PLC station in case of UPS failure.

Adequate lightning and surge protection units (on mains side) shall be installed.

C3.4.6.5 PLC 5:PLC GENERAL

The PLC shall be capable of scanning all inputs and storing data in memory for collection by the SCADA system.

It must also be possible to perform sequence control and interlocking of plant equipment.

Outstations shall be modular PLC packaging system and shall consist of all necessary modules as may be required for the specific application. These PLCs shall be connected to the SCADA system via a Field bus of Ethernet system.

PLC 5.1 Input and output cards

The allocation of input and outputs shall be in logical manner. The allocation shall be on the basis of process units or streams or drives such that the failure of a card will cause minimum loss of plant availability.

Specifically for any motor starter the inputs shall be grouped on one card. The number of inputs allocated to a motor starter is such that they can be grouped on a 16 way input card so that at most two starters are allocated to one card. The allocation inputs and outputs of motor starters shall be such that a duty and standby motor starters are not together on the same I/O cards.

Rack Capacity

The final rack and input and output card installation shall have at least 10 percent spare slot capacity over and above any spare inputs or outputs on the installed cards.

PLC 5.2 Programmable logic software

All PLC software shall be structured in a logical manner representing the key process units and control regimes required for plant control/

PLC 5.3 Documentation

All PLC software shall be fully documented and the documentation shall consist of the following as a minimum:

- a) Functional specification of the plant to be controlled
- b) Process control logic diagrams
- c) Sample report forms
- d) Sample alarm report details (list and format reports)
- e) Fully annotated listing of the full software package
- f) Full input/output listings
- g) Full allocated register listing with functional description
- h) Program software in electronic format
- i) All documentation is subject to the approval of the Electrical Engineer.

PLC 5.4 Execution of control regimes

Control regimes shall generally be executed at PLC level unless the algorithms are too complex to execute at PLC level. Approval to execute control functions at supervisory level shall be obtained from the Engineer before commencement of the software.

C3.4.6.6 PLC 6 : COMMUNICATION

PLC 6.1 General

PLC to PLC communication shall be field bus or Ethernet and if the communication link is required to go beyond a single room optical fibre modems shall be used. PLC CPU's located within a single building room shall communicate over conventional cabled networks using a suitable cable for the Communication link.

In some cases it may be possible to communicate directly with devices (such as variable speed controller, etc.) in which case master slave communication is permitted, peer to peer communication. If such facility for communication is available it is to be used in preference to hardwired 4-20mA and contact closured signals for process interfaces.

PLC 6.2 Interlocking control using communication networks

Where necessary to execute process control on a PLC and/or supervisory network the following shall apply:

Safety interlocks where human or equipment safety is a criterion may be communicated over a PLC to PLC network. The interlocks may not be communicated over a higher level supervisory network. This requirement does not negate the requirement to have hardwired safety stop controls on all drives and switchgear.

Non-essential interlocks, the failure of which will not cause harm to persons or equipment may be communicated with prior permission over a supervisory communication network. Preference, however, is to keep all interlocking at the field bus or Ethernet level unless rate of communication is compromised due to excessive traffic levels.

Data for the purpose of reporting and management information shall be channelled through the supervisory level network. Such data shall preferably not be transmitted on the field bus or Ethernet network level unless a supervisory level channel is not available.

PLC 6.3 Enclosures

PLC equipment shall be mounted in an IP54 enclosure with a suitable viewing window in front of the modules. The enclosure will form part of the motor control centre and in the event of no motor control centre available a separate enclosure will be acceptable.

PLC 6.4 Hardware Configuration Unit Basis

Hardware shall be configured on a unit basis which is each pump set shall be configured in a module with equipment dedicated to that pump set only on a unit by unit basis so that the failure of any one item will affect only a single pump set at any instant.

It will however be necessary to serve pump set PLC hardware with common services such as uninterruptible power supplies.

For this purpose the pump set shall be provided with the following:

- a) A control console located on the operating floor in a position where the operator is able to overlook the pump sets if specified.
- b) A Human Machine Interface terminal to display process and fault information if specified. The normal start and stop functions shall be executed by way of soft keys on the HMI terminals.
- c) An Emergency Stop push button for each pump set in the pump station mounted on the control console if so specified. The emergency stop push button shall have a red mushroom operator and shall be of the latching, twist to release type.
- d) Stop circuits shall be hardwired in the main circuit breaker control circuit as the primary trip route and shall also be wired into the PLC control circuit.

 Emergency trip push button shall activate both the trip coil and no volt release coil of the main circuit breaker or contractor where used.

PLC 6.5 HMI Terminal Process Information

The monitoring and control functions of each pump set shall be accessible on the human-machine interface.

The device shall be programmed that the control soft keys of each pump set are the same. To ensure that this requirement is maintained, a standard software package shall be applied to each pump set. Variable speed pump sets shall have the facility for speed adjustment added.

The HMI shall have a 10.4 inch colour screen (256 colours) and definition of 640 x 480 pixels. Sufficient application memory shall be available to ensure at least 50% spare memory after application building. The HMI shall be equipped with an Ethernet port for PLC communication.

The HMI shall be equipped with at least 8 dynamic keys with LED indicators 12 static keys with LED indicators and re-usable labels 12 service keys and 15 Alpha numeric keys.

The following basic process information shall be displayed for each pump set or pump stage as applicable.

- a) Operating Parameters
- Suction pressure
- Delivery pressure
- Delivery flow rate
- Running hours- accumulated total and since last start
- Accumulated kWh
- b) Valve Parameters
- Suction valves position indication
- Delivery valve position indication
- c) Pump Parameters
- DE and NDE bearing temperatures
- Thrust bearing temperature
- Vibration level
- Volute temperature
- d) Motor Parameters
- DE and NDE bearing temperatures
- Phase stator temperatures
- Motor Power
- Motor current
- Motor speed (variable speed drives only)
- Power factor (variable speed drives)

- Vibration level
- e) Auxiliary Devices
- Device run and stop indication
- Device fault indication
- Flood alarm
- f) The following basic information screen hall be provided
- Process indication of the pump set
- An Alarm Screen
- Historic alarm screens (if required)
- Protection settings with adjustment capabilities
- Status indication of interlocks to facilitate evaluation of the start-up sequence
- Status indication of the interlocks that are in Bypass condition
- Main overview
- Main 11kV electrical power supply system with status indication of all circuit breakers and associated equipment.

PLC 6.6 SCADA Interface

To facilitate an interface with a SCADA system the PLC shall have a field bus or Ethernet port as may be required.

The intention is that all main water pump sets be controlled from the relevant local control panel as well as from the SCADA system. However, process data will be collected via the field bus or Ethernet port for reporting and trending on the SCADA system.

Provision shall be made for control of the pump sets via the SCADA system by means of a selector switch on the motor starter panel located in the pump station which shall have the functions Automatic/Manual. Switching of this selector switch while a pump is running shall not trip the relevant motor.

Terminal strips in programmable logic controller panels.

Wiring directly to the PLC I/O cards is not permitted. All wiring shall be by way of two sets of terminals arranged such that one set of terminals are grouped on a cable by cable basis and the second set of terminals reflect the PLC I/O card slots. Patch Terminals used in PLC cubicles shall be of the knife type.

C3.4.6.7 PLC 7 :PLC SOFTWARE DEVELOPMENT

PLC 7.1 Software

IEC 1131 Standard software with up and down load capabilities programmable over the field bus or Ethernet network and compiles with a standard Graphical User. Interface 32 bit operating system for network applications shall be used.

The software shall allow the reusability of function blocks as building blocks in future applications and shall have a built-in PLC simulator that will allow the running of the IEC program for debugging purposes.

This specification describes the procedure for the development of PLC software. All PLC software developed shall conform to the conventions and standards described in this procedure. The documents described in this procedure shall be produced as outputs during the software development process and together they will enable the maintenance and use of software and they will simplify configuration management of software items/

PLC 7.3 Software Engineering requirements

PLC software shall be designed for continuous reliable operation

The software shall be designed for maintainability. This particular requirement enforces the following constraints on the software development:

It shall be possible to change the software in response to changing requirements by modifying only those sections of code that are directly related to the changed requirements.

The code shall be written on the premises that it shall be possible to make changes to local code sections without affecting the functionality of other code.

The programme style shall be direct and simple wherever possible. This will enable future modifications to be performed by programmers that may not have been involved in the development of the original system. Convoluted programming techniques tend to mask the essential design of the program. Such techniques shall only be used when the programmer has no alternative, or when the benefit (efficiency, size, execution time etc.) significally outweighs the cost.

All PLC programs shall be extensively documented to convey the intended function of the program.

PLC 7.4 Computer Software configuration items

High level plant classes identified during the analysis phase shall be mapped to computer software configuration items (CSCI). Child classes shall be mapped to computer software components (CSC) and computer software units (CSU), in accordance with the class hierarchy of the system.

Each CSCI shall be comprehensively documented in a software requirements specification (SRS).

A CSCI, CSC and CSU shall be characterised by one or more control function instances. These instances may be grouped into one or more control function types. Control function types include interlocks, trips, control algorithms and other functional and logical entities that are required with and control of a specific piece of plant equipment.

PLC 7.5 Software requirements and specifications

Each CSCI be specified by means of a software requirements specification. The software requirements specifications shall meet the following requirements:

Each plant components that has been subjected to object-oriented analysis shall be described by a set of overview class hierarchy diagrams that illustrates the inheritance relationships inherent in the system. The class hierarchy diagrams shall illustrate inheritance in:

- a) The PLC input/output points
- b) Discrete and batch control functions, e.g. interlocks, trips, start-up sequence
- c) Continuous process control functions, e.g. PID control
- d) The analog and digital values that are generated by the PLC software and/or communicated to the SCADA system, e.g. metering information.

RETROFITTING OF 6 sewer pump stations, INSTALLATION OF INLINE GRINDERS AND REPAIRS TO WASTE WATER TREATMENT PLANT IN HOOPSTAD AND TIKWANA

SCOPE OF WORK

The requirements section shall contain an introductory subsection that describes the purpose of the software system, and in particular, the role of the PLC software in the system.

The requirements section shall specify the names and descriptions of all analog and digital plant inputs and outputs that are communicated to or from the PLC.

The requirements section shall incorporate several subsections called control function sections (CFS), each describing a number of instances of a specific control function. For example, a PLC program may implement several PID control loops. The software segment specification would then incorporate a PID Control Loops section in which each PID control loop is described in detail, in keeping with a standard layout.

The requirement section shall list and describe all digital or analog values that are generated by the PLC software (or that are scanned into the PLC) and then transmitted to the SCADA system.

The requirements sections shall include a detailed explanation of how the PLC driven systems operate in conjunction with the hard –wired systems.

PLC 7.6 Generic Layout

Each CS shall conform to the following generic layout:

a) Control function (CF) type and instance number- this number shall be unique for each instance in a control function class hierarchy

Name A short text label that describes the control function

Description Textual explanation of the behaviour of the control function

Software algorithm Explanation of the PLC logic that is used to implement the control

function. The names of all the PLC inputs and outputs that are used

shall be given in the algorithm description.

b) SCADA indication – the SCADA indication details of the control function are given, including the location of the indicator, the colour of the indicator, and the message details.

c) Notes and associated conditions – any settings that may be relevant to the CF, or any conditions such as alarms or pre-conditions that relate to the CF shall be documented.

For example the requirements section may incorporate a subsection describing the interlocks that pertain to the particular class. Each interlock description shall incorporate the following:

Interlock number
This number shall be unique for each interlock in a class hierarchy

Name A short text label that is normally the same as the interlock message

Description Textual explanation of the function of the interlock

Software algorithm Explanation of the PLC logic that is used to implement the interlock. The names of all the PLC inputs and outputs that are used shall be given in the algorithm description.

SCADA indication The SCADA indication details of the interlock are given, including the location of the indicator, the colour of the indicator, and the message details

Pre-condition Any pre-conditions that must be satisfied before it can be confirmed that the interlock is unhealthy. In some cases it may be necessary to explain the algorithm and PLC logic of the pre-conditions and any overrides that may be present.

PLC 7.7 Naming and documentation of software

Each PLC program shall be documented in a manner that allows the reader to understand the functionality of the program and to locate the desired section of ladder logic.

A short program description document shall be produced for each PLC program. The primary functions of the program shall be listed in this document. For example the program might monitor and control electricity reticulation, provide water quality monitoring functions, and allow for the control of certain pump sets.

Each PLC program shall consist of several segments. Segments are used to divide the program in to logical sections. Segments are the basic schedulable entities within the PLC software. Each segment shall be documented by means of an SFC list. The SFC list gives some indication as to the purpose and structure of the program. Segment comments may be up to one page in length.

PLC segments consist of several SFC's. Each SFC shall be documented by means of a list of networks within the SFC. The list shall identify which of these networks are implemented as macros

and which are specific and unique to the SFC. This list is intended to give some indication as to the purpose and structure of the SFC. SFC comments may be up to one page in length.

Each SCF consists of a number of networks. The logic employed in each network shall be described in the network comments that may be up to one page in length. Where a network is implemented by a macro, the macro comments may be copied to the network comments screen or the network comments screen may simply reference the macro comments. Macro comments and network comments shall describe the PLC logic in terms of Power flow that is regulated by the opening and closing of coils.

Each coil and register that is used in the PLC program shall be described in the comments field that may be 50 characters long (10+10+10+20).

Print outs of appropriate ladder logic shall be attached to all network comment documents.

PLC 7.8 Macros

Macros shall be used wherever possible in the implementation of PLC software in order to promote software re-use.

Common software elements shall be identified from the plant class hierarchy.

A set of macros shall be associated with a specific plant class hierarchy, although a direct mapping of macros to entities in the hierarchy may not result in optimal re-usability. In such instances, the macros shall rather be designed for optimal re-usability.

The PLC logic used in macros shall be described in the macro comments screen.

The design of macros shall not be explicitly documented. The software segment specification relating to each software segment identified in the plant class hierarchy shall describe the functional and behavioural aspects of the PLC software. If the software has been implemented in terms of macros, then the reader shall know this from the network comments that are associated with the relevant software.

PLC 7.9 Operations manual

An Operations Manual shall be delivered with the software. This manual shall contain the following information:

- a) Details of all instruments and devices that shall be connected to the PLC
- b) Details of PLC network connections
- c) A user document that describes how the PLC program shall operate in conjunction with SCADA systems, hard wired systems and mimic panels. This document shall inform the user of alternative control options and give some ideas of how the PLC system integrated with the plant and its hard wired systems.

PLC 7.10 Qualifications

PLC 7.10.1Test Specification

A test plan shall be developed for each software segment whilst the software segment specification is being drawn up.

The test plan shall focus initially on verifying the architectural design of the program that is the partitioning into segments, SFC's and networks has been performed in an intuitive and logical manner.

Each trip, interlock and data output shall be tested by varying all pre-conditions and overrides. The test scenario for each case shall be comprehensively described. Details of how to model a particular override or pre-condition by modifying the hard wired configuration shall be given. Explicit criteria shall be given in terms of which the interlock or trip shall be deemed to have passed or failed the test.

PLC 7.10.2 WALK-THOROUGHS

Structured walk-throughs and code inspections shall be carried out during the development of each software segment.

Walk-throughs shall initially focus on verifying the architectural design of the program that is the partitioning into segments, SFC's and networks has been performed in an intuitive and logical manner.

Ladder logic networks shall be tested individually. All possible coil status permutations shall be identified for each network. Factors that may cause coil statuses to change shall be identified and the ramifications of changing coil statuses shall be investigated. Where registers are used in the networks, factors affecting register values shall be identified, and tests shall be devised to investigate the behaviour of the software when register values changes to and from critical values.

A checklist shall be used to allow PLC programs to be checked for common PLC programming faults. The checklist shall be maintained on an on-going basis to ensure that the maximum number of common errors can be detected before testing and commissioning.

Walk through inspections shall be limited in duration to two hours or less.

Walk-through inspections shall be performed by a team of not less than three (and not more than four)people.

PLC 7.10.3 TEST PROCEDURE

Software testing shall be carried out on site.

Before testing begins, the plant to be used in the on-site tests shall be decommissioned and configured for testing.

Trips, interlocks and data outputs shall be tested individually. These tests shall follow the test specification that was produced in parallel with the software segment specification.

A test compliance document shall be completed during the test phase, and this document shall be included in the project documentation.

PLC 7.10.4 CHANGE MANAGEMENT

Changes to the functionality of a program may be required if the system fails due to an identifiable fault in the program, if the requirements change such that the change in specification forces a change in the software, or if sub-optimal system behaviour can be provided through software modification.

Faults reports shall be generated by the plant operators and they shall be passed on to the software configuration manager. Similarly, any change in requirements that leads to a change in specification shall be passed on to the software configuration manager.

Changes shall first be made to the software requirements specification. The ramifications of making the changes shall be investigated, and the software modules (segments, SFC, networks) that are affected shall be identified and modified.

Before the software changes are affected, a test plan shall be produced that describes how the changes are to be approved. This test plan shall be incorporated in the project documentation in the Change control section.

A walk – through inspection shall be held once the changes are complete. The primary goal of this inspection shall be to determine that all possible side effects that may be produced by the changes have been anticipated and explicitly dealt with.

Minutes from this inspection shall be appended to the body of the main project documentation in the Change control section.

The modified software shall then be tested according to the test procedure that was produced when the specification was amended.

C3.4.7 UN-INTERRUPTED POWER SUPPLY

INDEX

ITEM	DESCRIPTION
UPS 01	UN-INTERRUPTED POWER SUPPLY
UPS 02	CONSTRUCTION OF CUBICLES AND SWITCHBOARDS
UPS 03	INSTRUMENTATION AND CONTROLS
UPS 04	ALARMS
UPS 05	VENTILATION
UPS 06	QUALITY ASSURANCE
UPS 07	INSTRUCTION OF OPERATOR AND MANUALS
UPS 08	TESTS

C3.4.7.1 UPS01: UNINTERRUPTED POWER SUPPLY (UPS)

- 2.1 Definitions
- (a) UPS shall denote the complete UPS unit with associated controls, remote alarm panel and batteries and any accessories required by the system for its successful operation.
- (b) Power Converter Module shall denote a rectifier, battery charger, inverter, electromechanical by pass switch and manually operated by pass switch.
- (c) Rectifier shall denote that portion of the converter module containing the equipment and controls to convert the incoming AC power to regulated DC power required by the inverter.
- (d) Inverter shall denote that part that converts the DC supplied by the rectifier to AC satisfying the load requirements.
- (e) Electro mechanical by pass static switch shall denote a bypass system provided break free switching from inverter to mains operation and vice versa.

- (f) Battery charger shall denote that portion of the power converter module containing the equipment and controls to convert the incoming AC power to precisely regulated DC power required for battery charging.
- (g) Critical load denotes the load as presented to the UPS by the computer or other load requiring constant supply and associated circuits and apparatus.
- (h) Mean Time Between Failure (MTBF) shall denote an overall MTBF of the UPS as a complete system.
- (i) A system failure shall denote any interruption to, or degradation of the critical load bus voltage or frequency beyond the limits set forth herein.
- (j) Efficiency shall denote the ratio of real output power (kW) to real input power (kW) with the UPS operating at a defined load power at the defined power factor, the battery fully charged and with nominal input voltage.
- 2.2 System Requirements (The Required Input and Output Voltages Are Detailed In Part 2 Of This Specification)
- (A) Input to the UPS
- (a) Input voltage : $400/231V \pm 10\%$ or $231V \pm 5\%$
- (b) Frequency : $50Hz \pm 4\%$
- (c) System : 1 phase 2 wire or 3 phase 4 wire with operative earth

conductor, supplied from utility network or standby generator

set. Refer to detail specification.

- (d) Power factor : Not less than 0,8 lagging.
- (e) Max starting current : 10 times full load current for not more than $\frac{1}{2}$ a cycle with

rectifier soft starting facility.

- (B) Output to Load
- (a) Rating : Refer to detail specification.
- (b) Output voltage : Refer to detail specification.
- (c) Frequency :50 Hz \pm 0,5 Hz.
- (d) System : 1 phase 2 wire or 3 phase 4 wire with operative earth conductor.

Refer to detail specification.

(e) Voltage regulator : ± 10% maximum deviation of steady state voltage recovering to

within 5% in less than 50 ms and to within 1% less in that 100 ms.

(f) Frequency stability : Normally automatically synchronised to mains frequency if the

latter is within 50 Hz ± 2% (adjustable window) Runs free at 50 Hz ±

0,5 Hz at any load when mains is out of limits.

- (g) Harmonic content : Less than 4% total distortion.
- (h) Amplitude modulation : Less than 2%
- (C) Overall Performance

SCOPE OF WORK

Efficiency (overall) : 80 85%

(D) Ambient Operating Conditions

Refer to Section 1, General - Clause 5

(E) System Description

The system shall consist of a static UPS complete with the following components:

- (a) Rectifier/charger.
- (b) Inverter.
- (c) Battery.
- (d) Automatic electronic no break bypass circuit and switch.
- (e) Separate manual bypass switch.
- (f) Protective devices and measuring equipment.
- (g) The required controls and necessary equipment.
- (h) A self-monitoring system with digital readout by means of which all critical functions can be checked.

Note: Requirement (h) Is Only For Ups Systems Above 200 kVA

The system shall be capable of providing an uninterrupted supply to the load with the output characteristics as specified for a minimum period of 30 minutes during a total mains failure (i.e. normal mains and standby generator supply failure). The batteries shall be rated at an AC load power factor of 0,8 lagging.

The complete system, including all controls shall be designed in such a way that the failure of any one vital central component will NOT cause a complete system failure. If necessary such a failure must be avoided by connecting the load directly to the mains by means of the bypass switch.

The UPS shall operate satisfactorily synchronous with the mains supply even under severe conditions of up to 100% unbalanced load.

The UPS shall be amply rated to carry the stated full load current. The UPS shall furthermore be capable of withstanding the following overloads.

Static Overloads: 100% of full load continuously.

125% of full load for 5 minutes.

150% of full load for 2 minutes.

165% of full load for 1 second with inductive decay after initial equipment switch on surge current.

Dynamic Overload: 300% for less than 5 msec.

1000% for less than 1 msec.

All component parts, cables and other connections shall be amply rated to withstand the overloads stated and maintain the input voltage at the load within the tolerances stated.

SCOPE OF WORK

The equipment shall be designed for the maximum operating efficiency. The efficiency shall be determined when the system is delivering full load at 0,8 power factor with the batteries fully charged. The load required by the auxiliary equipment (controls, alarms, etc.). Electronic switches and cabinet fan shall be included in the determination of overall efficiency. A typical test report clearly showing how the efficiencies are calculated, shall be submitted with the tender.

It shall be the responsibility of the successful tenderer to ensure satisfactory operation of the complete system for the load to be supplied. It is, therefore, essential that the tenderer acquaints himself fully with typical load conditions before the tender closing date.

with typical load conditions before the tender closing date.		
All cabinets containing thyristors shall be adequately screened and earthed to prevent direct radio frequency radiation.		
Tenderers shall submit with their tenders a schematic diagram showing :		
Input circuit breakers.		
System busbars.		
Rectifiers.		
Batteries.		
Inverters.		
Electronic switches.		
Bypass circuit.		
Detour circuit.		
Fuse protection.		
Output circuit breakers.		
Oscillator.		
Power supply circuits to oscillator, alarms, controls, etc.		
Battery isolator.		
The diagram shall also show the relative phase displacement of the rectifier transformers.		
NOTE: This Is Not Applicable To Systems Below 200kVA.		
(F) Inverter Oscillator		
The inverter shall contain an oscillator capable of operating and maintaining the inverter output frequency as specified. The inverter oscillator shall be capable of frequency synchronisation and		

The inverter shall contain an oscillator capable of operating and maintaining the inverter output frequency as specified. The inverter oscillator shall be capable of frequency synchronisation and phase locking to the mains (or standby generator) power source frequency. When operating as a slave to the mains or standby power and a failure occurs in the slaving signal, the invertor oscillator shall automatically revert to a free running state and maintain the specified limits. All changes in output frequency to free run or synchronise shall be gradual to suit the load requirements.

(G) Rectifier

The UPS shall have its own rectifier and rectifier transformer which shall operate satisfactorily from the mains or standby supply.

The rectifier shall be of the solid state type providing full wave rectification of the input voltage suitably regulated to suit the input requirements of the inverter. Where necessary, a high grade DC filter shall be utilised to limit the output ripple to within acceptable levels for the inverter input. Current limiting features shall be provided to protect the rectifier. The current limiting settings shall be variable for final adjustment on site.

Voltage free contacts shall be provided for the malfunction alarms of the rectifier.

An input monitoring circuit shall be provided for the rectifier. This circuit shall switch off the rectifier when the r.m.s. value or frequency of the input voltage falls below present values.

The necessary protection circuitry shall be provided to switch off the rectifier if any one of the rectifier phases should fail, thus presenting an unbalanced load to the incoming supply.

The output of the rectifier shall be connected in parallel to the battery and inverter.

The rectifier shall have over temperature protection. Temperature sensing probes shall be placed on the thyristor housing, thyristor mounting, or on the heat sink close to the thyristor. The sensing of the off coming air temperature alone is not acceptable.

Tenderers shall take into account the possible effects of harmonics that may be present on the input supply due to non-sinusoidal waveforms at the rectifier input, phase commutation, the effect of reactance during phase commutation etc. The input voltage monitoring circuits of the rectifiers shall be adequately filtered and buffered to ensure reliable load control and to prevent continuous on off switching of the rectifiers.

For three phase units each of the three rectifier transformers shall have a different primary to secondary phase displacement in order to minimise the harmonics generated by the rectifiers.

NOTE: This Is Not Applicable For Systems Below 200 kVA

(H) Inverter

The inverter shall be adequately protected against any excessive overload or short circuits that occur in the load. Reactive current limiting or other methods shall be employed to render the thyristors short circuit proof. The successful tenderer shall replace any thyristors or any inverter components at his own expense if these should be damaged.

The necessary feedback and control circuits shall be incorporated to ensure satisfactory operation separately or in synchronisation with the mains supply under all conditions of dynamic load variations, stated overloads, severe unbalanced conditions and high operating temperatures. The thyristor bridge shall contain the necessary auxiliary circuitry to ensure satisfactory operation.

The output of the inverter shall be connected in parallel with the thyristor switch output.

Each inverter shall have over temperature protection similar to the over temperature protection for the rectifier.

A discharge device shall be provided across the D.C. input to the inverter, which will discharge any capacitors in the inverter module when it is switched off.

Battery charger

The battery charger shall be a solid state, constant voltage type providing full wave rectification of the input voltage with the output regulated to an accuracy as specified. A high grade D.C. filter shall be utilised to limit the output ripple to the stated tolerance. Current limiting features shall be provided.

The value of the current limit setting, shall be in accordance with the maximum allowable charging current that the batteries can withstand.

The maintained voltage on float charge shall be such as to give maximum life to the batteries whilst maintaining the maximum charge conservation and minimising gas formation and water loss. The optimum float charge voltage shall be specified by the battery manufacturer but is expected to be approximately 2,23 volts per cell. The voltage shall be kept within \pm 0,5% of the nominal value for all loads from no load to the full rated battery charger current when supplying the full output with batteries discharged.

(J) Computer rooms/office UPS installation

The rectifier shall be equipped with 2 independent over voltage shutdown contacts for maximum charger security.

The battery charger shall be designed to charge the batteries to 90% of its fully charged capacity within 14 hours and to 100% capacity within 20 hours.

The battery charger shall be capable of boost charging the batteries to 2,6 volt per cell. The boost facility shall be manually operated.

The battery charger shall be provided with a current limiting circuit.

The current limit setting shall be variable for easy adjustment on site.

The necessary voltage free contacts for the alarms and battery charger failures shall be allowed for in the tender price.

The battery charger shall have over temperature protection similar to the protection specified for the rectifier.

The battery charger shall have circuitry to inhibit the charging of batteries from the standby generator. This circuitry shall be activated by normally open contacts on the generator control panel. The interconnecting cables will be supplied and installed as part of this contract.

NOTE: This requirement is only applicable for UPS systems above 200kvA

(K) Battery

The battery capacity shall be sufficient to provide full load for the specified time. The capacity shall be rated at a maximum specific gravity of 1,245 at 25 C and correctly filled.

Tenderers shall state the discharge capacity of the battery after 10 hours of charge and the battery voltage at its terminals under various conditions. The inverter shall switch off on low battery voltage.

The battery cells shall be of the maintenance free type.

The batteries shall give satisfactory service for a minimum period of 3 years. Tenderers shall state the maximum expected lifetime of the batteries and motivate their statement, and provide a statement by the battery manufacturer supporting this and stating that the charger offered is suitable for the battery.

The cells must be mounted in a matching steel cabinet or in the same cabinet as the control equipment. The vented type cells should be mounted on a wooden stand, consecutively, numbered with positive and negative terminals clearly marked in a ventilated battery room.

The batteries shall be complete with cell inter-connectors and row inter connectors. The output terminals shall be robust and adequately dimensioned for the output cable terminations.

The inter connectors between cells and shall be made in a manner giving the lowest volt drop and maximum resistance to corrosion.

All connections to cells must consist of flexible cable to avoid mechanical stress at the cell terminals.

The tenderer shall describe the method of removal and replacement of a faulty cell.

The battery shall be complete with a battery fuse isolator capable of breaking the full load current drawn by the inverter. These battery fuse isolators shall be installed in the inverter unit room or cabinet.

Terminal posts should be effective for the expected lifetime of the battery and should be effective even if the cell is overfilled.

The battery may be resistance grounded through 5000 ohm to 10000 ohm for the purpose of ground fault.

Tenderers shall submit full details with dimensioned drawings of the batteries offered.

Tenderers shall submit the calculations and motivations complete with curves supporting the selection of a specific battery cell.

All cabling for the battery shall be installed on PVC cable trays and fitted to the satisfaction of the engineer.

(L) Automatic by pass switch

An integral automatic bypass switch shall be provided to transfer the critical load without break to the mains should the UPS unit fail. The latter unit shall simultaneously be disconnected from the critical load bus. This transfer shall, however, be inhibited if the mains is out of synchronism with the UPS output. Retransfer to the UPS output shall be on a manual or automatic command. This switch must have a cover fitted screwed to the panel so as to make the operating of this switch impossible without having first removed the cover. This switch cover must also have the following words etched in white with a red background mounted on or adjacent the cover: CAUTION: BYPASS SWITCH ONLY: ONLY TO BE OPERATED BY QUALIFIED PERSONNEL

The static switch should prevent "hunting" and after trying unsuccessfully to switch a maximum of three times the static switch should be inhibited from further switching.

C3.4.7.2 UPS 02: CONSTRUCTION OF CUBICLES AND SWITCHBOARDS

All the converter equipment shall be housed in totally enclosed, free standing, floor mounted cubicles, designed to provide adequate ventilation for the equipment.

All cubicles shall be rigid with suitably braced doors providing front access.

All cubicles shall be vermin proof.

All equipment shall be mounted on the metal framework suitably arranged to provide safe operation and ease of access. Fuses and switchgear in particular should be safely accessible even under load conditions.

All power bridges, filters and other major components both in the inverter and rectifier, shall be completely withdrawable to facilitate rapid repair and/or replacement. The method of withdrawal shall be such that a complete module can be extracted in the operating condition so that checks and measurements may be made while in operation and access to all components facilitated.

All electronic printed circuit cards shall be of a good quality and shall be easy and simple to interchange.

All auxiliary power supplies shall be duplicated and shall be connected so as to operate in parallel redundancy. At least two primary sources of power shall be provided for each of the power supplies in the system.

Flexible wires shall not be soldered directly onto terminals but shall have a crimped tab, which is soldered onto a terminal or post. The wire wrapping technique shall be employed for electronic circuits where possible.

The front panel alarms shall be clearly and adequately marked in both official languages. A single line mimic layout of the switchgear shall be provided on the front of the cubicles providing a graphic display of the circuitry of the equipment involved.

All input and output power cables shall be terminated using approved cable glands, onto a cable gland support bracket. The cable conductors shall terminate at the connecting busbars or shall be connected directly to the appropriate switchgear. All power cables shall be properly numbered with wrap around cable markers with punched figures to identify cables at each termination point.

C3.4.7.3 UPS 03: INSTRUMENTATION AND CONTROLS

All the required instrumentation as indicated on the drawings shall be provided.

Supply and install all the necessary controls for the operation of the system. Facilities shall be provided for controlling the rectifier, switching the inverter on, switching the inverter output to the synchronous motor/alternator and controlling the bypass thyristor switch circuit.

All control switching of the rectifier and inverter as well as the bypass operation shall be pushbutton initiated.

Standard electronic equipment from overseas manufactures shall not be accepted if not duly protected with transsorbs and metal oxide varistors in power supplies and external communication lines. Standard electronic equipment not internally protected with transsorbs or MOV's may be protected externally by means of transsorbs and MOV's mounted on klippon type terminals. All external communication and remote power supply lines shall be protected by means of transsorbs and MOV's of sufficient rating mounted on klippon type terminals.

C3.4.7.4 UPS 04: ALARMS

All alarms shall be of the tell-tale type with memory features e.g. a flashing light indicates a fault coupled with an audible alarm. The pressing of the appropriate button shall cancel the audible alarm and allow the alarm lamp to burn continuously until the fault is removed.

The following minimum alarm conditions shall be monitored on the equipment:

- (1) Normal
- (2) Mains failure
- (3) Inverter failure
- (4) Shutdown imminent
- (5) Load on mains
- (6) Overload

(7) Charger fails

Where required a remote panel must be supplied and installed. The alarms indicated must duplicate all the alarms indicated on the UPS control panel. In addition a buzzer must be provided. Any alarm occurring must sound the buzzer to draw attention. An alarm accept pushbutton to silence the buzzer must be provided.

Provision shall be made on all the alarms mentioned above to be remotely monitored. Normally open contacts shall be supplied at the converter for each alarm for this purpose. The contacts shall close under an alarm condition.

C3.4.7.5 UPS 05: VENTILATION

All equipment racks shall be positioned in logical fashion on the floor in a configuration, which will ensure proper ventilation

Each cubicle containing heat-generating equipment (thyristors, transformers electronic circuitry, filters, etc.) shall, where necessary, have extraction ventilation fans mounted on the top of the cubicle to assist air circulation. These fans shall be fed from the output distribution panel of the uninterrupted power supply.

C3.4.7.6 UPS 06: QUALITY ASSURANCE

The manufacturer shall be responsible for the performance as specified herein and to prove such performances to the satisfaction of the engineer. Except as otherwise specified, the supplier must utilise facilities acceptable to the engineer.

C3.4.7.7 UPS 07: INSTRUCTION OF OPERATOR AND MANUALS

After completion of the installation, and when the plant is in running order, the successful tenderer will be required to instruct an attendant in the operation of the plant, until he is fully conversant with the equipment and handling thereof.

Three (3) copies of maintenance, fault localising and operating manuals together with the drawings required shall be handed over to the engineer.

C3.4.7.8 UPS 08: TESTS

The complete testing including the provision of test facilities, instruments, dummy loads and switchgear at the manufacturer's premises in the Republic of South Africa shall form part of this contract. If the factory tests cannot be performed in the RSA, the client may, at his discretion and own cost, decide to attend tests at the supplier's overseas factory. Tenderers shall not allow for this.

For the test in the manufacture's premises the client shall be notified four weeks in advance in order that a representative can be sent to witness these tests.

C3.4.8 SCHEDULE OF MATERIALS AND EQUIPMENT OFFERED

It is **compulsory** for the Bidder to complete the table below, and failure to do so may lead to disqualification. Furthermore, degree of compliance with specifications will count in scoring of tenders received.

C3.4.8.1 MCC

NO.	ITEM	BIDDER'S DESCRIPTION
1	MCC Motor Protection System	
	Manufacturer	
	Make	
	Model Number	
	Is the MCC protection system as per section 0 of this document?	
2	MCC and Distribution Boards	
	Manufacturer	
	Supplier	
	Installation contractor	
	Manufacture of LT circuit breakers	
	Manufacturer of contactors	
	Manufacturer of meters	
	Manufacturer of current transformers	
	Manufacturer of motor protection relays	
C3.4.8.2	SENSORS	
1	Ultrasonic level sensor	
	Manufacturer	
	Supplier	
	Installation contractor	
2	Hydrostatic level sensor	

RETROFITTING OF 6 sewer pump stations, INSTALLATION OF INLINE GRINDERS AND REPAIRS TO WASTE WATER TREATMENT PLANT IN HOOPSTAD AND TIKWANA

SCOPE OF WORK

	Manufacturer	
	Supplier	
	Installation contractor	
3	Pressure sensors	
	Manufacturer	
	Supplier	
	Installation contractor	
4	No-flow sensors	
	Manufacturer	
	Supplier	
	Installation contractor	
	motanation contractor	
C3.4.8.3	OW VOLTAGE CABLES AND TELEMETR	YSYSTEMS
C3.4.8.3 I	LOW VOLTAGE CABLES AND TELEMETRY Low voltage cables	Y SYSTEMS
		Y SYSTEMS
	Low voltage cables	Y SYSTEMS
	Low voltage cables Manufacturer	
	Low voltage cables Manufacturer Supplier	
	Low voltage cables Manufacturer Supplier	
1	Low voltage cables Manufacturer Supplier Installation contractor	
1	Low voltage cables Manufacturer Supplier Installation contractor Telemetry System	
1	Low voltage cables Manufacturer Supplier Installation contractor Telemetry System Manufacturer	
1	Low voltage cables Manufacturer Supplier Installation contractor Telemetry System Manufacturer Supplier	
1	Low voltage cables Manufacturer Supplier Installation contractor Telemetry System Manufacturer Supplier	
1	Low voltage cables Manufacturer Supplier Installation contractor Telemetry System Manufacturer Supplier	
2	Low voltage cables Manufacturer Supplier Installation contractor Telemetry System Manufacturer Supplier Installation contractor Coaxial cable	
2	Low voltage cables Manufacturer Supplier Installation contractor Telemetry System Manufacturer Supplier Installation contractor	

	Installation contractor	
C3.4.8.4	programmable logic controller (plc)	
1	PLC Board	
	Manufacturer	
	Supplier	
	Installation contractor	
C3.4.8.5	UN-INTERRUPTED POWER SUPPLY	
1	Manufacturer	
	Supplier	
	Installation contractor	
2	Battery	
	Manufacturer	***************************************
	Supplier	
	Installation contractor	

C3.4.9 TESTING OF EQUIPMENT

The Contractor shall execute and submit to the Engineer all test results in accordance with clause 29 of the General Conditions of Contract in order to prove that the equipment supplied under the Contract conforms in all respects to the Specifications. In particular, successful execution of the following testing is required in respect of completion of the Works:

C3.4.10 FACTORY ACCEPTANCE TESTING

Any imported material and equipment needs to be inspected, checked and tested before shipment. The contractor shall submit a list of all factory acceptance tests to be performed for all critical equipment supplied under the contract.

The Contractor shall prior to shipment, submit to the Engineer all test results on Plant and Material that are to be manufactured or shipped from foreign destination. No material shall on any account be shipped before receiving the Engineer's approval in writing.

C3.4.11 DRY COMMISSIONING

Once the construction of the Works or a Sub-section has reached the stage of completion where it can be tested, the Contractor shall give to the Employer notice of the date after which the Contractor will be ready to carry out Dry Commissioning of the Works or any

Sub-section thereof. Dry Commissioning shall commence as soon as the Works or a Sub-section is mechanically and electrically ready to test, it shall undergo commissioning tests and inspections to check the following general aspects:

- a) Components of the Works or Sub-section are complete and comply with drawings, specifications and data as indicated in the manufacture's documentation.
- b) The assembly has been carried out in compliance with the above documents and professional practice
- c) Visual checking installation and appearance

In addition dry commissioning shall include the following specific aspects:

- a) Through check of all ergonomic (Lighting and noise), maintainability and safety related aspects.
- b) Through check of flow lines of products, materials, fluids and compressed air
- c) Through check of electrical, hydraulic, pneumatic and electromechanical circuits.
- d) Through check of all functional and control loop tests (Equipment level).
- e) Dry-run of every machine and checking of its operation and, if necessary, running in.
- f) Calibration checks and supporting documentation on all metering and monitoring equipment.
- g) Dry-run or no-load run of every section.
- h) Fixing of equipment, cable racks, pipes, brackets, anchors, etc.
- Written proof of all direction testing and alignment tests on pumps, motors and rotating equipment.
- j) Statutory testing requirements (Lifting, hoisting, pressure vessels etc.)
- k) Checking and testing of all actuators, valve and control valve settings.
- I) Water testing of chemical dosing equipment, pipes, and joints.
- Water tightness and pressure tests on all water retaining structures, pressure vessels, pipelines and pipe fittings.
- n) Completion and assuring of all tests reports and test certificates
- o) Completion of cathodic and lighting protection.
- Compiling of an asset register suitable for interrogation with the financial and Computerised Maintenance Management system of the client.
- q) Completion and issuing of all equipment and O&M manuals including functional specifications and control philosophy.
- r) Supply of all critical spares and special tools on site

Following the successful completion of Dry Commissioning the Employer and Contractor will designate each completed Sub-section to complete as Ready for Wet Commission (RWC). A request to proceed with wet commissioning will be issued by the Contractor after completion of the dry commission phase.

C3.4.12 WET COMMISSIONING

After being designate as Ready for Wet Commissioning ,each process will commence with wet commissioning test runs which shall include the same operations as for dry commissioning tests but with the equipment loaded .The Employer will provide suitable raw water or treated water and power as set out by the Contract. The Contractor shall provide the first charge of chemicals.

- Performance testing of all equipment at specific duties and efficiencies for at least 24 hours continuously.
- a) Check of levels, flows, pressure and temperatures at minimum and maximum operating conditions for all operation scenarios.
- b) Temperatures of all bearings.
- c) Vibration of rotating elements.
- d) Calibration of dosing equipment
- e) Water tightness tests of installation at full production.
- f) Functional and control loop testing (process level)
- g) Site performance tests on individual equipment as per the testing plan
- h) Performance and control tests on the entire system

After successful of the Wet Commissioning of all equipment and process and the Works as a whole, the trial operation period of the entire system will commence. The Engineer shall confirm in writing the date on which successful wet commissioning was achieved.

C3.4.13 TRIAL OPERATION PERIOD

On successful completion of the wet commissioning stage the system will be put into service by the contractor. The contractor shall ensure that the system is put into service in compliance with the O&M Manual and the OHC Act and its Regulations.

A detailed procedure for conducting the trial period will be developed and agreed between the contractor and the Employer.

The purpose of the trial operation is to, demonstrate the reliability of the works, system integrity with regards to system losses and evaluate the training effectiveness of the training of the operators.

Once the trial period has commenced, the works will be operated successfully and continuously for a period of six weeks, with interruptions only to alter plant settings, effect final settings and optimization, test auto-functionality and train the operator in the detail functioning of the plant. The Engineer shall confirm in writing the date on which the trial operation period commenced.

During the **6 weeks** trial operation period, the Contractor shall record all operational data and at its completion submit to the engineer a report confirming final settings, calibration, auto control functions, approved tests and successful training of the operator to the satisfaction of the Employer before a Taking-Over Certificate will be issued for the works in terms of clause 32 of the General Conditions of Contract.

The availability of the equipment during the trial operation period shall not be less than 95%.

All failures occurring during the trial period will be subject to a root cause analysis and repaired accordingly by the contractor. A failure investigation analysis and close-out report shall be submitted for each failure of the works and included in the section dealing with total plans and reports.

If declared unsuccessful, the Engineer may request a repeat of the Trial Operation period. Under such circumstances the Contractor shall repeat the Trail Operation Period and Performance Test as indicated herein within three months after the Engineer's request. The costs in performing this, or any further Performance Tests, will be for the Contractor's account.

C3.4.14 FINAL PERFORMANCE TEST AFTER COMPLETION OF TRIAL PERIOD

Once the trial period has been completed successfully the Engineer shall set the date of the Final Performance Test.

The Performance Test Shall establish:

- a) The capacity and characteristics of the Works are as specified, and that they meet the performance guarantees.
- b) The works can meet the performance guarantee for all the operating scenarios.

The equipment provided by the Contractor on site to test the performance of the equipment shall include all the instrumentation not included in the permanent installation, (e.g. Energy meter), and all tools and suitable trained staff necessary.

If the outcome of the Performance Test, the Contractor Shall inform Personnel Provided by the Employer of all appropriate technical information derived from the result.

On successful completion of the performance Test a take-over report shall be drawn up by the Contractor and shall be signed by the Engineer.

C3.4.15 GUARANTEES OF PERFORMANCE

The Contractor shall guarantee the output and efficiency of all machines, which guarantees shall be binding under the Contract.

The fulfilment of these guarantees shall be demonstrated at the Contractor's factory premises or a suitable off-site test facility approved by the Engineer.

All measuring instruments used in the tests shall have previously been certified by an independent testing authority, not more than one month prior to the test and to the Engineer's satisfaction.

C3.4.16 LIQUIDATED DAMAGES FOR FAILURES TO ACHIEVE GUARANTEES

The Contractor shall ensure that the motor control circuits shall be adequately rated to ensure that the motor control circuits shall be adequately rated to ensure that pumps deliver the "required minimum and maximum discharge", by taking whatever action is necessary should there be any shortfall in the quantity of water measured when the pumps are delivering at the total head associated with the "duty point" in fulfilment of the guaranteed Performance criteria.

Payment by the Contractor in lieu of under-performance of the pump sets relative to guaranteed Performance will not be acceptable.

C3.4.17 DEFECTS NOTIFICATION PERIOD

All equipment supplied under this contract shall be tested and adjusted where necessary by the operator at the end of the 52 weeks Defects Notification Period, to prove that it continues to comply with the specified requirements.

All failures during the Defects Notification Period shall be investigated as described in elsewhere in this document.

C3.4.18 TEST PLAN AND REPORTS

Test reports shall be submitted after the successful completion of each testing phase. The following documents shall be submitted in writing to the Employer:

- a) Testing plan
- b) Progressive testing reports as detailed in the testing plan
- c) Tests on completion: Dry commissioning report and wet commissioning report
- d) Trial operation: Trial operation report and performance test report
- e) Failure investigation reports (where necessary) during defects notification period

C3.4.19 ENGINEERING

C3.4.19.1 CONTRACTOR'S DESIGN

The Contractor shall carry out, and shall be responsible for the final design of all the Permanent Works included in this contract. Cable routes and other layout drawings are provided to indicate the general requirement of the Permanent Works and shall be used for tender purposes. The Contractor shall remain responsible for all detail design and final workshop details.

C3.4.19.2 DRAWINGS.

Drawings are issued in a separate volume.

C 3.5 STANDARD AND TECHNICAL SPECIFICATIONS – CIVIL ENGINEERING WORKS

C3.5 STANDARD AND TECHNICAL SPECIFICATIONS - CIVIL ENGINEERING WORKS

C3.5.1 SCOPE

These Project Specifications are set out in two portions. Portion 1 covers the general description of the project, the facilities available and the requirements to be met. Portion 2 covers variations and additions to the SANS 1200 Standardised Specifications that are applicable to this Contract.

C3.5.2 STATUS

In the event of any discrepancy between the Project Specifications and a part or parts of the SANS 1200 Standardised Specifications, the Schedule of Quantities or the Drawings, the Project Specifications shall take precedence.

C3.5.3 PORTION 1: THE WORKS

PS APPLICABLE STANDARDISED SPECIFICATIONS

Portion 1: The Works

- PS 1 General Description of Works
- PS 2 Description of Site and Access
- PS 3 Nature of Ground and Sub-soil Conditions
- PS 4 Details of Contract
- PS 5 Construction Programme
- PS 6 Site Facilities Available
- PS 7 Site Facilities Required
- PS 8 Features Requiring Special Attention
- PS 9 Preservation of the Site
- PS 10 Key Personnel
- PS 11 Safety Personnel
- PS 12 Site Meetings
- PS 13 Notices to the Engineer
- PS 14 Use of defective Works
- PS 15 SABS 1200 Series Standardized Specifications
- PS 16 Prime cost items and Provisional sums

For the purposes of this Contract, the following SANS 1200 Standardised Specifications shall apply:

SANS 1200 A : General (1986)

SANS 1200 C : Site clearance (1982)

SANS 1200 D : Earthworks (1990)

SANS 1200 DB : Earthworks (pipe trenches) (1989)

SANS 1200 L : Medium-pressure pipelines (1983)

SANS 1200 LB : Bedding (pipes) (1983)

SANS 1200 LD : Sewers (1982)

SANS 1200 LE : Stormwater drainage (1982)

SANS 1200 PA : Fencing (1984)

Variations and additions to the following SANS 1200 Standardised Specifications are given in **Portion 2** of the Project Specifications:

SANS 1200 A : General

SANS 1200 C : Site clearance

SANS 1200 D : Earthworks

SANS 1200 DB : Earthworks (pipe trenches)

SANS 1200 G : Concrete (structural)

SANS 1200 H : Structural Steel

SANS 1200 HB : Cladding and sheeting

SANS 1200 L : Medium-pressure pipelines

SANS 1200 LB : Bedding (pipes)

SANS 1200 LD : Sewers

SANS 1200 LE : Stormwater drainage

C3.5.4 PORTION 1: THE WORKS

PS1 GENERAL DESCRIPTION OF WORKS

This contract comprises of the retrofitting of 6 sewer pump stations, installation of inline grinders and repairs to waste water treatment plant in hoopstad and tikwana including the supply, delivery, installation, testing, commissioning and handing over of the pumps.

The Contractor's obligations under Contract comprise the construction, completion and maintenance of the Works. The provision of all labour, materials, construction plant, temporary works and everything, whether of a temporary or permanent nature required in and for such construction, completion and maintenance so far as the necessity for providing the same is specified in or reasonably to be inferred in the Contract.

PS2 DESCRIPTION OF SITE AND ACCESS

The sites of the works are the existing at Hoopstaad and Tikwana pump stations, which are situated along R700 provincial road between Bloemfontein and the North West Province. The main town is Hoopstad and its twonship is Tikwana.

PS3 NATURE OF GROUND AND SUBSOIL CONDITIONS

No geotechnical report will be provided to the Contractor. It is the Contractor's responsibility in terms of the General Conditions of Contract, to satisfy himself as to the conditions on the site and the possible variation thereto due to seasonal effects.

PS4 DETAILS OF CONTRACT

- Retrofitting of 6 sewer pump stations .
- Installation of inline grinders.
- Repairs to waste water treatment plant.

PS 5 CONSTRUCTION PROGRAMME

PS 5.1 Time for Completion

Time is of the essence for this contract. The works shall be completed in a period of four (4) months.

PS 5.2 Bidder's Programme

The Bidder shall attach a preliminary programme indicating each portion of the works. The proposed order and rate of progress of the various construction activities shall be consistent with, and in support of, his time required for completion and measured against recorded deliverables.

PS 5.3 Contractor's Programme

After award of the Contract, the Contractor shall submit a detailed programme to the Engineer for approval. The Engineer may from time to time during the contract, require this programme to be amended in the interest of the project, and such amended and approved programme shall be adhered to rigidly.

PS 6 SITE FACILITIES AVAILABLE

PS 6.1 Water and Electricity Supply

The Contractor shall make his own arrangements for the supply and distribution of water and power.

PS 6.2 Location of Contractor's Camp and Depots

The Employer, in conjunction with the Engineer, will allocate a suitable area to the Contractors for the erection of temporary site offices and for storing materials.

PS 6.3 Sources of Construction Materials

If the existing material is not of the required standard, suitable material will be imported from an approved commercial source. All construction material must be found, selected and supplied by the Contractor him/herself and approved by the Engineer.

PS 7 SITE FACILITIES REQUIRED

No existing facilities are available. All the necessary site facilities shall be provided and maintained by the Contractor. The requirements regarding notice boards, laboratories, accommodation and survey equipment for use by the Engineer. etc. are set out in sections PSA and PSAB of the project specification.

PS 7.1 Temporary Offices and Storage Sheds

The Contractor shall provide, erect, maintain and remove on completion of the Contract, ample temporary offices and sheds for the proper storage of perishable materials and for the use of his workmen. An office approximately 4m x 5m in size with a desk and 10 chairs is to be provided for the purpose of holding site meetings.

PS 7.2 Laboratory Facilities

No laboratory, testing or storage facilities are available from the Employer. The Contractor must make his own arrangements and provide all facilities which must be acceptable to the Engineer for all testing required. Refer also to Clause PSA 4.1

PS 7.3 Sanitary Facilities

No separate sanitation facilities for the specific use of the Engineer or his staff need be provided. The Contractor shall provide and maintain adequate and approved temporary ablution and latrine facilities for his workmen on site and remove on completion.

PS 7.4 Telephone Facilities

No telephone facilities are available from the Employer. The Contractor is advised to establish his/her own communication facilities from the site to his/her outside organizations.

PS 7.5 Accommodations for the Engineer

A separate office is required for the specific use of the Engineer.

PS 8 FEATURES REQUIRING SPECIAL ATTENTION

PS 8.1 Existing Services

There is little data on the existing services; neither the Employer nor the Engineer will accept the responsibility for the accuracy or for any omission that may have been made.

The Contractor shall take all reasonable steps to protect any existing works against damage which may arise as a result of his operations on the site. The Contractor shall acquaint himself with all existing works. Before any excavation is commenced the Contractor shall submit to the owners of such works plans showing the extent of the proposed excavations together with a programme giving approximate

dates on which excavations will be commenced, and shall where possible, obtain from the owners plans showing the position of all existing works.

Where the Contractor anticipates that it will be virtually impossible for him/her to carry out the work without causing damaged to existing services or works, and the Engineer in his discretion feels such damage is likely to occur, the Contractor shall make arrangements with the authority concerned to temporarily remove, deviate, protect or suspend the work or service concerned and pay the costs incurred, which shall be reimbursed to the Contractor.

The Contractor shall be responsible for the proper consolidation of the ground under and around any exposed mains, cables, valves, stopcock boxes and the like. The uncovering of boxes and covers that may become buried during excavation or refilling operation will be at the expense of the Contractor.

When crossing under or running parallel to poles supporting electrical services, they shall be sustained securely in place until the work is complete and shall then be made safe as before.

Where any existing services are crossed or temporarily removed, the Contractor shall be responsible for the repair and/or reinstatement of the crossings to the satisfaction of the owners and the Engineer's Representative.

The Contractor shall be held responsible for damage to any existing works and any damage caused, including any claims, which arise as a result there from. All such claims shall be borne by the Contractor, unless it is established by the Engineer that the Contractor exercised reasonable care and damage was unavoidable and that the notices were served timeously.

All damage done to existing works shall be immediately notified to the owners concerned and to the Engineer. If so direction by the Engineer, the positions of any existing work shall be changed by the Contractor to meet the requirements of the proposed work and the cost of such changes will be paid for as extra works.

PS 9 PRESERVATION OF THE SITE

The Contractor shall not start any fires and naked flames/smoking is strictly prohibited.

The Contractor shall not permit the destruction of or injury to, animals or bird life within the site of the works during the period of the contract.

During the progress of the work and at the completion thereof the site is to be kept, and left, in a clean and orderly condition to the satisfaction of the Engineer.

The Contractor shall at all times store materials and equipment for which he is responsible in an orderly manner and shall keep the premises free from debris and obstruction.

Only trees marked and indicated by the Engineer may be removed.

Existing graves are to be identified and protected from damage arising out of construction activities.

PS 10 KEY PERSONNEL

The Contractor shall furnish the Engineer with a list of addresses and telephone numbers of key personnel in the Contractor's organization who may be contacted in an emergency both during and outside office hours.

PS 11 SAFETY OF WORKMEN

The safe conduct of the Works shall be a primary consideration and the entire Works (until completion or termination of the contract) shall be carried out in conformity with the Occupational Health and Safety Act, 1993 (Act No 85 of 1993) and all other applicable statutory regulations and requirements. Bidders must price their Bids accordingly.

Particular attention is drawn to the following:

If the Contractor has more than 20 employees, a health and safety representative (or representatives) must be designated.

The Contractor is responsible for the compliance with the Act by all his/her subcontractors, whether or not nominated and/or approved by the Employer.

- c) The Contractor accepts sole responsibility for compliance with the relevant duties, obligations and prohibitions by the Act, and expressly absolved the Employer and the Employer's consulting engineer's of responsibility for compliance with the Act in respect of work included in the contract
- d) The Contractor shall be obliged to report forthwith to the Employer any investigation, complaint or criminal charge which may arise as a consequence of the provisions of the Act pursuant to work performed on behalf of the Employer.
- e) The Contractor shall provide and maintain in readiness on the Site, all equipment and materials necessary to render first aid in case of accidents or other emergencies. The Contractor shall also assign to the Works and designate for this purpose, trained employees who are able to render first aid.

PS 12 SITE MEETINGS

The Engineer shall hold regular site meetings and keep and circulate minutes. The Contractor shall attend and shall ensure that all sub-contractors are represented when required by the Engineer.

PS 13 NOTICES TO THE ENGINEER

Apart from the specific notice periods called for in the Contract Documents, the Contractor shall give the Engineer forty eight (48) hours notice of any work requiring inspection by the Engineer. No further subsequent work dependent on such approval may be undertaken until confirmation of such receipt by the Engineer has been received.

PS 14 USES OF DEFECTIVE WORKS

Should any of the works be found to be not in accordance with the Contract, the Client shall have the right to use such defective works until the Contractor shall have rectified the defect or replaced the defective works with works complying with the Contract, without prejudice to any of the Client's rights under the Contract and without incurring any obligation in respect of the use of the defective works.

PS 15 SABS 1200 SERIES STANDARDIZED SPECIFICATIONS

The Contractor shall provide on site a copy of the relevant sections of both SANS 1200 Series Standardized Specification and the related 0120 Code of Practice.

PS 16 PRIME COST ITEMS AND PROVISIONAL SUMS

In cases of any provisional sum set out in the Schedule of Quantities for work which has not been specified or scheduled in detail when the contract is entered into, where work to which the provisional sum relates has been ordered by the Engineer and such work is: -

 Executed by the Contractor, it shall be valued in accordance with Clause 6.4 of the General Conditions of Contract,

- b) Executed by a Sub-Contractor, the Contractor shall be reimbursed the sum or sums he actually paid to the Sub-Contractor plus either:
 - i) A commission of 7,5% (seven and one half percent) on the sum or sums actually paid to the Sub-Contractor, irrespective of by whom payment is made to the Sub-Contractor, or
 - ii) If the Contractor shall have added to the provisional sum in question, a sum in respect of charges and profits, a sum in the same proportion to the amount paid to the provisional sum

Where sums are stated in the Schedule of Quantities to be provided to cover the prime cost (P.C.) for goods or materials to be supplied under the Contract, the amount to therefore be paid to the Contractor shall be the actual price paid by him in substitution for the prime cost sum, together with any charge included by the Contractor in his Bid for labour, profit, carriage, establishment and other charges.

When required by the Engineer, the Contractor shall produce all invoices, vouchers and receipts in respect of payments made by him in connection with provisional or prime cost items.

C3.5.5 PORTION 2: VARIATIONS FROM STANDARD SPECIFICATIONS

PSC 2 CONSTRUCTION

PSD SABS 1200 D: EARTHWORKS

PSD 3 MATERIALS

PSD 3.1 Classification for Excavation Purposes

Classification of material other than soft shall be agreed upon prior to excavation commencing. The Contractor shall immediately inform the Engineer if and when the nature of the material being excavated warrants a new classification. Failure on the part of the Contractor to notify the Engineer timeously shall entitle the Engineer to classify the material at his discretion.

PSD 5 CONSTRUCTION

PSD 5.2 Methods and Procedures

PSD 5.2.2.4 Selection and Stockpiling

The Contractor shall select suitable material from the excavated and stockpiled materials for which use it is intended, disregard unsuitable material and reserve material for other purposes as necessary. When required and as ordered by the Engineer, material shall be stockpiled for later use when excavation thereof is unavoidable in order to excavate the material required at the time.

PSD 5.2.5.1 Free-haul

All haul within the site of works or within a distance of 2,0 km outside the of the boundaries of the Contract as indicated on the drawings shall be regarded as free-haul.

PSD 8 MEASUREMENT AND PAYMENT

PSD 8.1 Basic Principles

Further to the requirements of Clause 8.1, no allowances will be made for bulking and/or shrinkage. It shall be assumed that 1 cubic metre of excavated material from the site shall form 1 cubic metre of compacted fill. Measurements for bulk earthworks shall be from topographical survey and DTM modeling. No extra or separate payment will be made for work considered to be of a restricted nature.

PSDB EARTHWORKS (PIPE TRENCHES)

PSDB 3 MATERIALS

PSDB 3.5 BACKFILL MATERIALS

"(c) Cement-stabilized backfilling

Backfilling shall, where directed by the Engineer, be stabilized with 5% cement. The aggregate shall consist of approved soil or gravel containing stones not bigger than 38 mm and with a plasticity index not exceeding 10.

The soil or gravel shall be mixed with 5% cement and shall be compacted in layers of 100 mm thick to 90% of modified AASHTO density.

(d) Soilcrete backfilling

The aggregate for soilcrete shall be mixed with 5% cement and shall consist of approved soil or gravel containing stones not bigger than 38 mm and with a plasticity index not exceeding 10.

The soil or gravel shall be mixed in a concrete mixer with the cement and enough water to acquire a consistency that allows the mixture to be placed with vibrators to fill all voids between the pipe and the sides of the trench. Shuttering shall be used where necessary."

PSDB 5 CONSTRUCTION

PSDB 5.1 PRECAUTIONS

PSDB 5.1.3 Accommodation of traffic and access to properties

(b) Where necessary to achieve compliance by the Contractor with his obligations in terms of subclause PS 8.5 of Portion 1 of the Project Specifications to provide and maintain pedestrian and vehicular access to properties affected by the works, the Contractor shall construct and maintain to the satisfaction of the Engineer, such temporary access roads around, and/or steel or timber bridges over excavations in roads, pavements, entrances or accesses to properties.

Temporary pedestrian access bridges shall be at least 1,2 m wide and temporary access bridges for vehicles shall be at least 3,6 m wide. All temporary access bridges shall be fitted with handrails as well as protective mesh fencing on both sides.

On completion of the work, the Contractor shall dismantle and remove all such temporary constructions and reinstate these areas to their former condition.

Except only where the Engineer has included in the Schedule of Quantities, particular payment items specifically therefor, the Contractor will not be paid directly for the construction and maintenance of temporary access roads and/or the provision and maintenance of bridges as aforementioned, and the costs thereof shall be deemed included in the Contractor's tendered rates for excavation."

PSDB 5.2 MINIMUM BASE WIDTHS

The specified width of trenches and the width of the excavation measured for payment shall not be less than 0,5 m, but the Contractor may reduce the actual width with the Engineer's permission."

PSDB 5.4 EXCAVATION

"Except where otherwise specified, trenches shall be of such a depth that the minimum cover over the pipes shall be 800 mm except at road-crossings where the minimum cover shall be 1 000 mm."

PSDB 5.6 BACKFILL

PSDB 8 MEASUREMENT AND PAYMENT

PSDB 8.3 SCHEDULED ITEMS

PSDB 8.3.2 Excavation

(a) Excavate in all materials, for trenches, backfill compact and

dispose of surplus material

REPLACE "of 1,0 m" IN THE FIRST SENTENCE OF 8.3.2(a) WITH:

"as specified in the Tender Drawings."

(b) Extra over item (a) above for:

"No payments will be made under subitems (1) and (2) in respect of any materials measured and paid for under subitem 3 below."

- "(3) Hand excavation where ordered by the Engineer in:
 - (a) Soft material Unit: m3
 - (b) Intermediate material Unit: m³
 - (c) Hard material Unit: m3

The unit of measurement shall be the cubic metre of material, measured in place according to the authorised dimensions, which was excavated by hand on the specific prior written instructions of the Engineer; provided always that the Engineer's said instruction shall have stated that measurement and payment for such hand excavation will be in accordance with this item.

The tendered rate shall include full compensation for the additional cost, effort and time resulting from excavating in the respective materials using hand methods only.

The Engineer shall not be obliged to authorise payment under this item in respect of any hand excavation carried out (whether ordered in writing or otherwise), which hand excavation was in any case necessary to achieve compliance by the Contractor with his obligations under the Contract to

- (i) utilise construction appropriate to the nature of the specific parts of the works;
 - (ii) protect existing structures and/or services; and/or
 - (iii) comply with all prevailing legislation and regulations.
- (4) Backfill stabilized with 5% cement where directed

by the Engineer Unit: m3

and/or

The unit of measurement shall be the cubic metre of backfill material, measured in place after compaction according to the authorised dimensions, which was stabilized on the Engineer's instructions in accordance with subclause PSDB 3.5(c).

The tendered rate shall include full compensation for supplying the cement and for selecting, mixing, backfilling and compacting the stabilized material to 90% of modified AASHTO density.

(5) Soilcrete backfill where directed by the Engineer Unit: m³

The unit of measurement shall be the cubic metre of soilcrete placed on the Engineer's instructions in accordance with subclause PSDB 3.5(d), measured in place according to the authorised dimensions.

The tendered rate shall include full compensation for supplying the cement and for selecting, mixing and placing the soilcrete as well as for the cost of shuttering if required."

"(d) Excavate in all materials for stormwater inlet and outlet structures and for manholes, catchpits, valve chambers and the like, irrespective of depth, and backfill around structures: Unit: m³

The unit of measurement shall be the cubic metre of material excavated, measured in place according to the authorised dimensions, and excluding the volume of material excavated and paid for under subitem (a).

The tendered rate shall include for the costs of excavating in all materials, backfilling, compacting, trimming and tidying the final surface around the structure, disposing of surplus and unsuitable materials within the free-haul distance and, where applicable, selecting and keeping separate, excavated material suitable for use as backfill.

(e) Excavate open drains in all materials Unit: m³

The tendered rates shall include full compensation for excavating in all materials within the dimensions specified or authorised by the Engineer and to the specified lines and profiles, for the disposal of surplus and unsuitable excavated material where applicable, and in the case of item (d), for backfilling with suitable approved material compacted to 90% of modified AASHTO density around the structures.

- (f) Extra over subitems (d) and (e) for excavating in:
 - (1) Intermediate material Unit: m³
 - (2) Hard rock material Unit: m³

Measurement and payment shall be in accordance with the provisions of 8.3.2(b) of SABS 1200 D (as amended)."

PSDB 8.3.3 Excavation ancillaries

PSDB 8.3.3.3 Compaction in road reserves

"PSDB 8.3.3.3 Compaction in road crossings"

"To determine the volume in the case of gravel roads, the depth will be measured from the underside of the gravel wearing course to the top of the fill blanket, and in the case of bitumen roads, from the underside of the subbase to the top of the fill blanket.

The rest of the trench shall be backfilled as specified in clauses 5.9.3, 5.9.4 and 5.9.5, as applicable, and payment will be made under item 8.3.6.1."

PSDB 8.3.7 "Accommodation of traffic Unit: sum

The tendered sum shall, (except where particular items are scheduled to cover particular costs) include full compensation for compliance with the requirements of 5.1.3 of SABS 1200 DB (as amended), including the construction and maintenance of bypasses and the use of existing roads as bypasses during the construction period.

It shall also include full compensation: for the provision, maintenance and removal of all traffic control measures, including temporary traffic signs, road markings, lighting, barricading, flagmen and, where

necessary, communications equipment to regulate traffic; for the construction of temporary drainage works; for the maintenance of drainage works; and for arrangements for moving and subsequently reinstating services for the purposes of accommodating traffic, attending to traffic problems and complying with the requirements of the Road Traffic Ordinance and the relevant local authorities.

The tendered lump sum shall not be adjusted in the event of any extension of time for completion being granted by the Engineer in accordance with Clause 45 of the Conditions of Contract.

Payment shall be made in equal monthly installments over the entire period allowed for completion, provided that where any extension of time for completion is granted, the amount which shall be payable under this item in any subsequent monthly payment certificate shall be the outstanding unpaid amount of the lump sum, divided by the number of months remaining until the due completion date of the Contract, as revised in accordance with the Conditions of Contract."

PSL MEDIUM-PRESSURE PIPELINES

PSL 3 MATERIAL

PSL 3.7 OTHER TYPES OF PIPES

PSL 3.7.1 uPVC pipes

ADD THE FOLLOWING:

"Pipes and couplings should conform to SANS."

PSL 3.7.2 Polyethylene pipes

"Polyethylene pipes compression fittings shall be as shown the Tender drawings and shall comply with SABS 533 Part II."

"Valves shall comply with the following requirements:

- (a) They shall open/close clockwise and shall have a non-rising spindle and handwheel.
- (b) They shall be class 16 valves complying with SABS 664.
- (c) They shall comply with the requirements of SABS 1123 table 1600.

PSL 7 TESTING

PSL 7.3 STANDARD HYDRAULIC PIPE TEST

PSL 7.3.1 Test pressure and time of test

PSL 7.3.1.2 The maximum working pressure for the different pipes is indicated by the class of the pipe.

PSL 8 MEASUREMENT AND PAYMENT

PSL 8.2 SCHEDULED ITEMS

PSL 8.2.18 Connection to existing main supply

The rate shall include all the installation of any coupling required by the connection and approval thereof by the relevant Authority.

PSLB BEDDING (PIPES)

PSLB 3 MATERIALS

PSLB 3.1 SELECTED GRANULAR MATERIAL:

"Selected granular material shall have a PI not exceeding 6 and shall be free from sharp-edged particles exceeding 19 mm."

PSLB 3.2 SELECTED FILL MATERIAL

"Selected fill material used for bedding shall be stabilized with 5% cement as specified under subclause PSDB 3.5(c)."

PSLB 3.3 BEDDING

"uPVC and HDPE pipes are deemed to be flexible pipes for the purposes of this subclause."

PSLB 3.4 SELECTION

PSLB 3.4.1 Suitable material available from trench excavation

REPLACE THE WORDS "(but is not required)" IN THE FIFTH LINE WITH THE WORDS "(at his own cost)".

PSME 5 CONSTRUCTION

PSME 8 MEASUREMENT AND PAYMENT

PSME 8.1 BASIC PRINCIPLES

"(d) that, in the case of material from a commercial source or from borrow pits selected by the Contractor, no additional payment will be made for the class of excavation, method of processing (except stabilizing), or overhaul."

PSME 8.3 SCHEDULED ITEMS

PSME 8.3.2 Construct the subbase course/shoulders/gravel wearing course with material from designated excavations

"The rate for (a) shall include full compensation for excavating and selecting subbase material, for loading and transporting the material within the free-haul distance, and for either placing the material on the road or stockpiling the material for later use. When material is stockpiled, the rate shall include compensation for shaping and grading the stockpile so that it is free-draining."

PSME 8.3.3 Construct the subbase course/shoulders/gravel wearing course with material from commercial sources or designated borrow areas

"PSME 8.3.3 Construct the subbase course/shoulders/gravel wearing course with material from commercial sources"

"This item shall also apply to the construction of subbase course/shoulders/gravel wearing course with material from borrow pits selected by the Contractor."

PSME 8.3.9 Overhaul (haul exceeding 2 km):

- "(a) Limited overhaulUnit: m³
- (b) Long overhaul Unit: m³-km

Overhaul will be paid in accordance with item 8.3.6 of SABS 1200 D."

C 3.6 HIV/AIDS REQUIREMENT

C3.6 HIV/AIDS REQUIREMENTS

C3.6.1 SCOPE

This specification contains all requirements applicable to the Contractor for creating HIV/AIDS awareness amongst all of the Workers involved in this project for the duration of the construction period, through the following strategies:

- Raising awareness about HIV/AIDS through education and information on the nature
 of the disease, how it is transmitted, safe sexual behaviour, attitudes towards people
 affected and people living with HIV/AIDS, how to live a healthy lifestyle with HIV/AIDS,
 the importance of voluntary testing and counselling, the diagnosis and treatment of
 Sexually Transmitted Infections and the closest health Service Providers
- Informing Workers of their rights with regard to HIV/AIDS in the workplace
- Providing Workers with access to condoms and other awareness material that will enable them to make informed decisions about sexual practices

C3.6.2 DEFINITIONS AND ABBREVIATIONS

C3.6.2.1 Definitions

Service Provider: The natural or juristic person recognised and approved by the

Tswelopele Local Municipality as a specialist in conducting

HIV/AIDS awareness programmes.

Service Provider Workshop Plan: A plan outlining the content, process and

schedule of the training and education workshops, presented by a Service Provider which has been approved by the

Representative/Agent.

Worker: Person in the employ of the Contractor or under the direction or

supervision of the Contractor or any of his Sub-contractors, who

is on site for a minimum period of 30 days in all.

C3.6.2.2 Abbreviations

HIV : Human Immunodeficiency Virus

AIDS : Acquired Immune Deficiency Syndrome

STI : Sexually Transmitted Infection

C3.6.3 BASIC METHOD REQUIREMENT

The Contractor shall, through a Service Provider, conduct onsite workshops with the Workers.

The Service Provider shall develop and compile a Service Provider Workshop Plan to be presented at the workshops and which will be best suited for this project to achieve the specified objectives with regard to HIV/AIDS awareness.

The Service Provider Workshop Plan shall be based on the following information provided by the Contractor:

- Number of Workers and Sub-contractors on site
- When new Workers or Sub-contractors will join the construction project
- Duration of Workers and Sub-contractors on site
- How the maximum number of Workers can be targeted with workshops
- How the Contractor prefers workshops to be scheduled, e.g. three hourly sessions per Worker, or one 2.5 hour workshop per Worker
- Profile of Workers, including educational level, age and gender (if available)
- Preferred time of day or month to conduct workshops
- A Gantt chart reflecting the construction programme, for scheduling of workshops
- Suitable venues for workshops The Contractor shall submit the Service Provider Workshop
 Plan for approval within 21 days after the tender acceptance date. After approval by the
 Tswelopele Local Municipality Representative/Agent, the Contractor shall make available a
 suitable venue that will be conducive to education and training.

The Service Provider Workshop Plan shall address, but will not be limited to the following:

- 3.1 The nature of the disease;
- 3.2 How it is transmitted;
- 3.3 Safe sexual behaviour;
- 3.4 Post exposure services such as voluntary counselling and testing (VCT) and nutritional plans for people living with HIV/AIDS;
- 3.5 Attitudes towards other people with HIV/AIDS;
- 3.6 Rights of the Worker in the workplace;
- 3.7 How the Awareness Champion will be equipped prior to commencement of the HIV/AIDS awareness programme with basic HIV/AIDS information and the necessary skills to handle questions regarding the HIV/AIDS awareness programme on site sensitively and confidentially;
- 3.8 How the Service Provider will support the Awareness Champion;
- 3.9 Location and contact numbers of the closest clinics, VCT facilities, counselling services and referral systems;
- 3.10 How the workshops will be presented, including frequency and duration;
- 3.11 How the workshops will fit in with the construction programme;
- 3.12 How the Service Provider will assess the knowledge and attitude levels of attendees to structure workshops accordingly;
- 3.13 How the video will be used;

- 3.14 How the Service Provider will elicit maximum participation from the Workers;
- 3.15 A questions and answers slot (interactive session)

The Service Provider Workshop Plan shall encompass the Specific Learning Outcomes (SLO) as stipulated.

C3.6.4 HIV/ AIDS AWARENESS EDUCATION AND TRAINING

4.1 Workshops

The Contractor shall ensure that all Workers attend the workshops.

The workshops shall adequately deal with all the aspects contained in the Service Provider Workshop Plan. A video of HIV/AIDS in the construction industry, which can be obtained from all Offices of the Tswelopele Local Municipality, is to be screened to Workers at workshops. In order to enhance the learning experience, groups of not exceeding 25 people shall attend the interactive sessions of the workshops.

4.2 Recommended practice

4.2.1 Workshop Schedule

Presenting information contained in the Service Provider Workshop Plan can be divided in as many workshop sessions as deemed practicable by the Contractor, provided that all Workers are exposed to all aspects of the workshops as outlined in the Service Provider Workshop Plan. Breaking down the content of information to be presented to Workers into more than one workshop session however, has the added advantage that messages are reinforced over time while providing opportunity between workshop sessions for Workers to reflect and test information. Workers will also have an opportunity to ask questions at a following session.

4.2.2 Service Providers

A database of recommended Service Providers is available from all Offices of the Tswelopele Local Municipality.

4.2.3 <u>HIV/AIDS Specific Learning Outcomes and Assessment Criteria</u>

Workers shall be exposed to workshops for a minimum duration of two-and-a-half hours. In order to set a minimum standard requirement, the following specific learning outcomes and assessment criteria shall be met

4.2.3.1 UNIT 1: The nature of HIV/AIDS

After studying and understanding this unit, the Worker will be able to differentiate between HIV and AIDS and comprehend whether or not it is curable. The Worker will also be able to explain how the HI virus operates once a person is infected and identify the symptoms associated with the progression of HIV/AIDS.

Assessment Criteria:

- Define and describe HIV and AIDS
- List and describe the progression of HIV/AIDS

4.2.3.2 UNIT 2: Transmission of the HI virus

After studying and understanding this unit, the Worker will be able to identify bodily fluids that carry the HI virus. The Worker will be able to recognise how HIV/AIDS is transmitted and how it is not transmitted.

Assessment Criteria:

- Record in what bodily fluids the HI virus can be found
- 2. Describe how HIV/AIDS can be transmitted
- Demonstrate the ability to distinguish between how HIV/AIDS transmitted and misconceptions around transmittance of HIV/AIDS

4.2.3.3 <u>UNIT 3: HIV/AIDS preventative measures</u>

After studying and understanding this unit, the Worker will comprehend how to act in a way that would minimise the risk of HIV/AIDS infection and to use measures to prevent the HIV virus from entering the bloodstream.

Assessment Criteria:

- 1. Report on how to minimise the risk of HIV/AIDS infection
- 2. Report on precautions that can be taken to prevent HIV/AIDS infection
- 3. Explain or demonstrate how to use a male and female condom.
- 4. List the factors that could jeopardize the safety of condoms provided against HIV/AIDS transmission

4.2.3.4 UNIT 4: Voluntary HIV/AIDS counselling and testing

After studying and understanding this unit, the Worker will be able to recognise methods of testing for HIV/AIDS infection. The Worker will be able to understand the purpose of voluntary HIV/AIDS testing and pre- and post-test counselling.

Assessment Criteria:

- 1. Describe methods of testing for HIV/AIDS infection
- 2. Report on why voluntary testing is important
- 3. Report on why pre- and post-test counselling is important

4.2.3.5 UNIT 5: Living with HIV/AIDS

After studying and understanding this unit, the Worker will be able to recognise the importance of caring for people living with HIV/AIDS and be able to manage HIV/AIDS.

Assessment Criteria:

- 1. List and describe ways to manage HIV/AIDS
- 2. Describe nutritional needs of people living with HIV/AIDS
- 3. Describe ways to embrace a healthy lifestyle as a person living with HIV/AID
- 4. Explain the need for counselling and support to people living with HIV/AIDS

4.2.3.6 UNIT 6: Treatment options for people with HIV/AIDS

After studying and understanding this unit, the Worker will be familiar with the various treatments available to HIV/AIDS infected or potentially HIV/AIDS infected people.

Assessment Criteria:

- Discuss anti-retroviral therapy
- List methods of treatment to prevent HIV/AIDS transmission from mother-tochild
- Describe the need for treatment of opportunistic diseases for people living with HIV/AIDS
- 4. Describe post exposure prophylactics.

4.3 Displaying of plastic laminated posters and distribution of information booklets

The Contractor shall obtain a set of four laminated posters conveying different key messages and information booklets, which are available from Offices of the Tswelopele Local Municipality.

The above-mentioned posters and information booklets have been prepared to raise awareness and to share information about HIV/AIDS and STI's.

Posters or display stands shall be displayed on site as soon as possible, but not later than 14 days after the date of site handover.

Posters shall be displayed in areas highly trafficked by Workers, including toilets, rest areas, the site office and compounds.

The posters on display must always be intact, clear and readable.

Information booklets must be distributed to all Workers as soon as possible, but not later than 14 days after site handover, or as soon as the Worker joins the site.

5. PROVIDING WORKERS WITH ACCESS TO CONDOMS

The Contractor shall provide and maintain condom dispensers and make both male and female condoms, complying with the requirements of SABS ISO 4074, available at all times to all Workers at readily accessible points on site, for the duration of the contract. The Contractor may obtain condom dispensers from the Department of Health and condoms may be obtained from the Local Clinic or the Department of Health.

At least one male and one female condom dispenser and a sufficient supply of condoms, all to the approval of the Representative/Agent, shall be made available on site within 14 days of site hand over. Contractors should note that arrangements to obtain condoms from the Department of Health Clinics prior to site hand over may be necessary, to ensure that condoms are available within 14 days of site handover.

Condoms shall be made available in areas highly trafficked by Workers, including toilets, the site office and compounds.

C3.6.5 ENSURING ACCESS TO HIV/AIDS TESTING AND COUNSELLING FACILITIES AND TREATMENT OF SEXUALLY TRANSMITTED INFECTIONS (STI)

The Contractor shall provide Workers with the names of the closest Service Providers that provide HIV/AIDS testing and counselling and Clinics providing Sexually Transmitted Infection (STI) diagnosis and treatment. Information on these Service Providers and Clinics must be displayed on a poster of a size not smaller than A1 in an area highly trafficked by Workers.

C3.6.6 APPOINTMENT OF AN HIV/AIDS AWARENESS CHAMPION

Within 14 days of site handover the Contractor shall appoint an Awareness Champion from amongst the Workers, who speaks, reads and writes English, who speaks and understands all the local languages spoken by the Workers and who shall be on site during all stages of the instruction period.

The Contractor shall ensure that the Awareness Champion has been trained by the Service Provider on basic HIV/AIDS information, the support services available and the necessary skills to handle questions regarding the HIV/AIDS programme in a sensitive and confidential manner.

The Awareness Champion shall be responsible for:

7.1 Liaising with the Service Provider on organizing awareness workshops;

RETROFITTING OF 6 sewer pump stations, INSTALLATION OF INLINE GRINDERS AND REPAIRS TO WASTE WATER TREATMENT PLANT IN HOOPSTAD AND TIKWANA

SCOPE OF WORK

- 7.2 Filling condom dispensers and monitoring condom distribution;
- 7.3 Handing out information booklets;
- 7.4 Placing and maintaining posters

C3.6.7 MONITORING

The Contractor shall grant to the Representative/Agent reasonable access to the construction site, in order to establish that the Contractor complies with his obligations regarding HIV/AIDS awareness under this contract.

The Contractor must report problems experienced in implementing the HIV/AIDS requirements to the Representative/Agent.

C 3.7 OCCUPATION HEALTH AND SAFETY

C3.7 OCCUPATIONAL HEALTH AND SAFETY

C3.7.1 GENERAL

C3.7.1.1 Tender Document

This document is the pre-contract Health and Safety Specification which must be used by the Principal Contractor and Sub Contractors appointed by the Principal Contractor to compile Health and Safety Plans for this project and forms part of the tender documentation.

The Principal Contractor and Sub Contractors' particular attention is drawn to this specification whereby

"Upon award of the contract, the contractor is to assume and adopt the function and duties of the Principal Contractor as set out in the Construction Regulations 2003 No. R. 1010 promulgated 18 July 2003."

The health and safety specifications outlined herein must be taken into account and due allowance made within the pricing of appropriate items contained within the specification. Where the tenderer is of the opinion that a requirement is missing or is not adequately specified then this shall be drawn to the Client attention during the tender period. In the absence of any direction to the contrary, the tenderer shall as part of the tender submission, set out the details of such discrepancy together with the costs associated therewith, separately identified and included within the tender figure.

C3.7.1.2 Principal Contractor

The successful tenderer will on signing of the contract for:

Project Name: RETROFITTING OF 6 sewer pump stations, INSTALLATION OF INLINE GRINDERS AND REPAIRS TO WASTE WATER TREATMENT PLANT IN HOOPSTAD AND TIKWANA

be required to fulfil the function and duties of the Principal Contractor as set out in the Construction Regulations 2003 No. R.1010 promulgated 18 July 2003.

C3.7.1.3 Start of Construction Phase

The construction phase shall not commence until the Principal Contractor's Health and Safety Plan was considered and approved by the Client and Design Team. The Client shall discuss and negotiate with the Principal Contractor the contents of the Health and Safety Plan submitted by the Principal Contractor before finally approving it for implementation.

The construction phase shall not commence until written permission is received from the Client. In this respect the Client may rely on the advice of the Technical Team as to the adequacy and comprehensiveness of the Plan offered by the Principal Contractor.

In preparing their detailed Health and Safety Plan based on the relevant sections of this Health and safety Specifications supplied to them by the Client, contractors must allow for the adoption of safe working procedures and co-ordinate and rationalize activities to avoid controllable hazards arising due to clashes of activities.

C3.7.2 SUB-CONTRACTORS, SUPPLIERS & DESIGNERS

The Principal Contractor shall ensure that all direct appointments in connection with this project include provisions for the compliance of his sub-contractors, suppliers and designers, etc., with the relevant provision of the Occupational Health and Safety Act (Act 85 of 1993) and it's Regulations, in particular the Construction Regulations 2003 No. R. 1010 promulgated 18 July 2003.

C3.7.2.1 liaison

The Principal Contractor shall together with all his appointees, liaison with the Client as required under the Regulations and agrees procedures for the transfer of relevant Information in respect of designs and in connection with the preparation of the Health and Safety File.

C3.7.2.2 Advice

The tenderer shall, as part of the tender submission, indicate where advice will or may be required of the Client in respect of the competence of the tenderer's designers and the adequacy of resources allocated or to be allocated by them.

C3.7.2.3 Undertaking by Principal Contractor and Sub-Contractors appointed by the Principal Contractor.

The Principal Contractor as well as Sub-Contractors appointed by him / her shall undertake in writing to ensure that the provisions of the Occupational Health and Safety Act (Act 85 of 1993) and it's Regulations, in particular the Construction Regulation of 2003 No. R 1010 and any amendments or reenactments thereto are complied with.

The attached Occupational Health and Safety provisions undertaking form for the Principal Contractor shall be completed and signed by the Project Manager of the company / firm awarded the tender.

Client's Occupational Health and Safety Agent: To be appointed

C3.7.3 INFORMATION REQUIREMENTS

The contractor must provide the following information.

C3.7.3.1 General

- The Principal Contractor / Sub-Contractor shall have an OHS Policy in accordance with the OHS(Occupational Health and Safety Act, Act 85 of 1993) and include a copy of the Policy in the Health and Safety Plan to be submitted by the Principal Contractor / Sub-Contractor.
- The Principal Contractor / Sub-Contractor shall promptly display a copy of the Company's OHS
 Policy on the OHS Notice Board for the duration of the contract and include it into information
 provided to persons at the contract OHS induction.
- The Principal Contractor shall develop a Contract specific OHS Management Commitment Statement based on the Company's OHS Policy.
- The Principal Contractor's Project Managing shall sign the Commitment statement and prominently display a copy on the OHS Notice Board for the duration of the contract. A copy of the Commitment Statement shall be included in information provided to persons at the Contract OHS induction and a copy shall also be supplied to each sub-contractor.

C3.7.3.2 Management

 Details of the personnel and management systems to be put in place to prepare, manage, implement, conduct and monitor the Health and Safety Plan for the project.

Broadly speaking your:

Organization's internal structure that establishes SHE (Safety, Health and Environmental) ROLES, RESPONSIBILITIES, ACCOUNTABILITIES, and REPORTING RELATIONSHIPS,

- SHE (Safety, Health and Environmental) PLANS, POLICIES, PROCEDURES, DIRECTIVES and STANDARDS that provide instructions as to how activities and functions are to be carried out.
- SHE (Safety, Health and Environmental) CONTROLS, INSPECTIONS, REVIEWS, etc. built
 into construction operations to ensure that performance is consistent with SHE (Safety, Health
 and Environmental) objectives and requirements,
- SHE (Safety, Health and Environmental) COMMUNICATION MECHANISMS for collecting, handling and reporting information.
 - In other words Management Systems that specifies WHO is going to do WHAT, WHERE, WHEN, WHY and HOW.
- Details of relevant qualifications and experience held by the persons nominated above, including recent health and safety education and training undertaken.
- Procedures for determining the competence of contractors engaged on the project, whether employed by the contractor directly or by others, to fulfil their duties under the Construction Regulations 2003 (No. R.1010 Promulgated 18 July 2003)

C3.7.3.3 HAZARD IDENTIFICATION, RISK MANAGEMENT AND CONTROL

- The Principal Contractor / Sub-Contractor shall detail and implement procedures that will identify hazards, assess risks and determine suitable control measures as they arise throughout term of the contract. These procedures shall both comply with and be implemented and managed in accordance with the specification.
- The Principal Contractor / Sub-Contractor shall detail and implement procedures that ensure control measures are evaluated for effectiveness and modified as necessary. The evaluation procedure shall detail the responsibilities, timelines and records that will be kept as part of the process.
- Where Risk is controlled through administrative control measures, the Principal Contractor / Sub-Contractor shall ensure that the administrative measures are:
- Clearly documented and those personnel responsible for implementation and management are explicitly defined;
- b) Understood by all relevant personnel through training and assessment;
- Implemented as documented and promptly reviewed for effectiveness following initial implementation;
- d) Amended and authorised as required;
- e) Adequately supervised, managed and audited to ensure continuing compliance;
- f) Available at all times wherever the measures are being implemented.
- Any piece of plant or equipment not complying with the specification shall cease operation until the Principal Contractor / Sub-Contractor can demonstrate to the satisfaction of the Client / Client's Agent that the piece of non-conforming plant or equipment conforms to these requirements.

C3.7.3.4 Health and Safety Plan

The Principal Contractor / Sub-Contractor shall develop a Health & Safety Plan to reflect variations in design or changes in site conditions and liaise with the Client / Client's Agent.

The Principal Contractor shall develop this Health and Safety Plan so that it:

- a) Incorporates the contractor's approach to managing the construction work to ensure the health and safety of all persons carrying out the construction work and all persons who may be affected by their work.
- b) Includes the risk assessments prepared by all Contractors under their duties set out in the Construction Regulations 2003 and any other relevant legislation (i.e. the OHS Act and Regulations, etc.).
- c) Includes the arrangements for ensuring that, where appropriate or specifically requested, all Contractors / Sub-Contractors prepare suitable and sufficient method statements for their construction works which incorporate adequate measures for ensuring the health and safety of all persons who may be affected by these works.
- d) Incorporates the common arrangements for site safety, statutory notices and registers etc.
- e) Includes the site rules to be adopted for controlling the risks to health and safety during the construction phase(s) or the project.
- f) Includes reasonable arrangements for monitoring compliance with health and safety legislation and site rules.
- g) Includes reasonable measures to ensure co-operation between all Contractors and Sub-Contractors in respect of health and safety provisions and prohibitions.
- h) Includes the steps to be taken to ensure that only authorised persons are allowed into any premises or parts of the site / premises where construction work is being carried out.
- Includes arrangements for emergency procedures.
- j) Includes arrangements for ensuring that, so far as is reasonably practicable, every Contractor and Sub-Contractor is provided with comprehensible information about the risks to health and safety of that Contractor / Sub-Contractor, or of any employees or other persons under their control, arising out of the construction works, including the emergency procedures
- k) Includes details of the arrangements for ensuring, so far as is reasonably practicable, that the employees or other persons under the control of any Contractor / Sub-Contractor, and any visitors to the site, receive adequate information about the risks to their health and safety arising out of the construction works and, where necessary, adequate training to carry out their work in a safe and healthy manner.
- Includes arrangements for providing all persons at work on the site and visitors to the site with the opportunity and means of discussing and offering advice on health and safety issues relating to the construction works.
- m) Includes arrangements for the reporting of any accidents, injuries or dangerous occurrences, including conforming to the statutory requirements.
- n) Can be modified as the work proceeds to take account of any information received from Contactors / Sub-Contractors, any experience gained during the course of the project or any changes necessary as a result of unforeseen circumstances or alterations to the design.

C3.7.3.5 PROGRAMME

A time estimate required by the contractor to implement the Health & Safety Plan sufficiently for works to commence on site.

C3.7.3.6 Cost

A detailed breakdown of costs allowed in the contractor's tender for preparing, managing, implementing and monitoring the Health and Safety Plan, and for complying with the requirements imposed on the Principal Contractors under the Construction Regulations of 2003(No. R. 1010 Promulgated 18 July 2003).

C3.7.4 GENERAL SITE SAFETY

C3.7.4.1 Safety training & education

The Principal Contractor shall detail the OHS competencies and training received by its contract management personnel.

The Principal Contractor's Health and Safety Plan shall have a detailed register of the skills and competencies for all personnel for the activities that the personnel will undertake under the contract. (e.g. Mobile plant operators, crane operators etc.)

The Principal Contractor shall demonstrate and maintain documentary evidence of competencies on site for the duration of the contract.

C3.7.4.2 Induction Training

The Principal Contractor / Sub-Contractor shall develop and detail a Site Induction Training Programme as part of the Occupational Health and Safety Plan to be submitted to the Client prior to commencement of construction that includes as a minimum:

- a) Training related to hazards likely to be encountered on Site and control measures that have been developed in response to these hazards;
- b) Roles and Responsibilities;
- c) The requirements of the Health and Safety Plan submitted and approved
- Address the identified issues in the Fire Safety, Emergency, Evacuation and Rescue Plan to ensure that all Site personnel are aware of procedures in the event of an incident or emergency occurring;

The Principal Contractor / Sub-Contractor shall evaluate all persons undertaking the site Induction Training through a written test to ensure that inductees have an understanding of the OHS (Occupational Health and Safety) requirements for the contract. The written tests shall be signed and dated by the person undertaking the induction training to attest to their understanding and be retained by the Principal Contractor / Sub-Contractor as a record that the training has been completed.

C3.7.4.3 Induction training for specified work

The Principal Contractor / Sub-Contractor shall conduct Site Specific Occupational Health and Safety Induction Training for all personnel, the Client and all visitors not escorted on Site by inducted persons.

The Principal Contractor / Sub-Contractor shall evaluate all persons undertaking the Site Induction Training through a written test to ensure that inductees have an understanding of the OHS (Occupational Health and Safety) requirements for the contract. The written tests shall be signed and dated by the person undertaking the induction training to attest to their understanding and be retained by the Principal Contractor / Sub-Contractor as a record that the training has been completed.

C3.7.4.4 Recording & reporting of injuries

Make arrangements for all contractors to report accidents, ill health and dangerous occurrences notifiable to the Department of Labour under Section 24 of the OHS Act (Occupational Health and Safety Act, Act 85 of 1993) (Reporting to DOL (Department of Labour) Inspector regarding certain incidents).

All lost time incidents associated with the contract works or reportable as defined by **Section 24** of the OHS Act shall be immediately reported to the Client.

The Principal Contractor / Sub-Contractor shall provide a detailed report of all accidents / incidents, including events that could have become lost time incidents were it not for fortuitous circumstances to the Client within 5 days of the incident occurring. The Principal Contractor / Sub-Contractor shall provide copies of all reports and information associated with the incidents to the Client. Copies of reports must be placed on the Health and Safety File.

Where the Principal Contractor / Sub-Contractor has been:

- Served with a prohibition, contravention or improvement notice under the OHS Act; or
- Required to comply with any order issued by an inspector for the Department of Labour;
 - The Principal Contractor / Sub-Contractor shall immediately supply a copy of that notice, order or notification to the Client.
 - Where the Principal Contractor / Sub-Contractor have been served with a summons or is convicted of any offence in relation to occupational health and safety, the Principal Contractor / Sub Contractor shall immediately supply a copy of that summons to the Client.
 - The Principal Contractor / Sub-Contractor shall detail the reporting and investigation procedures for incident investigation. The procedures shall include the investigating officer responsible and the time limits imposed for reporting and investigating the incident and to implement corrective action in a timely manner so as to prevent a recurrence.
 - The client may participate in or undertake an investigation into the incident, injury or illness at its discretion and the Principal Contractor / Sub-Contractor shall cooperate with and provide assistance to the investigation organized and undertaken by the Client.

C3.7.4.5 First Aid

 Establish and implement a first-aid programme to provide emergency treatment to victims of accidents, chemical substances or excessive exposure to toxic substances.

The programme shall include:

- proper first aid facilities administered by qualified personnel,
- first-aid boxes,
- first-aid room, where there are 500 or more workers on site,
- training and re-training of first-aiders,
- first-aid treatment procedures,
- standard procedures,
- special procedures, e.g. for poisoning,
- maintenance of first-aid facilities
- All first-aid provisions shall comply with the OHS Act (Act 85 of 1993)

C3.7.4.6 Fire protection and prevention

- Appropriate measures must be taken to avoid the risk of fire.
- Sufficient and suitable storage must be provided for flammable liquids, solids and gases.

- Smoking must be prohibited and notices in this regard must be prominently displayed in all places containing readily combustible or flammable materials;
- Combustible materials must not accumulate on the construction site.
- Welding, flame cutting and other hot work may only be done after the appropriate precautions have been taken to reduce the risk of fire.
- Suitable and sufficient fire-extinguishing equipment must be placed at strategic locations and such equipment must be maintained in good working order.
- A sufficient number of workers must be trained in the use of fire-extinguishing equipment.

C3.7.4.7 Site Emergency Procedures

The Principal Contractor / Sub-Contractor shall establish an Emergency Evacuation and Rescue plan.

The plan shall include the following detail:

- The role and responsibility of every individual in the work area on fire safety emergency evacuation and rescue:
- General work area precautions, fire prevention, detection, protection and warning alarm systems;
- Firefighting and rescue equipment including types of fire extinguishers:
- Fire safety measures for Site accommodation;
- Escape and communication;
- Fire brigade access, facilities and coordination;
- Fire drills and training including the use of fire-fighting equipment;
- · Material storage including flammable liquids, gasses and waste;

The Principal Contractor / Sub-Contractor shall ensure that all procedures, precautionary measures and safety standards stipulated in the Plan are communicated, implemented and complied with by all workers including other interfacing contractors on Site.

The Principal Contractor / Sub-Contractor shall practice their emergency preparedness within six (6) weeks of the commencement of work and at least four (4) monthly intervals thereafter.

The Principal Contractor / Sub-Contractor shall review and ensure the adequacy of the Plan as the work progress.

The Principal Contractor / Sub-Contractor shall conduct monthly checks on fire-fighting equipment and test alarms and detection devices installed on Site and document findings in a register which shall be on site at all times for inspection.

The Principal Contractor / Sub-Contractor shall conduct weekly inspections of escape routes, fire brigade access, fire-fighting facilities and working areas to ensure that the requirements stipulated in the Fire Safety, Emergency, Evacuation and Rescue Plan are complied with. All inspection records shall be documented in registers and kept in the Health and Safety file for inspection at any time.

C3.7.4.8 Housekeeping

Suitable housekeeping must continuously be implemented on the construction site, including:

- · proper storage of materials and equipment
- removal of scrap, waste and debris at appropriate intervals;

Loose materials shall not be placed or allowed to accumulate on the site so as to obstruct access and egress from workplaces and passageways.

C3.7.4.9 Stacking & Storage

- · Adequate storage areas are must be provided.
- Storage areas must be kept neat and under control.

C3.7.4.10 Illumination

Provide adequate artificial lighting when work is carried out after dark or inside buildings.

C3.7.4.11 Sanitation / Hygiene

Provision of site hygiene facilities:

- One sanitary facility for every 30 workers.
- · Adequate washing facilities.
- One shower facility for every 15 workers;

Drying sheds, huts, rooms or other accommodation for sheltering during bad weather, storing clothes and taking meals. Facilities should include tables and chairs, suitable means for boiling water and a supply of wholesome drinking water.

The contractor shall provide reasonable and suitable living accommodation for the workers at construction sites which are remote from their homes and where adequate transportation between the site and their homes, or other suitable living accommodation, is not available.

C3.7.4.12 Personal Protective Equipment

The Principal Contractor / Sub-Contractor shall provide and maintain suitable PPE (Personal Protective Equipment) for all employees employed on the Site.

The Principal Contractor / Sub-Contractor shall ensure that such PPE comply with the requirements of the OHS Act (Occupational Health and Safety Act, Act 85 of 1993).

The Principal Contractor / Sub-Contractor shall also ensure that all equipment is properly used by his / her employees during the course of their work.

The Principal Contractor / Sub-Contractor shall record all issues of all equipment to his / her employees in documented registers and such registers shall be kept in the Health and Safety File on site and made available for inspection at all times.

The Principal Contractor / Sub-Contractor shall provide the Client / Client's Agent with a colour code by which employees will be identified with regard to occupations, responsibilities, accountabilities, reporting relationships and access to different locations on site. (e.g. hard hats, overalls).

PPE shall be provided, used, and maintained in a sanitary and reliable condition wherever it is necessary by reason of hazards.

All personal protective equipment shall be of safe design and construction for the work to be performed.

C3.7.4.13 Permit to Work Requirements

Institute a "hot work" permit system in respect of:

- · metalwork flame cutting,
- site welding,

C3.7.4.14 Lock-Out

Institute a "Lock-out" procedure in respect of controlling energy so as to prevent unexpected operation or activation of machinery or equipment. This procedure must include a written policy, specific procedures, rules and supervisory follow-up, covering the positive locking of switches and valves to ensure that alterations, maintenance, set-up and or other work can be performed safely.

C3.7.4.15 Monthly Health and Safety Audits

The Principal Contractor shall carry out monthly Health and Safety Audits on the measures contained within his / her Health and Safety Plan submitted to the Client as well as Health and Safety Plans submitted by Sub-Contractors appointed by the Principal Contractor to demonstrate that the required level of health and safety are being achieved and maintained and compile a full report to the Client on such audit.

The Client will audit the Principal Contractor as well as his / her Sub-contractor's Health and Safety Plans from time to time and will advise the Principal Contractor of any matter with which he / she is not satisfied and the Principal Contractor shall take such steps as are necessary to satisfy the Client.

The Client will carry out such audits as he / she considers necessary but not less than monthly.

The Principal Contractor shall make available, specialist personnel as the Client may consider necessary for the performance of such audits.

The Principal Contractor shall develop and maintain an Audit Schedule that details the audits planned to be undertaken by the Principal Contractor of the work under the contract, including sub-contractors, for the duration of the contract. The Audit Schedule shall form part of the Health and Safety Plan that needs to be submitted by the Principal Contractor.

Audit reports shall detail the scope of the audit, the audit questions and the audit findings.

The Client shall be promptly provided with copies of all audit reports together with other documentation to show that all matters raised have been appropriately addressed.

Unless otherwise directed by the Client the Principal Contractor / Sub-Contractor shall undertake its initial OHS Audit within 4 weeks of commencement of work. The Principal Contractor / Sub-Contractor shall undertake subsequent OHS Audits at a frequency not less than once every 3 months.

All Principal Contractor's OHS Audits shall include an assessment of Sub-Contractor compliance with the approved OHS Plan.

C3.7.4.16 Management Review


The Principal Contractor shall undertake an independent review of the Health and Safety Plan for the contract in accordance with the requirements of the OHS Act, relevant Regulations and in particular the Construction Regulations 2003.


A review shall be undertaken 3 months after commencement of the contract and every 6 months thereafter for the duration of the contract.

Following the completion of the review, the Principal Contractor shall submit a written report that details the suitability, adequacy and effectiveness of the OHS Plan and to certify that the Site procedures, practices and operations are in accordance with the contract.


C3.7.4.17 Provision of Information


• Provide Sub-Contractors appointed by him / her with the relevant sections of the Health and Safety specifications pertaining to the construction work which has to be performed.





TYPICAL PALISADE SCALE 1: 25





PALISADE SLIDING GATE SCALE 1: 25

CLIENT	MUTEO CONSULTING
	M

39 GROBLER STREET
POLOKWANE 0699
P.O. BOX 6196
POLOKWANE NORTH
0750
TEL: (015) 291 4065
FAX: (015) 291 4043
website: www.muteo.co.za

CHECKED 10 OCT 2025 N.M DO NOT SCALE IF IN DOUBT ASK. DRAWN 10 OCT 2025 S.D PROJECT MNG. APPROVED FWPQ 27 OF 2022-2026							
CHECKED 10 OCT 2025 N.M DRAWN 10 OCT 2025 S.D PROJECT MNG. APPROVED DO NOT SCALE IF IN DOUBT ASK. PROJECT No. FWPQ 27 OF 2022-2026	PROJECT APPR.	DATE	BY	SIGNATURE	SCAI	LE	
DRAWN 10 OCT 2025 N.M IF IN DOUBT ASK. PROJECT MNG. PROJECT No. APPROVED FWPQ 27 OF 2022-2026	DESIGNED	10 OCT 2025	S.D				TI
DRAWN 10 OCT 2025 S.D PROJECT MNG. APPROVED PROJECT No. FWPQ 27 OF 2022-2026 DRC SIZE	CHECKED	10 OCT 2025	N.M				
APPROVED FWPQ 27 OF 2022-2026	DRAWN	10 OCT 2025	S.D		n nvboc	Bi iisik.	
DDC SIZE DI	PROJECT MNG.				PROJECT	Γ No.	
	APPROVED				FWPQ 27 OF	2022-2026	
	CLIENT				DRG SIZE	A1	DR

ISSUED FOR TENDER

LL DIMENSION IN mm UNLESS SPECIFIED OTHERWISE	
RETROFITTING OF 7 SEWER PUMP STATIONS,	
INSTALLATION OF INLINE GRINDERS AND REPAIRS T	C
WWTW PLANT IN HOOPSTAD AND TIKWANA	

FENCING DETAILS

FWPQ 27 OF 20222-26/CIVIL/FENCE/01


REV	DATE	СНК	APP	1
10.	Ditte	CITIC	7111	


DESCRIPTION


NOTES:

CONTRACTOR TO PROVIDE FINAL FABRICATION


DRAWING FOR APPROVAL BY ENGINEER.










SECTION BB











CALCAMITE STEP IRON SPACING











NOTES:

1. ALL STRUCTURAL CONCRETE 25/19 MPa.

3. COVER TO REINFORCEMENT 40mm.

2. PROVIDE 20×20 CHAMFERS ON ALL EXPOSED EDGES.

4. A MINIMUM CLEAR DISTANCE OF 50mm IS

REQUIRED BETWEEN PUDDLE FLANGE AND REINFORCING STEEL.

AROUND STEEL PIPE AT CONCRETE OR BRICK INTERFACES EXCEPT PUDDLE PIPES.

6. REFER DRAWING 2099-005-C-02-WMC REINF FOR REINFORCEMENT DETAILS.

5. WRAP 2 LAYERS THREE PLY MALTHOID

WATERPROOFING DETAIL

ALL PRODUCTS APPLIED IN ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS

ISSUED FOR TENDER

REV	DATE	СНК	APP	DESCRIPTION	





MUTEO CONSULTING

39 GROBLER STREET
POLOKWANE 0699
P.O. BOX 6196
POLOKWANE NORTH
0750
TEL: (015) 291 4065

0750
TEL: (015) 291 4065
FAX: (015) 291 4043
website: www.muteo.co.za


PROJECT APPR.	DATE	BY	SIGNATURE	SCAI	LE	
DESIGNED	10 OCT 2025	S.D				
CHECKED	10 OCT 2025	N.M		DO NOT IF IN DOU		
DRAWN	10 OCT 2025	S.D		n nvboc	BITISK.	
PROJECT MNG.				PROJEC'	Γ No.	
APPROVED				FWPQ 27 OF	2022-2026	
CLIENT				DRG SIZE	A1	


ALL DIMENSION IN mm UNLESS SPECIFIED OTHERWIS	šΕ


ALL L	DIMENSION IN mm UNLESS SPECIFIED OTHERWISE
TITLE	RETROFITTING OF 7 SEWER PUMP STATIONS,
INS	STALLATION OF INLINE GRINDERS AND REPAIRS TO
	WWTW PLANT IN HOOPSTAD AND TIKWANA


OUTLET CHAMBER STRUCTURE

FWPQ 27 OF 20222-26/CIVIL/CHAMBER/01









SECTION D-D ON WALL A (WALL B TO OPPOSITE HAND)

BENDING SCHEDULE

BAR TYPE	BAR MARK	No. OF MEMBERS	No. IN EACH	TOTAL NUMBER	TOTAL LENGTH OF EACH BAR(mm)		SHAPE)CODE	А	В	С
Y10	01	1	17	17	1900	20.00	35	1660		
Y10	02	1	3	3	1000	1.85	35	740		
Y10	03	1	6	6	500	1.85	35	240		
Y10	04	1	6	6	3500	12.96	35	3250		
Y10	05	1	3	3	2550	4.72	35	2300		
Y10	06	1	4	4	750	1.85	20	750		
Y10	07	1	11	1 1	3800	25.79	35	3550		
Y10	08	2	4	8	2850	14.07	54	140	900	
Y10	09	2	4	8	3750	18.51	38	140	900	
Y10	10	2	10	20	500	6.17	20	500		
Y10	11	1	20	20	2250	27.77	35	1960		
		•			TOTAL	135.54				

ISSUED FOR TENDER

REV	DATE	СНК	APP	DESCRIPTION	



CLIENT



MUTEO CONSULTING

39 GROBLER STREET
POLOKWANE 0699
P.O. BOX 6196
POLOKWANE NORTH
0750
TEL: (015) 291 4065
FAX: (015) 291 4043

39 GROBLER STREET	PROJECT APPR.	DATE	BY	SIGNATURE	SCA	LE
POLOKWANE 0699	DESIGNED	10 OCT 2025	S.D			
P.O. BOX 6196	CHECKED	10 OCT 2025	N.M		DO NOT IF IN DOI	SCALE UBT ASK.
POLOKWANE NORTH 0750	DRAWN	10 OCT 2025	S.D		n n bo	OBI TISIK.
TEL: (015) 291 4065	PROJECT MNG.				PROJEC	T No.
FAX: (015) 291 4043	APPROVED				FWPQ 27 OF	2022-2026
website: www.muteo.co.za	CLIENT				DRG SIZE	A1


ALL DIMENSION IN mm UNLESS SPECIFIED OTHERWISE RETROFITTING OF 7 SEWER PUMP STATIONS, INSTALLATION OF INLINE GRINDERS AND REPAIRS TO


OUTLET CHAMBER STRUCTURAL DETAILS


DRAWING No. FWPQ 27 OF 20222-26/CIVIL/CHAMBER/02 REV 0

WWTW PLANT IN HOOPSTAD AND TIKWANA














TYPICAL FOOTING SECTION - F1 SCALE 1:20














ISSUED FOR TENDER

					1
					-
					4
REV	DATE	CHK	APP	DESCRIPTION	





MUTEO CONSULTING


39 GROBLER STREET
POLOKWANE 0699
P.O. BOX 6196
POLOKWANE NORTH
0750
TEL: (015) 291 4065
FAX: (015) 291 4043


	39 GROBLER STREET	PROJECT APPR.	DATE	BY	SIGNATURE	SCAI	LE	
	POLOKWANE 0699	DESIGNED	10 OCT 2025	S.D				TI
P.O. BOX 6196		CHECKED	10 OCT 2025	N.M		DO NOT IF IN DOU		
	POLOKWANE NORTH 0750	DRAWN	10 OCT 2025	S.D		— II II DOOD! A		
	TEL: (015) 291 4065	PROJECT MNG.				PROJEC'	Γ No.	
	FAX: (015) 291 4043	APPROVED				FWPQ 27 OF	2022-2026	
	website: www.muteo.co.za	CLIENT				DRG SIZE	A1	D

ALL D	ALL DIMENSION IN mm UNLESS SPECIFIED OTHERWISE								
TITLE	RETROFITTING OF 7 SEWER PUMP STATIONS,								
INS	STALLATION OF INLINE GRINDERS AND REPAIRS T	-C							
	WWTW PLANT IN HOOPSTAD AND TIKWANA								

GANTRY STRUCTURAL LAYOUT & DETAILS DRAWING No.

FWPQ 27 OF 20222-26/CIVIL/STRUCTURAL/01






NOTES:


BACK FILLING OF TRENCH EXCAVATIONS

- 1. SELECTED BACK FILL CLASS I IMPLIES APPROVED SELECTED MATERIAL FROM TRENCH EXCAVATION, FREE FROM STONES AND WITH A OPTIMUM MOISTURE CONTENT.
- 2. SELECTED BACK FILL CLASS II IMPLIES SELECTED BACK FILL FROM THE TRENCH EXCAVATION, WHICH SHALL NOT CONTAIN ANY STONES LARGER THAN 150mm Ø.
- 3. CLASS "A" BEDDING/ ENCASING CONCRETE BETWEEN JOINTS SHALL BE CARRIED OUT IN ONE CONTINUOUS OPERATION USING CLASS 20/19 CONCRETE.
- 4. FLEXIBLE JOINTS MUST BE PROVIDED, AT EACH PIPE JOINT IN A CLASS "A" CONCRETE BEDDING/ENCASING, WITH A 12mm THICK SOFT BOARD PLACED VERTICALLY FOR THE ENTIRE CONCRETE AREA. PIPE JOINTS MUST BE SEALED WITH WET CLAY TO PREVENT SLUSH FROM PENETRATING THE JOINT.
- 5. EXCEPT FOR THE 300mm BACK FILL ON TOP OF THE PIPE THE BALANCE OF THE TRENCH MAY BE BACK FILLED WHEN THE CLASS "A" BEDDING/ENCASING HAS OBTAINED A COMPRESSIVE STRENGTH OF 15 MPa.
- 6. APPROVED SELECTED GRAVEL MATERIAL WITH A PI NOT EXCEEDING 6, FREE FROM STONES EXCEEDING 20mm, ORGANIC MATTER AND LUMPS OF CLAY.


ISSUED FOR TENDER

		CLIENT	MUTEO CONSULTING	39 GROBLER STREET	PROJECT APPR.	DATE	BY	SIGNATURE	SCALE	ALL DIMENSION IN mm UNLESS SPECIFIED OTHERWISE	
		A (POLOKWANE 0699	DESIGNED 10	0 OCT 2025	S.D			TITLE DETROCITTING OF 7 SEWED DUMP STATIONS	
				P.O. BOX 6196				N.M		DO NOT SCALE IF IN DOUBT ASK.	RETROFITTING OF 7 SEWER PUMP STATIONS, INSTALLATION OF INLINE GRINDERS AND REPAIRS TO
				POLOKWANE NORTH	DRAWN 10	0 OCT 2025	S.D		IF IN DOOD! ASK.	WWTW PLANT IN HOOPSTAD AND TIKWANA	
			CONSULTING	TEL: (015) 291 4065	PROJECT MNG.				PROJECT No.	SEWER INLET MANHOLE DETAILS	
		ISWEL OPELE		ISWEL OPELE	FAX: (015) 291 4043	APPROVED				FWPQ 27 OF 2022-2026	
REV DATE	CHK APP DESCRIPTION			website: www.muteo.co.za	CLIENT				DRG SIZE A1	DRAWING No. FWPQ 27 OF 20222-26/CIVIL/SEWER/01 REV 0	





ISSUED FOR TENDER





CLIENT




	APPROVED BY	M.M	Project
	DESIGNED BY	A.N	
	DRAWN BY	E.M	TSWELOPELE SEWER PUMP
	DATE	2025.10.31	STATION REFURBISHMENTS
	ECSA	201901008	
	SIGNATURE		
	SIGNATURE		SCALE As indicated SHEET SIZE A0
			DRAWING NUMBER
			PR00545_1/ MF-400-PS1

PR00545_1/ ME-400-PS1


Descipline MECHANICAL ENGINEERING .WER PUMP Description


> **SEWER PUMP STATION 1 DETAIL LAYOUT**




SLOPE FLOOR SURFACE

STRUCTURAL ENG.








Legend


HDPE Pipe DIscharge Line





PUMP STATION 2 (PS2) KEY PLAN

ISSUED FOR TENDER



3D PUMP STATION 2



CLIENT

-CONCRETE PUMP SUMP

STRUCTURE

-PUMP DUCKFOOT



APPROVED BY	M.M	Project			
DESIGNED BY	A.N				
DRAWN BY	E.M	TSWELOPELE SEWER P			
DATE	2025.10.31	STATION I	REFUR	BISHN	JENT
ECSA	201901008				
SIGNATURE					
SIGNATURE		SCALE	As indicated	SHEET SIZE	A0


DRAWING NUMBER


PR00545_1/ ME-401-PS2


MECHANICAL ENGINEERING


Descipline

SEWER PUMP STATION 2 DETAIL LAYOUT









HDPE Pipe DIscharge Line

HDPE Pipe By-Pass Line

HDPE Pipe Drain

HDPE Pipe Suction Line

RECTIFIED AT THE CONTRACTORS OWN COST.

* FLAT FACED FLANGES TO BE USED

4. PROTECTION CODES:

FP: FACTORY PROTECTION.

BG: BRILLIANT GREEN

DIFFERENTLY.

6. VALVES:

PROJECTION,

7. ABBREVIATIONS: AC - ASBESTOS CEMENT

CI - CAST IRON

FA - FLANGE ADAPTOR

SS - STAINLESS STEEL

WASHERS AND A 3mm

GALVANISED MS

THREADS, WHEN THE ASSEMBLIES

ARE FULLY TIGHTENED, SHALL BE USED.

FC - FLEXIBLE COUPLING GS - GALVANISED STEEL MS - MILD STEEL

1. CONTRACTOR IS TO SUBMIT THEIR SHOP DRAWINGS BASED ON THESE DESIGN DRAWINGS FOR APPROVAL BY THE ENGINEER PRIOR TO ANY PIPE WORK BEING

ANY PIPES ORDERED WITHOUT THE APPROVAL OF THE ENGINEER WILL BE

EACH ITEM IS TO BE CLEARLY MARKED ACCORDING TO THE NUMBERS GIVEN

3. ALL FLANGES ARE TO BE IN ACCORDANCE WITH SABS 1123, UNLESS STATED

TESTING PRESSURE - 1,5 x WORKING PRESSURE, FOR ALL FLANGES, COUPLING

GASKETS FOR PRESSURE RATINGS UP TO AND INCLUDING 2 500 kPa, SHALL BE

GASKETS FOR PRESSURE RATINGS UP TO AND INCLUDING 1 600 kPa SHALL BE 3

EP: ALL SURFACES SHALL BE BLAST CLEANED TO SA 2½ AND TO BE COATED

5. MATERIAL: GRADE C CARBON STEEL AS PRESCRIBED IN SANS 719, ALL PIPE

ALL GEARBOX POSITIONS TO BE AS FOR RIGHT HAND VALVE, RIGHT HAND

RESILIENT SEAL GATE: IN ACCORDANCE TO SABS 664. RIGHT HAND LOCKING.

BE SUPPLIED WITH THE NECESSARY PRESSURE REDUCERS AND / OR GEARS

ARE TO BE EQUIPPED WITH HAND WHEELS, UNLESS OTHERWISE STATED.

ALL VALVES TO BE FLANGED AND RATED PN10 MINIMUM.

UNLESS STATED DIFFERENTLY ON DRAWINGS OR ITEM LIST.

FUNCTIONING AT THE SPECIFIED UNBALANCED PRESSURE.

BOLT LENGTHS SHALL MAKE ALLOWANCE FOR TWO x 3mm THICK

THICK GASKET SHALL BE PROVIDED FOR EACH PIPE ITEM AS LISTED.

BOLTS THAT PROTRUDE BEYOND THE NUT BY A MINIMUM OF TWO

A WASHER SHALL BE FITTED UNDER ALL BOLT/SCREW HEADS AND

9. PROVIDE APPROPRIATE BOLT UNITS (CONSISTING OF A STANDARD LENGTH

ALL BOLTS, NUTS AND WASHERS ON PIPE WORK TO BE HOT DIP

AND FOR FLANGE ADAPTOR TO FLANGE INSTALLATIONS.

CUT FROM MATERIAL MANUFACTURED TO THE SPECIFICATION BEP J59, OR

TABLE SANS1123

1 000/3

1 600/3

2 500/3

4 000/3

WORKING PRESSURE

1000kPa

1600kPa

ISSUED FOR TENDER

DRAWING ISSUED FOR TENDER 1 31.10.2025 EM ISSUED FOR TENDER Rev Date by COPY RIGHT RESERVED Revision Schedule

3D PUMP STATION 3



CLIENT



GAUTENG, SOUTH AFRICA

APPROVED BY	M.M	Project
DESIGNED BY	A.N	
DRAWN BY	E.M	TSWELOPE
DATE	2025.10.31	STATION RE
ECSA	201901008	
SIGNATURE	_	
4	Tral -	SCALE As
All	7142	DRAWING NUMBER
7-4	Manager and Marie or	PR00545 1/ ME-402-PS3

TYPICAL PUMP STATION

SCHEMATIC DIAGRAM

N.T.S

LEGEND DUCKFOOT SUBMERSIBLE PUMP


MANUAL GATE VALVE CHECK VALVE SEWER PIPE CLEANING BY-PASS LINE FLOW DIRECTION N.O: NORMALLY OPEN N.C: NORMALLY CLOSED


> ELE SEWER PUMP Description REFURBISHMENTS


s indicated SHEET SIZE A0 PR00545_1/ ME-402-PS3


Descipline MECHANICAL ENGINEERING

> **SEWER PUMP STATION 3 DETAIL LAYOUT**











Legend

HDPE Pipe DIscharge Line





PUMP STATION 5 (PS5) KEY PLAN

ISSUED FOR TENDER

				DRAWING ISSUED FOR			
1	31.10.2025	EM	ISSUED FOR TENDER	TENDER			
Rev	Date	by	Description				
	Revision Schedule			COPY RIGHT RESERVED			

3D PUMP STATION 5



CLIENT




		APPR
	TTO	DESI
ИU	TEO	DRAV
		DATE
CON	SULTING	ECSA
:	TEL: 012 664 6577 FAX: 012 664 4875 Email: mail@muteo.co.za Website: www.muteo.co.za	SIGN


APPROVED BY	M.M	Project			
DESIGNED BY	A.N				
DRAWN BY	E.M	TSWELOP	ELE SE	EWER	PUMP
DATE	2025.10.31	STATION	REFUR	BISHN	MENTS
ECSA	201901008				
CIONATUDE					
SIGNATURE		SCALE	As indicated	QUEET QIZE	40


PR00545_1/ ME-403-PS5

Descipline MECHANICAL ENGINEERING Description

> **SEWER PUMP STATION 5 DETAIL LAYOUT**







DRAWING ISSUED FOR

COPY RIGHT RESERVED

TENDER

1 31.10.2025 EM ISSUED FOR TENDER

Revision Schedule


Rev Date by






APPROVED BY	M.M	Project			
DESIGNED BY	A.N				
DRAWN BY	E.M	TSWELOP	ELE SE	WER	PUMF
DATE	2025.10.31	STATION I	REFUR	BISHN	JENTS
ECSA	201901008	_			
SIGNATURE					

MANUAL GATE VALVE CHECK VALVE SEWER PIPE CLEANING BY-PASS LINE FLOW DIRECTION N.O: NORMALLY OPEN N.C: NORMALLY CLOSED TYPICAL PUMP STATION PUMP STATION HOOPSTAD (PSH) KEY PLAN SCHEMATIC DIAGRAM N.T.S ISSUED FOR TENDER Descipline MECHANICAL ENGINEERING Description SEWER PUMP STATION HOOPSTAD DETAIL LAYOUT SCALE | As indicated | SHEET SIZE | A0 PR00545_1/ ME-404-PSH



SCHEDULE OF ITEMS



DRAWINGS FOR APPROVAL BY THE ENGINEER PRIOR TO ANY PIPE WORK BEING ANY PIPES ORDERED WITHOUT THE APPROVAL OF THE ENGINEER WILL BE

EACH ITEM IS TO BE CLEARLY MARKED ACCORDING TO THE NUMBERS GIVEN

RECTIFIED AT THE CONTRACTORS OWN COST.

CLASS	WORKING PRESSURE	TABLE SANS1123
6	600kPa	
10	1000kPa	1 000/3
16	1600kPa	1 600/3
25	2500kPa	2 500/3

3. ALL FLANGES ARE TO BE IN ACCORDANCE WITH SABS 1123, UNLESS STATED

* FLAT FACED FLANGES TO BE USED TESTING PRESSURE - 1,5 x WORKING PRESSURE, FOR ALL FLANGES, COUPLING

4 000/3

AS WELL AS PUDDLE FLANGES. GASKETS FOR PRESSURE RATINGS UP TO AND INCLUDING 2 500 kPa, SHALL BE CUT FROM MATERIAL MANUFACTURED TO THE SPECIFICATION BEP J59, OR

GASKETS FOR PRESSURE RATINGS ABOVE 2 500 kPa, UP TO AND INCLUDING 4 000 kPA, SHALL BE CUT FROM MATERIAL MANUFACTURED TO THE SPECIFICATION B.S. 2815 B, OR EQUIVALENT. GASKETS FOR PRESSURE RATINGS UP TO AND INCLUDING 1 600 kPa SHALL BE 3 mm THICK CAF FULL FACE GASKETS. GASKETS FOR PRESSURE RATINGS ABOVE 1 600 kPa SHALL BE 3 mm THICK CAF RING GASKETS.

EP: ALL SURFACES SHALL BE BLAST CLEANED TO SA 2½ AND TO BE COATED WITH 3 LAYERS OF EPOXY RESIN TO GIVE A MIN. DRY FILM THICKNESS OF

FP: FACTORY PROTECTION.

4. PROTECTION CODES:

5. MATERIAL: GRADE C CARBON STEEL AS PRESCRIBED IN SANS 719, ALL PIPE ITEMS TO BE 4,5mm MINIMUM WALL THICKNESS UNLESS INDICATED DIFFERENTLY. 6 VALVES:

ALL VALVES TO BE FLANGED AND RATED PN10 MINIMUM. ALL GEARBOX POSITIONS TO BE AS FOR RIGHT HAND VALVE, RIGHT HAND PROJECTION,

UNLESS STATED DIFFERENTLY ON DRAWINGS OR ITEM LIST. RESILIENT SEAL GATE: IN ACCORDANCE TO SABS 664. RIGHT HAND LOCKING. ARE TO BE EQUIPPED WITH HAND WHEELS, UNLESS OTHERWISE STATED. BE SUPPLIED WITH THE NECESSARY PRESSURE REDUCERS AND / OR GEARS

FUNCTIONING AT THE SPECIFIED UNBALANCED PRESSURE. 7. ABBREVIATIONS: AC - ASBESTOS CEMENT CI - CAST IRON

FC - FLEXIBLE COUPLING GS - GALVANISED STEEL MS - MILD STEEL SS - STAINLESS STEEL

FA - FLANGE ADAPTOR

BOLT LENGTHS SHALL MAKE ALLOWANCE FOR TWO x 3mm THICK WASHERS AND A 3mm

THICK GASKET SHALL BE PROVIDED FOR EACH PIPE ITEM AS LISTED. BOLTS THAT PROTRUDE BEYOND THE NUT BY A MINIMUM OF TWO THREADS, WHEN THE ASSEMBLIES ARE FULLY TIGHTENED, SHALL BE USED.

A WASHER SHALL BE FITTED UNDER ALL BOLT/SCREW HEADS AND

ALL BOLTS, NUTS AND WASHERS ON PIPE WORK TO BE HOT DIP GALVANISED MS

9. PROVIDE APPROPRIATE BOLT UNITS (CONSISTING OF A STANDARD LENGTH BOLT, NUT AND TWO WASHERS) AND RING GASKET FOR EACH SET OF FLANGES AND FOR FLANGE ADAPTOR TO FLANGE INSTALLATIONS.

10. SUPPORTS AND ANCHOR SUPPORTS


SUPPORTS OR ANCHOR SUPPORTS ARE REQUIRED FOR CERTAIN PIPE ITEMS. TENDERER TO SUBMIT DETAILS OF PROPOSED SUPPORTS AND ANCHORS AS PART OF WORKSHOP DRAWINGS REQUIRED FOR EACH PIPE ITEM, IF NOT DETAILED. NO SITE WELDING SHALL BE PERMITTED ON SUPPORTS OR ANCHORS, WHICH COULD DAMAGE FACTORY APPLIED CORROSION PROTECTION. ALL ANCHOR BOLTS TO BE 16 mm Ø MINIMUM of 316 STAINLESS STEEL.


LAYOUTS DETAILED INCLUDE FOR A 3mm THICK GASKET.


12. PIPE ITEM DIMENSIONS ON DRAWINGS NEED TO BE VERIFIED BY THE CONTRACTOR ON SITE PRIOR TO THE MANUFACTURE OF ANY ITEMS. PIPE COATING AND LINING NOTES:


1. COATING TO BE A RIGID POLYURETHANE WITH A MINIMUM THICKNESS OF 2000


2. LINING IS A SOLVENT FREE EPOXY WITH A MINIMUM THICKNESS OF 600MICRONS






















SECTIONK-K

SCALE1:40





APPROVED BY	M.M	Project	Project			D
DESIGNED BY	A.N					
DRAWN BY	E.M	TSWELOP	TSWELOPELE SEWER PUMP STATION REFURBISHMENTS			
DATE	2025.10.31	STATION F				
ECSA	201901008					
SIGNATURE						
	1	SCALE	As indicated	SHEET SIZE	A0	
Arthur		DRAWING NUMBER	DRAWING NUMBER			
•	7107192	PR00545_1_ME_803_WTV	PR00545_1-MF-803-WTWW			

PR00545_1-ME-803-WTWW

MECHANICAL ENGINEERING Description

ISSUED FOR TENDER

FRONT RAKE SCREEN 12mm GENERAL INSTALLATION